



Powering of FRIB

POCPA3 Workshop Hamburg, Germany

May 22, 2012

Kent Holland

Power Supply Staff Engineer
MSU NSCL / FRIB
640 S. Shaw, Room 1300G
East Lansing, MI 48824
Phone: 517-908-7348
Fax: 517-908-7126

MICHIGAN STATE

UNIVERSITY



U.S. DEPARTMENT OF
ENERGY

Office of
Science

Outline

- National Superconducting Cyclotron Laboratory (NSCL) history
- Facility for Rare Isotope Beams (FRIB) history
- FRIB Overview
- Integration
- RF Systems Overview
- PS Systems Overview
- Path forward

NSCL History


- **1954:** MSU receives funding to begin planning for a cyclotron-based nuclear research facility.
- **1961:** First National Science Foundation grant to build first 40 MeV cyclotron.
- **1965:** Because the device outperformed design, the 50 MeV, K-50 cyclotron is completed.
- **1975:** Funds for the superconducting magnet for the K-500 are awarded.
- **1977:** The superconducting magnet is completed and MSU is awarded the contract to build the cyclotron.
- **1981:** At 3:00 p.m. on Saturday, November 21, 1981, **the world's first superconducting cyclotron** was turned on.
- **1984:** The magnet for the second superconducting cyclotron is turned on.
- **1988:** The new cyclotron exceeds expectations and the K-800 is completed and renamed the K-1200.
- **1998:** Plans to couple the K-500 and K-1200 receive funding.
- **2000:** On October 1, the first beam of ions from the Coupled Cyclotron Facility is created.
- **2009:** Began construction of ReA3. ReA3 will provide world-unique low energy rare isotope beams produced by stopping fast, separated rare isotopes in a gas-stopper, and then reaccelerating them in a Linear Accelerator.

FRIB History

- **2004:** The Department of Energy puts out a call for proposals for a \$1 billion projected dubbed the Rare Isotope Accelerator (RIA). However, the project is shelved.
- **2007:** The Department of Energy puts out a new, scaled-down call for proposals for the Facility for Rare Isotope Beams (FRIB).
- **2008:** On December 11, the Department of Energy announced that MSU will host the new FRIB project.
- **2010 and beyond:** Plans for the \$615 million FRIB facility continue to move forward. Current estimations predict construction to begin in 2013 with a completion date in 2020, and a potential early completion date in 2018.
- **2012** Conventional facilities have completed final design, technical groups starting final design May, 2012.
- <http://www.nscl.msu.edu/>
- <http://www.nscl.msu.edu/interactivemap.html>
- <http://www.frib.msu.edu/>


FRIB overview

Site Layout




FRIB overview

Facility Layout



FRIB overview

Facility Layout




FRIB overview

Future Upgrade Opportunities

Space available for various upgrade options


- Higher energy
- ISOL targets
- Light ion injector (17 or 200 MeV/u)
- Multi-user simultaneous operation

Tunnel penetration locations identified in facility design




Integration: Service Building and Linac Tunnel

- Baseline 767 racks for Accelerator Systems and Experimental Systems technical systems (RF amplifiers, power supplies, vacuum controls, diagnostics, etc.)
 - Connect to tunnel lattice elements
 - Determine overall loads (water, power, air cooling) and distribution




20 feet of concrete & soil



Integration: Service Building and Linac Tunnel

Lattice Element and Power Supply counts in Parameter List


Rack layout



Total Power Consumption

Rack installed?	Yes
120Vac	20A 2
120V Backup	20A 0
120V Clean	20A 0
208Vac 1P	30A 0
208Vac 1P	50A 0
208Vac 3P	20A 0
208Vac 3P	30A 1
480Vac 3P	20A 0
480Vac 3P	30A 2
480Vac 3P	40A 2
480Vac 3P	60A 2
480Vac 3P	80A 0
LCVW	0 gpm
Fans	2 825 CFM
HVAC	2.8 Tons

Conduits





Rack counts

C6SB Racks Overview						
	400MeV LINAC					
T.3	# Systems	# Racks ea	# Racks	# Racks	space reserved (# PS Racks)	sq ft
Linac Segment 1						
beta = 0.041 QWR 4.2	3	7	21	21		
beta = 0.085 QWR 8.3	14	10	140	130		
beta = 0.285 HWR 2.0	1	6	6	6		
PS			2	4		
Diag			2	0		
Ctl			6	6		


→ = logical link

RF Systems Overview

- RF system provides the phase reference signal and regulates the cavity amplitude and phase, which accelerate the ions.
- Total of 337 RF systems



RF Systems Overview



New FRIB LLRF Controller



PS Systems Overview

- Power supplies (PS) are needed for FRIB ion sources, optical elements in the FRIB driver linac beam line, and in the FRIB experimental system
- PS provide regulated DC current to magnets which focus, and/or steer the ions.
- PS can be segregated into 3 PS family types
 - Room Temperature Magnet Power Supplies (RTM PS)
 - Superconducting Magnet Power Supplies (SCM PS)
 - High Voltage Power Supplies (HV PS)
- Many commercial off the shelf (COTS) PS are available, which will meet system requirements
- High reliability, stability, and availability of the FRIB PS systems with a reasonable price is a key for the success of the project.

PS Systems Overview

Parameter List

Linac Segment 1 Parameter List


Date 8/29/2011

Based on the FRIB_V12R4 lattice

T.3.06

WBS	Parameter	Qty or Type	Unit	Comments
	Segment One Length	103.097	m	
	Uranium Acceleration			
	Charge states (2)	33+/34+		
	Input Energy	0.5	MeV/u	
	Output Energy	16.6	MeV/u	
	Energy gain	16.1	MeV/u	
	Acceptance (Nominal)			
	Transverse (beam size/aperture)	60	%	24 mm max. beam size, 40 mm aperture
	Longitudinal	30	π .keV/u.ns	
T.3.06.02	Cavity & Cryomodule Configuration			
	$\lambda/4$, β_{opt} 0.041 (LS1_CA)			
	Number of cryomodules	3		Based on 500 keV/u RFQ
	Number of cavities/cryomodule	4		
	Number of solenoids/cryomodule	2		
	Number of cavities	12		
	Number of gate valves	6		2 per cryomodule
	Number of solenoids (type S1)	6		Superconducting with integrated steerers
	Dipole correctors	12		One in each plane per solenoid
	Cavity Data			
	RF Frequency	80.5	MHz	
	Flange to flange length	0.1755	m	
	Aperture	30	mm	
	Epk (numerical calculation)	30	MV/m	peak surface electric field
	Bpk (numerical calculation)	53	mT	peak surface magnetic field
	Va	0.81	MV	accelerating voltage design goal (includes transit time factor, at $\beta = \beta_{opt}$)
	R/Q (numerical calculation)	433	Ω	shunt impedance/Q (linac definition)
	G (numerical calculation)	15	Ω	geometry factor
	U	3.0	J	Average stored energy
	T	2	K	operating temperature

Type of PS and qty defined



PS Systems Overview

Example Power Supply Requirements for Electrostatic / HV PS

Name	PSED1a
Parameter list description	RT E-Dipole ED1 (+)
V required maximum (kilovolts)	20
I required maximum (Amps)	0.006
Field contingency % (included in V/I requirements)	30%
Range (Volts)	6 to 15
Polarity	Positive
Voltage stability – long term - % of Full Scale	±0.01%
Voltage ripple – short term - % of Full Scale (rms)	0.01%
Voltage set-point accuracy/precision - % of Full Scale	0.1% of rated +0.5% of setting
Voltage read-back accuracy/precision - % of Full Scale	0.1% of rated +0.5% of setting
Current read-back accuracy/precision - % of Full Scale	0.1% of rated +0.5% of setting
Voltage set-point resolution - % of Full Scale	0.05%
Voltage read-back resolution - % of Full Scale	0.05%
Current read-back resolution - % of Full Scale	0.05%
Voltage repeatability/reproducibility	±0.01%
Number of quadrants	1
Temperature Coefficient %/°C of of Full Scale Current	0.01%
Sampling rate Hz (note 3) (needs verification)	3-10
Magnet maximum voltage rating	
Magnet capacitance	200pF
Lead Capactance (100ft 30pF/ft)	3nF

PS Systems Overview


Value Engineering Performed

- RT correction magnet PS, eliminated the need for an external reversing switch, and reduced PS power, greatly reducing PS costs
- Q1 magnet/PS optimization reduced cost by ~\$250k, PSQ1 average power was reduced to ~5 kW from 10 kW. Details shown on next slide.
- Front End solenoid power supplies scaled with power. Similar to Q1, although due to the low quantity the cost reductions were much less.
- Request for procurement (RFP) in process for SC magnet PS
- High PS efficiency and power factor are key considerations in choosing suppliers
- Provisions made to allow future capability enhancements
 - Rack space, conduits, utilities planned for upgrade from 200 MeV to 400 MeV
 - Rack space, conduits, utilities planned for upgrade to Cable in Conduit (CICC) magnets in hot cell

PS Systems Overview

Q1 Power Supplies Optimized by Location


- Q1 magnet/PS optimization reduced cost by ~\$250k, PSQ1 average power was reduced to ~5 kW from 10 kW



PS Systems Overview

Cost Basis, SC Magnet PS

- **SCM PS Basis of Estimates (BOE) costs are based on previous experience at NSCL to build, install, and test**
 - All material costs are captured in Bill of Materials (BOM)
 - Labor estimates are based on previous workorders to build, install, and test SCM PS at NSCL
 - » Built 2 identical 10V 250A SCM PS for the cyclotron stopper
 - » Built 1 identical 10V 750A “Modular” SCM PS for a spare S800 dipole PS
 - » Built 50+ identical SCM PS for ReA3 and N4 vault reconfiguration, 20V 25A, 10V 40A, 10V 125A, 10V 250A.
 - » Built 4 prototype “Modular” SCM PS that have been in service since 2007
 - » 100+ SCM PS built at NSCL in 2001 in service
 - » 20+ SCM PS built at NSCL in 1990 in service
 - Supporting Items/systems captured in BOE
 - » Network connection
 - » Digital I/O
 - » AC power requirement specified
 - » LCW connection
 - Usage dependant costs captured in BOE
 - » DC lead – based on length



PS Systems Overview

Cost Basis, RT Magnet PS & HV PS

- RTM PS, and HV PS BOE costs are based on recent quotes from Ametek, TDK-Lambda, Glassman HV, etc.
 - Labor estimates are based on previous workorders to install RTM PS at NSCL
 - Supporting Items/systems captured in BOE
 - » Network connection
 - » Digital I/O
 - » AC power requirement specified
 - Usage dependant costs captured in BOE
 - » DC lead – based on length of path between PS and magnet



PS Systems Overview

Schedule Basis

- Installation time allowance, from BOEs, is 2 days per power supply, including final testing, plus DC lead time allowance depending on quantity, type, and length of leads
- Sufficient temporary labor will be available, and good instruction and oversight will be provided
- Install and test power supplies initially independent of magnet schedule
- Pull cables from racks to equipment locations (relatively) independent of status of equipment at each end

Path Forward

- Final Design, completed by Nov, 2013
 - Detailed acquisition and installation plans
 - Detailed acceptance and verification plans
 - RFP's for RT magnet PS and HV PS
 - SCM PS make vs. buy decision, manufacturing plan if make chosen
 - Finalize integration details
 - » Machine protection system
 - » Personnel protection system
 - » Grounding
 - » Cable routing
- Technical equipment installation beginning 2015
- Commissioning beginning 2018
- Early completion 2020