

RF upgrade program in LHC injectors and LHC machine

Erk Jensen, on behalf of BE-RF

Many thanks to M. E. Angoletta, O. Brunner, R. Calaga, E. Ciapala, H. Damerou, W. Höfle, E. Montesinos, M. Paoluzzi, C. Rossi, E. Shaposhnikova, J. Tückmantel
and all those I forgot to mention

New rough draft 10 year plan

2010			2011			2012			2013			2014			2015			2016																																																	
M	J	J	A	S	O	N	D	J	F	M	A	M	J	J	A	S	O	N	D	J	F	M	A	M	J	J	A	S	O	N	D	J	F	M	A	M	J	J	A	S	O	N	D	J	F	M	A	M	J	J	A	S	O	N	D	J	F	M	A	M	J	J	A	S	O	N	D



- Machine: Splice Consolidation & Collimation in IR3
- ALICE - detector completion
- ATLAS - Consolidation and new forward beam pipes
- CMS - FWD muons upgrade + Consolidation & infrastructure
- LHCb - consolidations
- ?Cryo-collimation point

X-Mas maintenance



SPS upgrade
? SPS - LINAC4 connection & ? PSB energy upgrade

2016			2017			2018			2019			2020			2021																																												
J	F	M	A	M	J	J	A	S	O	N	D	J	F	M	A	M	J	J	A	S	O	N	D	J	F	M	A	M	J	J	A	S	O	N	D	J	F	M	A	M	J	J	A	S	O	N	D	J	F	M	A	M	J	J	A	S	O	N	D



- Machine: Collimation & prepare for crab cavities & RF cryo system
- ATLAS: new pixel detect. - detect. for ultimate luminosity.
- ALICE - Inner vertex system
- CMS - New Pixel. New HCAL Photodetectors. Completion of FWD muons upgrade
- LHCb - full trigger upgrade, new vertex detector etc.

X-Mas maintenance

X-mas maintenance

X-mas maintenance



2022

LS3

Installation of HL-LHC hardware
Installation of LHeC
Preparation for HE-LHC

General


Some maintenance work could not be done during the relatively short winter shutdowns and was postponed to LS1. I quote E. Montesinos:

“...very important maintenance program of the injector systems during LS1 due to lack of maintenance these last years. ... e.g. we fixed some issues while repairing the Siemens system, **it shows we are close to the limits (5-6 near important accidents*) last year, avoided by careful survey of the team)**. ... we will have to do lot in order to have all our systems ready for a new 3 to 4 years run with only few technical stops”.

In the following, I'll mention the major RF upgrade and consolidation activities – but the list is not exhaustive.


*) example: cf. spare slides

Linac 4



M. Vretenar, F. Gerig, C. Rossi, ...

Linac 4 timeline



M. Vretenar

PSB LLRF upgrade

M. E. Angoletta, A. Blas, A. Findlay, J. Molendijk, ...



FMC carrier: front&side views




RTM



VXS Switch: front&side views



MDDS FMC



ADC FMC: front&side views



SDDS FMC

PSB LLRF upgrade: planning

- **2011:** Beam tests with prototype hardware.
- **2012:** Beam tests: prototype + new hardware (PSB ring 4), support Finemet® prototype.
- **2013:** H/w series production for PSB
- **2014:** Full deployment of new PSB LLRF (4 rings + ring 0), support Finemet® system (full 13 cells, 8 kV)
- **2015-16:** Commissioning, prepare for injection from Linac 4

M. E. Angoletta, A. Blas, A. Findlay, J. Molendijk, ...

PSB RF power upgrade: systems today

Three systems are presently installed in the machine:

C02

- Frequency range 0.6 (^{*}1.0) – 1.8 MHz
- Gap Voltage 8 kV
- Installed in sections 7L1 and 10L1

(Built 1996 for LHC)


C16

- Frequency range 6.0 – 16 MHz
- Gap Voltage 6 kV
- Installed in section 5L1

C04

- Frequency range 1.2 (^{*}2.0) – 3.8 MHz
- Gap Voltage 8 kV
- Installed in section 13L1

(ex $h=5$ system, today the system limiting intensity)



*** Frequency with injection from LINAC4**

M. Paoluzzi

PSB RF power consolidation: the plan

In the tunnel:

- Keep all cavities and C02 and C16 final amplifiers,
- Redesign C04 finals to increase available power,
- Replace all irradiated cables.

On the surface:

- Modernize interlock (PLC),
- Modernize G64 (!) controls interface,
- Move AVC & tuning loops into new digital LLRF,
- Implement new protections,
- Replace power supplies (anode and grid bias),
- Install new filament power stabilizers,
- Replace tuning supplies.

M. Paoluzzi

PSB RF power upgrade: New wideband system


M. Paoluzzi

Advantages

- Single system to cover C02 and C04 frequency range.
- Modular system.
- Solid-state amplifier.
- Multi harmonic operation.
- No tuning.
- Substantial increase of installed RF voltage (up to 300%).
- Increased system reliability (hot back-up by on line spare cells).

Risks:

- New technology.
- New configuration
- Completely new design.
- Different beam compensation scheme.
- ...?



PS consolidation/upgrade

Activity	Schedule	Status
LLRF studies	05/2011 – 06/2012	active
Digital beam control	06/2014 – 06/2018	planned
1-Turn delay feedback	01/2012 – 12/2014	active
HLRF studies	05/2011 – 12/2012	active
10 MHz system renovation	01/2013 – 06/2018	planned
Longitudinal damper in the PS	01/2012 – 12/2015	planned
Coupled bunch feedback	01/2012 – 12/2015	planned
40/80 MHz feedback renovation	06/2012 – 06/2017	planned
Fast tuner for the 80 MHz system	01/2012 – 12/2015	active
C201 C206 consolidation	01/2013 – 03/2014	planned


C. Rossi, H. Damerou, M. Morvillo, C. Völlinger, ...

SPS 200 MHz power upgrade

E. Montesinos

- 2011 : 4 cavities

2 x 4 sections



2 x 5 sections



+ 3 spare sections



- 2018 : 6 cavities

4 x 3 sections



2 x 4 sections





+ 1 spare section



SPS 200 MHz power upgrade: Draft schedule

E. Montesinos





BPWA:
319 to 311


AEWB:
319 to 314

During LS1: not a lot possible

REVISIONS
NO. DATE BY REASON
1 2009-03-20 J. RAMILLON VERSION 2897
2 2009-05-11 J. RAMILLON VERSION 2898
3 2009-06-18 J. RAMILLON MISE A JOUR
4 1999-03-28 J. RAMILLON MISE A JOUR
5 1999-03-28 J. RAMILLON MISE A JOUR
6 1999-06-29 J. RAMILLON MISE A JOUR

IND.	DATE	NOM/NAME	ZONE	MODIFICATION
1	2009-03-20	J. RAMILLON		VERSION 2897
2	2009-05-11	J. RAMILLON		VERSION 2898
3	2009-06-18	J. RAMILLON		MISE A JOUR
4	1999-03-28	J. RAMILLON		MISE A JOUR
5	1999-03-28	J. RAMILLON		MISE A JOUR
6	1999-06-29	J. RAMILLON		MISE A JOUR

LAYOUT D'INSTALLATION MACHINES LEP-SPS LSS3 SCHEMATIC LAYOUT FROM OF 3140 TO OF 3210 LSS3 PLAN SCHEMATIC DE OF 3140 A OF 3210	ECHELLE SCALE 1:50	DESIGNA. DESIGNER J. RAMILLON	1994-03-30
RELEVEE BY PROJECT ENGINEER	AS BUILT	REVISION REVISOR F. GALLEZZI	2009-04-24
SAC -	SPLNINS053	APPROVE APPROVED S.P.S. L.NINS O.L.NINS O.S.3	2009-01-29
NO. 1	1	REPLACEMENT PLATES	



BA3

BB3

Extension

Transformer platform

SPS Transverse Damper, LS1


E. Montesinos, W. Höfle, US-LARP

- Re-shuffling of equipment (PUs) in SPS LSS3 to make space for new high bandwidth transverse feedback system (US-LARP collaboration) and in preparation of the increase of the number of cavities.
- Installation of new pick-ups, kickers and power amplifiers for high bandwidth transverse feedback system as they become available
- Limited upgrade/consolidation of transverse damper in BA2 of SPS; perhaps link this to clean-up of cabling in LSS2 (When exactly?)
- Installation of dedicated pick-ups for SPS transverse damper (now being discussed with BE-BI).

SPS 800 MHz upgrade


E. Montesinos, W. Höfle

- Important system to keep the beams stable, required at 1/5 nominal intensity!
- A new system, based on IOT amplifiers, will replace the old “Valvo” klystrons.
- Industry has supplied the 0-series – now under test
- Initial problems with the HVPS could be fixed.
- Now the system is under severe scrutiny for long term stability (endurance test)
- Observed: MTBF (trips) < 168 h (not good enough!);
- Probable culprit: EMC of controls – there is hope, but plan B (SS) is in preparation.
- LLRF upgrade – complete overhaul



SPS: COLDEX for Crab Cavity tests

- Crab Cavities are an important element of the LHC luminosity upgrade, HL-LHC.
- Before installing new, Compact Crab Cavities into the LHC, they have to be tested with beam in SPS.
- A suited area (with a by-pass) is Coldex (BA4); E. Metral is studying details.
- During LS1, it is planned to prepare this area for first CC beam tests in 2015 (cryogenics, general services)
- The existing cryoplant (TCF20) should be upgraded to 2 K liquefaction mode. Agreed in LHC-CC'11.
- A 1st test in LHC (P4) could be envisaged for 2017.



R. Calaga, E. Jensen, E. Metral, L. Tavian


LHC Transverse Damper (ADT)

E. Montesinos, W. Höfle

- Upgrade of cabling for LHC transverse damper and measures to decrease noise level of system in preparation of 7 TeV run.
- Potentially use a number of additional pick-ups for transverse damper for noise reduction (under discussion with BE-BI, cabling required and additional bottom pick-ups if go-ahead).
- Add HV switch in the power supplies to allow automatic Off line of faulty amplifier.
- Modify water flow monitors, Eletta (ex LEP, not reliable) to rotameter, to avoid false reading.
- Modify transport system of the amplifier, induces new positioning system under the kickers, this will ease interventions.
- Need some studies to fix 40 MHz resonance (not a problem for normal intensity, but survey in view of HL-LHC)...

LHC - on-going work now and during 2012

O. Brunner




- 4 more **klystrons** were upgraded with new collector; now 8/16 can run flat out (4 for each beam), the others remain limited to 50 kV, 8 A.
- All remaining **old LEP equipment** (driver amplifiers, focus power supplies, ...) were replaced by dedicated new units.
- All 4 **thyratrons** in the HV bunkers were checked and replaced or adjusted where necessary. A more modern and less delicate solution (solid state) was investigated and will be ready for test very soon.
- Approximately 100 **HV connectors** (connecting the modulators with the klystrons), some of which were problematic will be replaced when necessary during short TS's.
- The **arc detectors** were further developed and the new versions are now ready for testing – some can be scheduled during short TS's.
- The cavities were re-inspected (concern: delicate – could have been affected by cabling work!)

Account for > 50% of RF
caused beam dumps 2011

LHC – planned work LS1

O. Brunner

- Finish the **klystron collector upgrade** (8 remaining) – takes about 4 weeks/klystron.
- **Thyratron** upgrade or replacement SS (in shadow).
- Replacement of **cavity module M1B2**, which contains the “sick” cavity #3:
 - First: spare module test in SM18: July/August – expected to be OK.
 - If OK, continue preparation to change module.
 - If not OK, limitation of cavity #3 (1.2 MV instead of nominal 2 MV) would remain.
 - Major intervention (2 months – RUX45 roof, *virtually all cavity related trips in 2011 were in M1B2*)
- **Oil to be reconditioned** for all 4 HV bunkers – takes a few weeks/bunker (in shadow)



LHC Modulators: tetrode replacement

O. Brunner

- Each power converter feeds 4 klystrons; to individually control the power of each klystron, modulation anodes are used.
- The modulation anode voltage is controlled by a tetrode voltage divider (Thales TH 5186 SC).
- Old technology – Thales has announced the end of production of these tetrodes.
- A more modern solid state replacement solution is under study.



D. Valuch

Planned RF consolidation & upgrade

	2011	2012	2013	2014	2015	2016	2017	2018	2019
LHC			LS1: Splice Consolid., Collimation IR3					LS2: Collimation, CC preparation	
Injectors								L4 Connection, PSB -> 2 GeV	
LHC work									
LHC klystron collector ug.		4	8 remaining						
Thyratron ug/replacement		verify spare							
Replace module M1B2			Swap with spare						
ADT			ug. cabling, PU						
Linac 4	IS/Services Installation		Acc. Installation		Commissioning				
PSB RF Power upgrade									
Finemet 5-cell, 6L1R4	Design-install		Beam tests						
Full system 6L1R4			Build,install		Beam tests				
Full system all rings					Design, build, install				
PSB LLRF upgrade									
Prototype hardware	Beam tests								
New hardware		Beam tests R4		Series production		All rings			
Linac4 connection					interlock system, ring synchro				
SPS 200 MHz upgrade									
RF hardware		Studies/tendering		Hardware construction/test		Equipment installation			
Tunnel LSS3			AEWB, BPWA, WP&K					Rearrange cavities	
Building BA3/BB3		Authorizations		Construction		Services		Equipment installation	
LHC Crab Cavity									
Technology Validation	Technology validation		Technical Design				Construction		
Beam Tests					SPS		LHC IR4		
LHC P4 cryo upgrade				possible?					
Preparation (Coldex)		Prepare Coldex & CC cryo							
Injectors Consolidation									
PS C201-C206			Renovation						
PS C10		Renovation (1-turn delay FB, fast FB, driver, gap relays, long. damper, coupled bunch FB, ...)							
SPS TWC800			Renovation						
SPSTransverse Damper			ug. PU, kicker, PS						

RF Upgrade/Consolidation: Summary


- **Whatever could be done in short TS's was done, but some maintenance work had to be delayed to LS1!**
- **Upgrade plans include:**
 - PSB RF Power upgrade (Finemet® wide-band system)
 - PSB LLRF upgrade
 - SPS 200 MHz (cavity re-distribution, HB damper) and 800 MHz (IOT)
 - Prepare Coldex area (SPS) for Crab Cavity test
- **Consolidation plans include:**
 - PS 10 MHz Gap relays renovation
 - PS C201-C206 (200 MHz system)
 - PS C80 automatic tuning system implementation
 - LHC klystron boiler/collector upgrade (8 remaining)
 - Replace cavity module M1B2

THANK YOU VERY MUCH!

Spare Slides

Example of near important accident SPS TX4 HV transformer

- During a daily visit, U. Wehrle identified a problem.
- Reparation at the factory (in collaboration with TE-EPC)
- No incident (fire) thanks to a good anticipation method



Reminder: in 1997 the same HVPS exploded!

→ No SPS during six months !



E. Montesinos