

Experience with X-band at FERMI@Elettra FEL

***Gerardo D'Auria
Sincrotrone Trieste***

HG2012

KEK Tsukuba, 18-20 April 2012


- **The FERMI@Elettra FEL project**
- ***X-band linearizer***
- ***RF power source:***
 - *HV modulator*
 - *XL5 klystron*
 - *WG system*
- ***Preliminary beam tests***
- ***Future activities, opportunities and challenges***







ELETTRA_3rd Gen. light source

FERMI@Elettra is a single-pass FEL user facility, covering the wavelength range 100-4 nm

<i>FEL parameters</i>	<i>FEL 1</i>	<i>FEL 2</i>
<i>Output wavelength (nm, fundamental)</i>	<i>100-20</i>	<i>20-4</i>
<i>e-beam parameters</i>	<i>FEL 1</i>	<i>FEL 2</i>
<i>Energy (GeV)</i>	<i>1.2</i>	<i>1.5</i>
<i>Nominal charge (nC)</i>	<i>0.8</i>	
<i>Peak current (A)</i>	<i>900</i>	
<i>Bunch length, full width (fs)</i>	<i>700</i>	
<i>Slice normalized emittance (μmrad)</i>	≤ 1.0	
<i>Projected normal. emittance (μmrad)</i>	≤ 2.0	
<i>Uncorrelated energy spread, rms (keV)</i>	<i>150 KeV</i>	
<i>Total energy spread rms (%)</i>	<i>0.1</i>	
<i>Pulse to pulse energy stability rms (%)</i>	<i>0.1</i>	
<i>Timing jitter, rms (fs)</i>	≤ 150	
<i>Undulator parameters</i>	<i>FEL 1</i>	<i>FEL 2</i>
<i>Period length (mm)</i>	<i>55</i>	<i>35</i>
<i>Minimum gap (mm)</i>	<i>10</i>	
<i>K param. @20 nm, 1.2 GeV</i>	<i>1.7</i>	
<i>K param. @10 nm, 1.2 GeV</i>	<i>1.0</i>	
<i>K param. @4 nm, 1.5 GeV</i>		<i>1.0</i>






- *Modulator completion and tests* *July '11*
- *Klystron installation and tests (diode)* *Sept. '11*
- *Accelerating structure and WG installations* *Oct. '11*
- *XL5 activation and tests with RF* *Nov.-Dec. '11*
- *XL5 gain curves verification (with SLAC)* *Jan. '12*
- *RF power connection to accel. structure* *Jan. '12*
- *RF conditioning (structure and WG system)* *Febr. '12*
- *Preliminary beam tests* *Febr.-March '12*




**Classic scheme based on
PFN and Thyatron,
in house assembled**




XL5-1B Operation data

In diode mode at 50 Hz p.r.r.									With 300 nsec RF	
				Calorimetric measurements		V and I integrals				
Charging voltage	Anodic voltage	Anodic current	Micro perveance	Body power	Collector power	Collector power	Beam losses	Transm. effic.	Input RF power	Output RF power
$V_{fug}(KV)$	$V_k(KV)$	$I_k(A)$	(μP)	$B_p(W)$	$C_p(KW)$	$C_p(KW)$	$B_L(\%)$	$\eta(\%)$	$RF_{in}(W)$	$RF_{out}(MW)$
33.3	350	245	1.18	83	8.40	8.37	0.98	99.02	571	9.1
34.5	360	259	1.20	79	9.00	9.23	0.88	99.12	571	12.1
35.7	370	267	1.19	91	9.64	9.87	0.95	99.05	571	15.7
36.8	380	278	1.19	98	10.22	10.58	0.96	99.04	571	19.5
38.0	390	289	1.19	89	10.86	10.99	0.82	99.18	571	24.3
39.2	400	300	1.19	93	11.61	11.57	0.80	99.20	571	29.2
40.4	410	311	1.18	100	12.29	12.03	0.81	99.19	571	34.5
Filament hours (total)			2781							
HV hours			1373							
Diode			232							
RF (WG loads)			678							
RF (section and WG circuit)			463							



Calorimetric measurements





Structure vacuum bake-out at CO.ME.B. (Rome):

- ~ 350 hours
- oven pressure $\leq 10^{-8}$ torr
- $T = 650$ °C





Structure preparation




Structure at ST

To recover a flange rotation of one of the RF input port ...





We were obliged to make a deformation on one of the RF "C" WG feedings.


Both the "C" were re-calibrated after the deformation keeping $\leq 1^\circ$ phase unbalance




**Klystron
output flange**



**Pumping ports,
mode converters and
vacuum valve
assembly**





X-band plant with vacuum insulation




Remote adjustments in the transverse plane:


- $x, y \pm 0.5 \text{ mm}$;
- control of x, y , yaw and pitch;
- $50 \mu\text{m}$ fine step;
- $\leq 20 \mu\text{m}$, position reproducibility.

Measured ϵ_x and ϵ_y as we move the beam (6.5 ps_fwhm, 350 pC) along a line from ± 1 mm in x-y, through the X-band structure (passive, no RF)





X-band OFF






X-band gain ~10 MeV

Beam energy 341.2 MeV

Beam energy 321.8 MeV


Beam energy 301.9 MeV




**X-band set +20 MeV,
on crest (acceleration)
energy jitter ~500 keV (rms)**

**X-band at zero crossing,
no energy gain
energy jitter ~200 keV (rms)**

**X-band set -20 MeV,
@180 deg (deceleration)
energy jitter ~900 keV (rms)**




Without X-band




With X-band at -17.5 MeV


X-band @-19 MeV



mscrccd_bc01.03
@ 300 MeV



mscrccd_tls.03
@ 1.2 GeV



mscrccd_tls.03
@ 1.2 GeV

Short term program on the linearizer

- *Full structure characterization with the beam:*
 - *improve the RF field stability and the beam energy jitter*
 - *find the best operating point checking the compression factor, R_{56} ...*
 - *measure the beam kick due to the RF couplers*
 - *verify the wake fields effects*
- *Activation of the wake field monitors*

Future opportunities and challenges

- *Assembly of a second RF station*
- *Acceleration tests of very short bunch at energy > 1 GeV and beam quality measurements*

Thanks to:

All the members of linac group and the Fermi commissioning team, Sincrotrone Trieste.

G. Riddone, D. Gudkov, J. Shi, A. Samoshkin, M. Filippova, S. Lebet, CERN.

M. Dehler, M. Pedrozzi, PSI.

F. Peauger, CEA.

J. Eichner, A. Haase, D. Sprehn, A. Vlieks, SLAC.