



RF Summary

Michael S. Zisman
Center for Beam Physics
Accelerator & Fusion Research Division
Lawrence Berkeley National Laboratory

MICE Collaboration Meeting 32—RAL
February 11, 2012



Outline





- Introduction
- RF cavity status
- RF power issues
- RF control and monitoring
- Testing issues
- Schedule
- Summary



- RF system required for Steps 5 and 6
- Responsibility shared between two institutions
 - LBNL responsible for cavities [D. Li]
 - as part of RFCC modules
 - Daresbury Lab responsible for RF power sources and distribution system [A. Moss]
 - refurbishing power sources (originally from LBNL and CERN)
 - planning for installation of power systems in Hall
 - planning coax distribution system from power source to cavity
- Shared responsibility implies need for careful attention to interface issues

- Complete or in progress

- TiN-coated Be windows (11) available for RFCC-1
- ceramic RF windows (10) delivered
- first set of 6 tuner arms in production at Fermilab
 - 6 actuators being fabricated
- input coupler design improved (based on results from prototype test)
- fixturing for electropolishing ready
 - awaiting ES&H approval to start (~1 month job to do 10 cavities)
- single-cavity test vessel completed
 - delivery to Fermilab happens this month



- To be done
 - physical (CMM) measurements to document cavity shape
 - few weeks work
 - frequency measurements
 - all cavities will be deformed to reach central frequency of 201 MHz
 - RF conditioning (without and with magnetic field \Rightarrow await first CC)
- No unresolved issues (yet)



- First amplifier tested to 1 MW
 - test with new TH116 tube to 2 MW full power level remains to be done
 - need to get this finished!
 - worthwhile to understand whether output power could be higher
 - permits “headroom” for amplitude regulation
 - and expected loss of performance as tube ages
 - accommodates transmission losses
 - however, there is some risk involved in finding out
- Review committee (December '11) made a number of comments that merit our consideration
 - Moss to prepare response for comment by Tech Board
 - low tube lifetime (15K hrs at ISIS)
 - and imminent lack of supplier for additional tubes
 - need for headroom for control
 - maintenance challenge behind shield wall
 - amplifier sticks out above magnetic shield wall

- Other review comments

- concern expressed about 4-in. coax power handling capability
 - suggested testing system at MTA before ordering waveguide
- concern that specifications for RF system undefined
- suggested that adjustable phase shifters were unnecessary complication

- Review comments and proposed responses discussed

- tube availability is a real issue, but not much can be done
 - have 4 tubes now (£45K)
 - have purchased spare glass tubes as insurance
- tube degradation information at 50 Hz (vs. MICE 1 Hz)
 - don't really know scaling, so some "exposure" here
 - not a go-no-go issue
- control headroom not accounted for, nor losses in transmission thru coax
 - not clear whether we need this control (see later)
 - could be we get less than 2 MW to cavity (\Rightarrow lower voltage)
 - or we cool cavities (not presently considered for routine operation)



- Proposed responses (cont'd)

- investigated removal of phase shifters

- looks sensible; get ~2% loss of acceleration compared with optimum phase
- simplifies the plumbing
 - relieving maintenance concern
- likely improves operational reliability

- cursory look at amplifier position indicates field should be modest

- power supplies on mezzanine are another story



- Proposed responses (cont'd)

- 4-in. coax should be okay with slow-fill ramp
 - much less reflected power (10%)
 - standard Fermilab operation mode
- waiting for test not viewed as necessary
 - delay in order puts \$ at risk
 - potentially disrupts MTA program

reflected power



- Issues raised at this meeting


- check whether more bellows are needed to simplify coax installation
- check CAD model to make sure latest RFCC is used
- need to start on LLRF design
 - have DL people to do this
 - need help from LBNL (Doolittle)
- need better understanding of MICE requirements (timing; stability; ...)

- Most hardware needed for first system built and tested now
 - test to 2 MW in March 2012
 - on track for full test at RAL in Sept. 2013
- Desire to have second system available at DL *before* sending system 1 to RAL
 - at risk due to “cash-flow” problems
 - need to define “drop-dead” date for purchases to stay off of critical path



20 kV PSU &
Aux. rack -
front view

Modulator
(operational)



- Prudent to test full system after delivery to RAL
 - desirable to duplicate MTA single-cavity vacuum vessel at RAL
 - will minimize disruptions to MTA
- Not obvious (to me) that test of coax at MTA is justified
- Prudent to **carefully** test amplifier above 2 MW
 - compensation for losses
 - headroom for control
 - measurements of amplitude and phase jitter are valuable
- **MUST** understand, document, and demonstrate specifications of system
 - needed for LLRF design
 - Li and Moss propose timing workshop to get requirements (before CM33)
 - need general RF parameter discussion/workshop
 - phase and amplitude stability requirements
 - and means to achieve them



Schedule (1)



• Planned schedule for RF power

Current work in progress:

- RF testing of System #1 with new 4616 and TH116 tubes Nov 11 to Mar 12

Future work (Step V): time-scales to be confirmed

- Assembly of CERN TH116 amplifier (System #2) ----- (July 2012)
- Test CERN amplifier at Daresbury ----- (December 2012)
- Develop RF Control Systems
- Pack & ship complete system #1 to RAL ----- (January 2013)
- Install RF System #1 in MICE Hall ----- (May 2013)
- Test complete RF system #1 at RAL ----- (September 2013)
- Construct & test 4616 #2 amplifier, power supply & controls
- Construct & test TH116 #2 power supply & controls
- Test complete RF system #2 at DL
- Pack & ship system #2 to RAL
- Install RF System #2 in MICE Hall
- Test complete RF system #2 at RAL

Tasks in red are required for TIARA (deadline in brackets)

Schedule (2)

- RF cavity cleaning should begin shortly
 - about 1 month job
- Single-cavity vacuum vessel fabrication complete
 - delivery to Fermilab this month
 - can test/process cavity to full field without B field
 - repeat with CC when ready
 - tests tuner mechanism and thermal performance
 - could test LN-temperature operation
 - risky, so do not use best cavity for this
 - open question: how many MICE cavities should be tested

- Steady progress on all aspects of RF system
 - RF power system review very valuable
 - responses should be reviewed by Tech Board before finalizing
 - need to separate required testing from “feel-good” testing
 - explore risks/benefits of testing above 2 MW
- Time to get serious about specifications
 - timing workshop and detailed parameter discussions should happen prior to CM33
 - important to have one RF group, not two half-groups
- Desirable to have complete second power system at DL before first system ships to RAL
- Desirable to have second single-cavity test vessel at RAL