

Final Focus Magnet Design SuperKEKB

N. Ohuchi

KEK

(on behalf of KEK SC magnet group, IR group and BNL SC magnet group)



- 1. IR Overview
- 2. Design of S.C. magnets
- 3. R&D magnet status
- 4. Construction schedule



IR Overview



S.C. Magnets in SuperKEKB IR

Design changes in the magnets: introducing iron yokes to the quadrupoles and magnetic shields on the beam pipes



	Integral field gradient, (T/m)•m Solenoid field, T	Position from IP, mm	Magnet type	Corrector	Leak field cancel coil
QC2RE	12.91 [34.9 T/m × 0.370m]	2925	S.C. + Iron Yoke	a ₁ , b ₁ , a ₂ , b ₄	
QC2RP	10.92 [27.17 × 0.4135]	1925	S.C. + Iron Yoke	a ₁ , b ₁ , a ₂ , b ₄	
QC1RE	24.99 [66.22×0.3774]	1410	S.C. + Iron Yoke	<i>a</i> ₁ , <i>b</i> ₁ , <i>a</i> ₂ , <i>b</i> ₄	
QC1RP	22.43 [66.52×0.3372]	935	S.C.	<i>a</i> ₁ , <i>b</i> ₁ , <i>a</i> ₂ , <i>b</i> ₄	b ₃ , b ₄ , b ₅ , b ₆
QC1LP	22.91 [67.94×0.3372]	-935	S.C.	<i>a</i> ₁ , <i>b</i> ₁ , <i>a</i> ₂ , <i>b</i> ₄	b ₃ , b ₄ , b ₅ , b ₆
QC1LE	26.67 [70.68×0.3774]	-1410	S.C. + Iron Yoke	<i>a</i> ₁ , <i>b</i> ₁ , <i>a</i> ₂ , <i>b</i> ₄	
QC2LP	10.96 [27.15 × 0.4135]	-1925	S.C. + Iron Yoke	<i>a</i> ₁ , <i>b</i> ₁ , <i>a</i> ₂ , <i>b</i> ₄	
QC2LE	14.13 [20.2×0.700]	-2700	S.C. + Iron Yoke	<i>a</i> ₁ , <i>b</i> ₁ , <i>a</i> ₂ , <i>b</i> ₄	
ESR	4.3 T (max. field)		S.C. Solenoid		
ESR-add	0.3 T	Each beam	S.C. Solenoid + Iron Yoke		
ESL	4.7 T (max. field)		S.C. Solenoid		

ZUIZ/UZ/IU

Super

KEKB

supero/supervevo joint ivieeting

QC1P (No iron yoke)



QC1P magnet design (QC1RP, QC1LP)

- Same design for QC1RP and QC1LP
- 2 layer coils [double pancake]
- SC correctors inside of the magnet bore
 - $-a_2, b_1, a_1, b_4$ from the inside
- Cryostat inner bore radius=18.0 mm
- Beam pipe (warm tube)

Super

<EKE

inner radius=10.5 mm, outer radius=14.5 mm

SC cancel coils against the leak field from QC1P

- b_5 , b_6 , b_4 , b_3 from the inside
- Cryostat inner bore radius=18.0 mm
- Beam pipe(warm tube)
 - inner radius=10.5 mm, outer radius=14.5 mm



QC1R/LP Magnet Parameters

	QC1RP	QC1LP		
Coil inner radius, mm	25.00			
Coil outer radius, mm	30.	485		
Turns in one pole	12 (1 st layer),	13 (2 nd layer)		
Spec. of integral field, T	22.43	22.91		
Field gradient, T/m	66.52	67.94		
Effective magnetic length, m	0.3	372		
Magnet current, A	1575.58	1609.30		
Current density of the cable (SC area), A/mm ²	1685.0	1721.0		
Current density of the cable (overall), A/mm ²	802.4	819.6		
Magnetic field by Belle and comp. sol., T	2.5 2.5			
Max. field in the coil without solenoid field, T	2.29	2.34		
Max. field in the coil with solenoid field, T	4.07	4.08		
Operating point with respect to B_c at 4.7 K	81.8%	83.5%		
Magnet physical length, mm	416			
Error field at r=1 cm (2D calculation)	$b_6 = 1.60 \times 10^{-5}$			
	$b_{10} = -2.28 \times 10^{-6}$			
	$b_{14} = 6.20 \times 10^{-7}$			
Error field at r=1 cm (3D calculation)	$b_6 = -1.13 \times 10^{-5}$			
	$b_{10} = -4$	1.71×10^{-6}		

QC1P operation point





QC1E with Iron Yoke





QC1E Operation Point



QC1RE G=66.22 T/m $I_{op}=1460.3 \text{ A}$ $J_{op}=1561.8 \text{ A/mm}^2$ $J_{op}/J_{c@4.7K}=67.3 \%$

QC1LE G=70.68 T/m $I_{op}=1558.5 \text{ A}$ $J_{op}=1666.9 \text{ A/mm}^2$ $J_{op}/J_{c@4.7K}=71.8 \%$

(L_{eff}= 0.3774 m)

In case that the operating point of 85 % w.r.t. the critical point is acceptable, the quadrupole field can be increased by 18 %.

1E magnetic field calculation in 2D





QC1E magnet design (QC1RE, QC1LE)

- 2 layer coils [double pancake]
- Cryostat inner bore radius=25.0 mm
- Beam pipe (warm tube)
 - Inner radius=17.0 mm, outer radius=21.0 mm
- Magnet current= 1655 A
 - Current density = 599.6 A/mm² (in the coils), 1770 A/mm² (in NbTi)
- *G_R* = 75.94T/m
- Maximum field in the magnet=2.89 T
- Ratio of field enhancement by iron is 1.338.



SuperB/SuperKEKB Joint Meeung



QC1, 2 Magnet Parameters

	Iron Yoke	Magnet current (A)	Field gradient (T/m)	Effective length (m)	Operating point (%)
QC1RP	No	1575.6	66.52	0.3372	82
QC1LP	No	1609.3	67.94	0.3372	84
QC2RP	Yes	817.9	27.17	0.4135	41
QC2LP	Yes	817.3	27.15	0.4135	41
QC1RE	Yes	1460.3	66.22	0.3774	67
QC1LE	Yes	1558.5	70.68	0.3774	72
QC2RE	Yes	1044.9	30.59	0.4221	55
QC2LE	Yes	724.1	22.07	0.6407	32





- QC1 and QC2 quadrupoles have SC correctors of a_2 , b_1 , a_1 and b_4 .
- All correctors and the leak field cancel coils will be manufactured by BNL under the international research collaboration.



SC wire is wound in coil with the direct winding method.

QC1P $b_1 \exists 1 l l$ 31 turns/pole $B_1 = 0.045 \text{ T at } 50\text{ A}$ $I_{op}/I_c = 68 \% \text{ at } 5.0 \text{ K}$

QC1P b_4 コイル 8 turns/pole B_4 =3398 T/m³ at 50A I_{op}/I_c = 68 % at 5.0 K



SC corrector design status



	G (T/m)	Corrector Current (A)	A1 (T)	B1 (T)	A2 (T/m)	B4 (T/m³)	dy (mm)	dx (mm)	dθ (mrad)
QC1RP	66.52	50	0.045	0.046	2.28	3398	0.657	0.632	14.0
QC1LP	67.94	50	0.045	0.046	2.28	3398	0.644	0.618	13.7
QC2RP	27.17	50	0.0792	0.0785	1.253	442.4	2.91	2.89	23.1
QC2LP	27.15	50	0.0792	0.0785	1.253	442.4	2.92	2.89	23.1
QC1RE	66.22	50	0.067	0.130	1.770	1853.6	1.01	1.955 (0.69:Optics 1.265:alignment)	13.4
QC1LE	70.68	50	0.067	0.130	1.770	1853.6	0.95	1.839 (0.69:Optics 1.159:alignment)	12.5
QC2RE	34.90	50	0.0795	0.0783	1.137	327.6	2.28	2.24	16.3
QC2LE	20.20	50	0.0795	0.0783	1.137	327.6	3.94	3.88	28.1

2D calculations of SC correctors have been completed.

3D design of the corrector coils for QC1P has been completed, and the other coils are evaluated under the condition that the coils have the same effective magnetic length as the main quadrupole.





- QC1P for the e+ beam line is non-iron magnet and the e- beam line is very close to QC1P. The leak fields along the e- beam line by QC1P are calculated.
- B_3 , B_4 , B_5 and B_6 components of the leak fields are designed to be canceled with the SC cancel coils.
- B_1 and B_2 components are not canceled, and they are included in the optics calculation.
 - B_2 component is used for focusing and defocusing the e- beam.





b₃ Cancel Coil Configuration



BROOKH

NATIONAL LABORATORY



Canceling QC1P Leak Field



Cancelling the leak fields by SC multipole coils





Compensation Solenoids



- In order to force the integrated solenoid field to zero from IP, the additional SC solenoids are designed inside of the QC2RE iron yoke on both beam lines.
- 3D magnetic field calculation is on going.



EMF on Solenoids and Iron

- ESL and ESR: ON
 - Right side
 - Superconducting solenoid : $3.70\times\,10^4$ N
 - Iron in the front helium vessel : $1.41 \times 10^3 \mbox{ N}$
 - Iron in the rear helium vessel $:-9.86\times10^3\,N$
 - Vacuum vessel (room temp.): $-2.86 \times 10^4 \mbox{ N}$
 - Left side
 - Superconducting solenoid $:-4.79\times10^4~N$
 - Iron in the front helium vessel $\,:8.08\times10^3\,N$
 - Vacuum vessel (room temp.) : $1.27 \times 10^4 \mbox{ N}$
- ESL and ESR: OFF
 - Right side
 - Iron in the front helium vessel $:-9.60\times10^3~N$
 - Iron in the rear helium vessel : $-1.67 \times 10^4 \mbox{ N}$
 - Vacuum vessel (room temp.) : $-4.29 \times 10^4 \mbox{ N}$
 - Left side
 - Iron in the front helium vessel $:8.47\times10^4~\text{N}$
 - Vacuum vessel (room temp.) : $1.42 \times 10^4 \mbox{ N}$



SuperB/SuperKEKB Joi



Effect of Solenoids on Beam Life

- Initial magnet configuration
 - In order to cancel the residual solenoid field between QC2RP and QC2RE, we placed 1.5 T additional solenoids behind QC2RE on each beam line.
- Optics calculation
 - This configuration reduced the LER beam life time from 570 s to 400 s. By reducing the peak field of the solenoid from 1.5 T to 0.2 T, the life time recovered to over 540 s. The optics calculation showed that the solenoid field bump between QC2RP and QC2RE had a small impact on the life time.
- Improving the solenoid design
 - By the above analysis and further calculation, we designed the additional solenoid of 0.7 m and 0.3 T inside of the QC2RE yoke.





R&D magnet status

Construction of QC1P R&D magnet

Construction of QC1RP R&D magnet started at the end of August.



1st pole-inner layer coil

1st pole-outer layer coil

R&D magnet status (cont.)

Construction of QC1P R&D magnet (cont.)

Super

KEKB



Four coils completed at 3rd October.



4 correctors were constructed in 2010. The corrector package has a function of magnet bobbin for the QC1P R&D magnet.





QC1P R&D magnet



2012/02/10



Magnet R&D schedule

- The QC1P R&D magnet has been tested at 4 K with the vertical cryostat in January.
 - Excitation results:
 - QC1P R&D magnet: no quench up to the nominal current (1510A and G=75.58 T/m).
 - Correctors (b_1, a_1, a_2, b_4) , cancel coils (b_1, b_2, b_3) : no quench to the nominal current of 50 A.
 - Field measurements:
 - There was some troubles in the harmonic coil.
 - Now the coil is repaired, and the cold test is scheduled from the 21th February.
- The proto-type of QC1E will be constructed in March and April 2012 and tested in May 2012.
- The proto-type of QC1P will be constructed in August 2012 with the company personnel after bidding the IR magnet-cryostat construction.



Construction schedule of IR magnets

	2011(4~9)	20)11(10~3)	2012(4~9)	2012(10~3)	2013(4~9)	2013(10~3)	2014(4~9)	2014(10~3)	2015(4~9)
	23			24		25		26		27
Commissioning SuperKEKB, and evaluating back ground noise to Belle									1	
Installing magnet-cryostats on the beam line, Interlock test of the system,										
Field measurement on the beam line										
Construction of IR magnets and cryostats								\rightarrow		
QCS and corrector excitation tests and field measurements as the acceptance test				-						
in the vertical cryostats				-				•		
Construction of the cryogenic system										
Cooling performance test of cryogenics (two system)					008-1				S-R	
Design and construction of cryostat supports										
Construction of power supplies (Cabling power lines))						
							•			

IR magnet-cryogenic system commissioning



Super

KEKB

6-

Summary

- Magnet and IR design
 - Basic magnet designs of SC-QCs and SC-correctors have been completed.
 - Calculation of 3D Solenoid field is on going.
 - Now improving the calculation precision.
- SC correctors and leak field cancel coils
 - All SC correctors and leak field cancel coils will be manufactured by BNL under the international research collaboration.
 - The construction schedule by BNL completely matches with SuperKEKB IR construction.
- R&D magnets
 - Construction of the QC1P R&D magnet was completed and cold tested.
 - The magnetic field measurements of the magnet will be carried out in this month.
 - The constructions of QC1P and QC1E prototypes are scheduled in this year.
- Completion of the IR superconducting magnet construction is scheduled at Nov. 2014.