


CWRF'2012

Brookhaven, 8-11 May 2012

New HOM Damped Cavity at the ESRF

Vincent Serrière (project leader), Jörn Jacob,
Loys Goirand, Bernard Ogier,
Anna Triantafyllou,
Ayan Bandyopadhyay



European Synchrotron Radiation Facility



* This work, carried out within the framework of the ESRFUP project, has received research funding from the EU Seventh Framework Programme, FP7.

Existing ESRF 5-cell copper cavity




- Synchrotron radiation losses in Storage Ring:
 - 5 MeV/turn for each electron
- 6 highly efficient accelerating RF cavities with five coupled cells:
 - Fundamental resonance = accelerating mode at 352.2 MHz for electron re-acceleration:
 - ☞ 300 kW to obtain 9 MV RF voltage
 - ☞ 1000 kW to compensate the synchrotron radiation losses of 200 mA of beam
 - **BUT** Higher Order Modes = **HOMs**:
 - ☞ If HOM in resonance with eigenfrequencies of the beam ⇒ possible **instabilities above**


$$I_{\text{threshold}} \approx 50 \text{ mA}$$

HOM driven Longitudinal Coupled Bunch Instabilities – Energy/Phase oscillations

Energy oscillation \Rightarrow Energy spread of electrons \Rightarrow Reduction of brilliance



Nice picture for
machine physicist



Disaster for
ESRF users

Beam stabilization at high currents



+



HOM detuning by
precise control of
cavity temperatures

$$T = T_{set} \pm 0.05 \text{ }^{\circ}\text{C}$$

⇒ **200 mA**

stable beam / any
filling pattern

+

Fast Bunch-by-Bunch
Feedback system
[Eric Plouviez et al.]



During MDT' 2010

⇒ **300 mA**

☞ **ALTERNATIVE** for high operation reliability at 300 mA:


Cavities with strongly damped HOMs

- 2004 start R&D with a PhD thesis [Nicolas Guillotin]
- 2007-2011 ESRFUP / WP13 = design, build & test an **operational cavity**

352.2 MHz Single cell NC HOM damped cavity

- 9 MV with 12 to 18 cavities ($4.7 \pm 0.4 \text{ M}\Omega$)
- Planned operation at 300 mA
- Power capability to sustain up to 500 mA
- No HOM up to 1 A

HOM absorbers:
Ferrite loaded tapered ridges




RF finger contacts on the ridges

HOM dampers = ridge waveguides

$$f_{rf} < \text{cut off} < \text{lowest HOM freq}$$

Based on 500 MHz BESSY, MLS, ALBA design
[E. Weihreter et al.]

ESRF 352.2 MHz design: several improvements



E-beam welding of HOM coupling sections to the body


- ⇒ to avoid a gap between ridges and cavity body, and thereby
- ⇒ to suppress residual HOM and flange over- heating (observed on BESSY/ALBA cavity)

ESRF optimization of ridge waveguides:


- ☞ Optimum coupling to all HOM
- ☞ Short HOM dampers despite lower RF frequency
- ☞ Numerical EM simulations and low power RF measurements on full scale aluminum models

Procurement of 3 operational copper cavities

- May 2009: Call for tender
 - mechanical design by ESRF
 - full set of detailed ESRF drawings
- Order of 3 power prototypes
 - validate the design
 - qualify 3 companies for a later series fabrication :
 - ◇ RI (D),
 - ◇ SDMS (F),
 - ◇ CINEL (I)
 - validate 2 different manufacturing procedures
 - obtain 3 operational cavities for phase 1 of ESRF upgrade





Initially specified mechanical design & manufacturing procedure applied by RI - Research Instruments (photos)




HOM absorbers


C48 ferrite tiles
brazed on Cu
plate



*RI: Ferrite HOM
absorber for IR thermal
test at ESRF*





Ferrite/Cu plate brazed on tapered
stainless steel absorber



*SDMS: direct brazing
to stainless steel –
successful IR thermal
test at ESRF*

1st cavity delivered by RI – Research Instruments



- ✓ Delivered 15 June 2011
- ✓ Excellent fundamental mode impedance:
 - $R_s = 4.9 \text{ M}\Omega$,
 - $Q_0 = 33800$ (expected 30000 to 35000)
- ✓ HOM spectrum a factor two lower than design goal
- ✓ **600 kV obtained in CW** on RF power test stand
 - ✎ Inspection of RF fingers between HOM coupling sections and dampers: no sign of degradation



October 2011: Installation on Storage Ring cell 25

- Passive operation with **excellent vacuum behaviour** at
 - ✓ 200 mA in multibunch fillings (a few hours after machine restart)
 - ✓ 95 mA in 16 bunch filling (most demanding for HOM dampers)
- Active operation - first tests with **beam acceleration very satisfactory**
 - ✓ $V_{acc} = 0.4 \text{ MV}$ with 20 kW
 - ✓ $I_{beam} = 168 \text{ mA}$ with total of 63 kW into new cavity

Alternative design proposed by SDMS, engineered by V. Serrière / ESRF applied by SDMS and CINEL




*CINEL: 3 body sectors
after machining of the
water cooling channels,
September 2010*




*SDMS parts of
end discs
ready for e-
beam welding*

Final assembly by e-beam welding




*SDMS: Body after
e-beam assembly
of the 3 sectors,
November 2010*

Difficult e-beam weld Cavity / HOM coupling section - SDMS cavity




Leak detected on one e-beam weld

1st attempt to repair: MIG welding, not successful




Difficult e-beam welding operation

2nd attempt: further e-beam weld from inside with an intermediate copper ring



Successful repair



2nd delivery: SDMS cavity


- Delivered on 20 July 2011
- Successful vacuum test
- $Q_0 = 32000$
- RF conditioning May-June 2012
- Installation for beam test on cell 25 in summer 2012

Very smooth fabrication of CINEL cavity (also alternative design)




3rd cavity: CINEL

- Last weld in April 2012
- All welds and surfaces perfect
- Vacuum test: these days
- HOM absorbers: assembly brazing still to be done
- Installation for beam test on cell 25 in winter 2013



Frequency
tuning before
assembly
welding


RF upgrade phase 1 well in progress !



3 SSA from ELTA for SR:

- ☞ Powering 3 new HOM damped cavities on the storage ring
- ☞ In fabrication

SY Cav 1 & 2




4 SSA from ELTA for the booster:


- ☞ In operation since March 2012

3 prototype HOM damped cavities ...

- ☞ Test with beam one by one on cell 25 with klystron transmitter TRA3:
- ☞ 1st cavity (RI) installed in October 2011: excellent behaviour with beam



Cav 6 & new cavity for test




Cell 23, length 5 m → 7 m

... 3 prototype HOM damped cavities

- ☞ 2013: all 3 cavities in new 7 m section/cell 23 with 3 SSA

First new Storage Ring RF unit with 3 HOM damped cavities

- Summer 2013: Installation of all 3 cavities on cell 23
- Connection to 3 x 150 kW SSA = 2nd batch from ELTA



Cell 23 = first straight lengthened to 7 m

THANK YOU !

