



Wir schaffen Wissen – heute für morgen

Paul Scherrer Institut

Markus Schneider

**Current activities on the rf-system for the proton
accelerator facility at PSI**

High intensity proton accelerator facility

590 MeV proton beam
2.2 mA operational beam current
2.4 mA maximal achieved beam current
(1.4 MW beam power)

**Injector 2 cyclotron
(upgrade of rf system)**

Cockcroft Walton

**Ring cyclotron
(Plasma crisis)**

UCN

Experimental area


SINQ

The Ring cyclotron

flattop cavity

sector magnet

copper cavity




numbers	type	material	frequency	gap voltage	incident power no Beam	incident power @ 2.4 mA Beam
4	Main cavity	copper	50 MHz	~ 850 kVp	~ 250 kW	~ 600 kW
1	Flattop cavity	aluminum	150 MHz	555 kVp	~ 90 kW	~ - 30 kW

Like a firework in the machine

During operation in 2010 a failure of the cooling system for trim coils in sector magnets occurred. The Magnet power supplies were switched off, rf was still running. Temperatures of trim coils went up to 100° C. Since this event the voltage of cavity 3 had to be reduced from 850 kVp to 650 kVp. At higher levels there was a lot of arcing in the cavity and no stable operation possible.




View inside the cyclotron at the end of operation period 2010 during tests to push the cavity 3 to nominal voltage.




Trim coils of sector magnet 5. During shutdown 2010 they were replaced.

cavity 3 suffered from the trim coils SM5


Trim coils SM5




View on cavity 3



Marks from the „fire work“ in the cyclotron




Closed view on cavity 3



Beam slit of cavity 3

Inside cavity 3



**Dirt (aluminum and stainless steel)
→ material from trim coils**

Cavity 3 cleaned during shutdown 2010 and afterwards conditioned to 900 kVp

Cleaning of cavity 2

During operation in 2011 we observed in cavity 2 about 7 to 10 times more micro sparks than in the other cavities. A micro spark is a short spark in the cavity and the rf is switched off for about 200 μ s. Inspection of cavity 2 in shutdown 2012.



Inside cavity 2.
The same mark as in cavity 3 but from the other direction.



Cleaning of cavity 2 with „Miobrill“ and alcohol.
After this procedure cavity condition to 900 kVp.
Reduction of micro sparks ? \Rightarrow result in one year.

Tuning system of copper cavity


A very expensive barometer

Change of resonance frequency

Hydraulic pressure $\sim 800 \text{ kHz / Bar}$

Atmospheric pressure $\sim 670 \text{ Hz / mBar}$


5 upper hydraulic tuning yokes



5 lower hydraulic tuning yokes

swivel joint

**hydraulic cylinder
operation at
about 33 Bar**



Measurements of radiated rf in cyclotron

AS: Pickup in vacuum chamber

AS-KAV2

Cavity 3

Radiated rf from flattop cavity ignites “plasma” in SM7.
Effect seen on BR3 and EEC.


Differential tuning system on cavity 3 and flattop cavity

rf measurements on pickups, BR3, EEC

BR1 has an impact on measured rf at BR3 and EEC

AS-KAV3

Flattop cavity




BR3
Beam stopper

EEC
Electrostatic extraction device

BR1
Beam stopper


differential tuning cavity 3, cavity 1 to 4 on nominal voltage

Operation point (symmetric tuning)



Differential tuning flattop cavity


+ / - 6 Bar (Limit at 10 Bar)



offset of 1V is equal to 2Bar


**Master controlled by
phase detector**

**Slave pressure controlled
by master pressure**




Hydraulic pressure of Flattop cavity during regular operation is at about 100Bar. Maximal pressure 120Bar. Cavity is working on the limits. High risk of damaging cavity!

Summary of „plasma crisis“ in Ring cyclotron



View in flattop cavity

*We have to live with some glowing in the cyclotron...
maybe it was there during the last 35 years*



View at plasma from window
at flattop cavity toward SM7

- Interlock on rf when cooling system for trim coils fails
- Cavity 3 cleaned and again up to nominal gap voltage
- Cavity 2 cleaned. Reduction of micro sparks?
- Differential tuning system on cavity 3 installed. Disadvantage of slower tuning, improvement on radiated rf in cyclotron only on AS-KAV3 measured. Offset -1mm \Rightarrow symmetric tuning during regular operation.
- BR1 (beam stopper) can not be installed
- Differential tuning system on flattop cavity tested. No effect seen during measurements. Back to symmetric tuning system. Extension of differential tuning range? Risk of permanent deformation of flattop cavity!

Injector 2 cyclotron

Resonator 1

Resonator 2

Resonator 4


Sector magnet

Resonator 3




150 MHz resonator 2 and resonator 4 will be replaced by 50 MHz resonators.
Amplifier chain and LLRF for all resonators will be renewed.
Project delayed due to priority given to SWISSFEL. Lack of manpower.

New 50 MHz Resonator 2 & 4 for Injector 2




Specification

Resonance frequency:	50.6328 MHz
Accelerating voltage:	400 keV
Dissipated power:	45 kW@400kV
Tuning range:	200 kHz
Cavity RF-wall:	EN AW 1050
Structure:	EN AW 5083
Vacuum pressure:	1e-6 mbar
Cooling water flow:	15 m ³ /h
Dimension:	5.6x3.3x3.0 m
Weight:	7'000 kg



New 50 MHz Resonator



The new 50 MHz Resonators were manufactured by SDMS in France.


Resonator 2: Delivered in 2009
 Power test in 2010 + 2011

Resonator 4: Delivered to PSI April 2012
 Power test during summer 2012



Inside the Resonator
Lip (electrode) on lower right side
removed

Tuner for new 50 MHz Resonator



Hydraulic cylinder


plunger

Vacuum vessel with
mounting structure

upper tuner

Coupling loop
with cone for
measurements

lower tuner



Power test of new resonator 2 (2010)

Resonator tested for 24 hours at 100 kW.
Nominal operation at 50 kW.



Multipactoring levels observed between 3.6 and 10 kW.

Mechanical resonance at 24.6 Hz.

Finger contacts of upper and lower tuner were bent.

Distance between plunger and contact was wrong calculated.

New contact rings were machined and plungers were polished



Second power test of new resonator 2 (2011)


The Resonator 2 was again tested for further characterization:

- Pulse power for startup procedure was measured.
- Calibration of gap voltage by measuring the bremsstrahlung.

During this second test sequence the resonator was fed with power between 150 kW and 200 kW by a mistake.

Later again a strange behavior of the tuning system was observed.

⇒ Melt down of finger contacts




Power test of Resonator 2




Resonator was inspected after power tests.

Bad rf contact at the bridge between the lips in the central region. Molten screws and marks from arcing were found.


Redesign of bridge?




Mechanical test of finger contacts




Automatic controlled test setup for finger contacts.
Only mechanical test, no current on contact



Copper plate after 800 moves over a distance of 50mm. →



Test of finger contacts




Finger contacts from:
Sumitomo Heavy Industries, Ltd, Japan
(Material: silver and graphite)


Contact area:
copper with 4 μm hard gold plating

After 30'000 movements over a distance of 50mm
(speed 12 sec / 50 mm) still good contact.

Solution found for tuners. Will be tested in summer
2012.



New amplifier chains




LLRF	Pre amplifier (2 kW) Solid state amplifier	Driver stage (35 kW) Tetrode amplifier Thales RS 2048 CJC New design PSI	Final stage (180 / 360 kW) Tetrode amplifier Thales RS 2074 HF Copy of 1MW amplifier Ring Smaller power supply
------	---	---	--



Contract with Thomson Broadcast AG,
Turgi, Switzerland, for 4 plate voltage
power supplies

Site acceptance test summer 2014

Coaxial transmission lines




Coaxial transmission lines (RL 100-230, 6 1/8" EIA) from final stages to cavities.
 Ordered at Spinner Munich, Germany.
 Delivery autumn 2012, Installation 2012 / 2013

Final stages (4 + 1 spare)



Parts for 5 final stages in the machine shop.
First amplifier will be assembled until begin of 2013.
Test of this amplifier in 2013.
Afterwards assembly of the others.

Status of project



More news on the CWRP 2014
Workshop in ????

Thanks to my colleagues from the RF and LLRF group. Especially to:
Hansruedi Fitze, Markus Bopp, Wolfgang Tron, Erich Wuethrich, Arthur Schmidheiny, Sebastian Jetzer, Oliver Brun, Harald Siebold, Manuel Brönnimann, Stefan Mair, Andreas Hauff

How many
cavities shall
be cleaned?

