

# **CLIC collaboration working meeting**

-

## **RF session**

-

# **Update of the proposal for a 12GHz CLIC Test Station at Saclay**

**Franck Peauger  
CEA Saclay - IRFU – SACM**


- First proposal in 2008
- 2009 – 2012: large involvement of CEA to the 1st test stand design and construction at CERN (modulator, RF components, ...)
- 2011: novel idea of 4 x 6 MW high rep rate klystrons and recombination
- April 2012: CERN announcement at the KEK workshop
  - > the 50 MW klystron #2 from CPI will be available for a collaborator

## What is our position now ?


- The development of a 12 GHz Test Stand at Saclay is still one of the main objectives for CEA (we also want to continue with accelerating structures activities)
- We prefer the 50 MW klystron based test stand solution and we are candidate to receive and use the 2<sup>nd</sup> CPI klystron at Saclay. We think it is more straightforward solution where we will fully benefit from our experience on high voltage solid state modulator, 100 MW class RF components, etc...

Similar to the CERN test stand:


- RF frequency: 11.9942 GHz
- Peak RF power: 100 to 120 MW
- Pulse length: 250 ns
- Pulse repetition rate : 50 Hz




- Full CATIA model using “real” models of individual components



Many thanks to Nicolas MISIARA (CEA)







SLAC XL5 klystron



The CPI klystron should be identical to the SLAC XL5 klystron in term of RF performances.

But,

The interfaces, handling and storage procedures must be carefully reviewed with CPI:

- Dimensions
- X-ray lead shielding
- Electrical (filament, HV, ion pumps)
- Hydraulic
- ...

**We think that we have at Saclay the necessary expertise to use and “take care” of such a unique and expensive high power klystron**



Even if some improvements are still necessary (HV rise time, control command, interlocks...), we think it is worth going on with the solid state technology for its compactness, reliability and stability.



ScandinoVA modulator at CERN  
ordered by CEA Saclay

## CEA/Scandinova contract

### ARTICLE 1 – OBJET

Le présent marché définit les conditions selon lesquelles le CEA confie au Titulaire, qui accepte, la réalisation d'un modulateur Haute Tension 50Hz pour un banc de test 12GHz, ci-après dénommé « l'Equipement » destiné à être livré et installé au CERN (Genève – Suisse).

Les prestations se déclinent comme suit :

- Tranche ferme : réalisation d'un modulateur Haute Tension 50Hz pour un banc de test 12GHz.
- Tranches optionnelles :
  - option n°1 : réalisation d'un second modulateur ayant les mêmes caractéristiques que le modulateur réalisé dans le cadre de la tranche ferme,
  - option n°2 : une année de maintenance préventive et corrective pour un modulateur Haute Tension 50Hz à l'issue de la période de garantie de 2 ans.

Le CEA se réserve la possibilité de lever, par lettre recommandée avec accusé de réception, l'option n°1 jusqu'au 30/06/2012 dans les conditions définies à l'article 20.1 du présent avenant n°2 et l'option n°2 au plus tard jusqu'à 1 mois avant la fin de période de garantie de 2 ans de l'Equipement.

En cas de levée de tout ou partie des options, le Titulaire s'engage à exécuter la prestation correspondante conformément aux conditions définies par le cahier des charges.

La réalisation de ces prestations sera effectuée pour le compte de la Direction des Sciences de la Matière (DSM), Institut de Recherches sur les lois Fondamentales de l'Univers (IRFU), Service des Accélérateurs, de Cryogénie et de Magnétisme (SACM) basé au CEA/Saclay.

The actual contract with ScandinoVA includes **an option for a second modulator with a reasonable price**. We must ask ScandinoVA the possibility to extend this option to the end of 2012 / beginning of 2013




In our implementation, the RF network is short and compact (low RF losses)

Most of the components have been developed these last 3 years and some of them have been successfully tested at high power.


The RF pulse compressor is the only critical component and its development is proposed in the frame of Eucard2. A directional coupler with low power RF window is under development now.

Some components are even in stock at Saclay or at CERN (WR90 waveguides, SLAC flanges, 3 dB hybrid, mode converters, Stainless steel 430 for loads)


$H_{01}^0$  mode converter and RF valve



3 dB Hybrid Coupler



RF pulse compressor




RF loads



$H_{01}^0$  Jog mode converter



Bidirectional coupler and window



Saclay Accelerator Platform  
'Synergium'

« Clean lab », available now

My office!


« Fosse Amalthée »: ~ 230 m<sup>2</sup>  
at the basement level, need  
to be restaured


IFMIF injector (bunker  
available in 2013)

SPIRAL2 injector (bunker  
available in 2013)

We have all the necessary  
infrastructure (crane capacity,  
electrical power, cooling power  
and concrete shielding blocks)

The future location of the test  
stand is still in discussion





**Feb 2014: CPI Klystron received at Saclay**

**Apr 2014: Modulator installed at Saclay**

**Jan 2015: Operation on accelerating structure**