





# CTF3 results, status and plans in next phase

R. Corsini for the CTF3 Team

#### Talk Outline:

- 1. Status of CLIC feasibility benchmarks in CTF3 and 2011 Highlights
- 2. Update on 2012 run, last results and schedule
- 3. Plans for 2013 and beyond





ltem	Feasibility Issue	Unit	Nominal	Achieved	How	Feasibility	Comments		
	Fully loaded accel effic	%	97	95	CTF3	$\sim$			
	Freq&Current multipl	-	2*3*4	2*4	CTF3		Novel scheme fully demonstrated in CTF3 in spite of lower current since beam dynamics more sensitive than nominal		
Drive beam	Combined beam current (12 GHz)	A	4.5*24=100	3.5*8=28	CTF3		due to lower energy (250MeV/2Gev)		
		nsec	240	140	CTF3				
	Intensity stability	1.E-03	0.75	< 0.6	CTF3		End of DBA. To be demonstrated for combined beam in 2011		
	Drive beam linac RF phase stability	Deg (1GHZ)	0.05	0.035	CTF3, XFEL		Achieved in CTF3, XFEL design		
	PETS RF Power	MW	130	>130	TBTS/SLAC	$\sim$	PD acts at apprical power and pulse length measured on		
	PETS Pulse length	ns	170	>170	TBTS/SLAC		BD rate at nominal power and pulse lenght, measured on Klystron driven PETS. Beam driven tests under way in CTF3		
Beam	PETS Breakdown rate	/m	< 1-10-7	≤ <b>2.4 10-7</b>	TBTS/SLAC		naysu on ta henr ers. Beam ta wen tests under way in CIPS		
Driven RF	PETS ON/OFF	-	@ 50Hz	-	CTF3/TBTS	2011	Prototype under fabrication for tests with beam		
power	Drive beam to RF efficiency	%	90%	-	CTF3/TBL		TBL with 8 (16) PETS in 2011(12) for 30(50%) efficiency.		
generation						<b>2112</b>	Benchmark beam simulation for safe extrapolation of high		
							efficiency at high drive beam energy(2GeV).		
	RF pulse shape control	%	< 0.1%	-	CTF3/TBTS	2011-2012	$\Rightarrow$		
Accelerating Structures (CAS)		MV/m	100	100	CTT2 To d		Nominal performances of 3 structures without damping.		
		ns	170	170			4 DC		
						2011	Nextef – RF test stand KEK		
		%	27	15		2			
Two Beam		MV/m - ns	100 - 170	106 - 170	TBTS	2011	Power production in Two Beam Test Stand (TBTS)		
							Probe beam acceleration by Two Beam Test Stand(TBTS)		
	Drive to main beam timing stability	psec	0.05	-	CTF3	2012			
	Main to main beam timing stability	psec	0.07	-	XFEL?	2012			
Ultra low	Emitttance generation H/V	generation H/V nm 500/5 3000/12 ATF, NSLS/SLS Jamping Ring design no		Damping Ring design nom perf. Relax emitt achieved ATF					
Emittances	Emittance preservation: Blow-up	nm	<b>160/15</b>	<b>16</b> 0/15	+ simulation		Simulation + alignment/stability		
Alignment	Main Linac components	microns	15	40 (orino )	Alignement & Mod. Test Bench	<b>2011</b>	Principle demonstrated in CTF2, to be adapted to long		
	Final-Doublet	microns	2 to 8	is thunch		<b>2011</b>	distances and integrated in Two Beam Module in 2010		
Vertical	Quad Main Linac	nm>1 Hz	1.5	0.13	Stabilisation Test Bench	2011-12	Adaptation to quad prototype and detector environment in		
stabilisation	Final Doublet (assuming feedbacks)	nm>4 Hz	0.2				2010. Integrated in Two Beam Module with beam till 2012.		
				Common lance la	CTF3		LUISTING AND IT THE BOUIL BOUND THE BOUIL DE LVIZ.		
nd Machine	72MW@2.4GeV					2011	Report integrating LHC experience under preparation		
	Drive beam generation Beam Driven RF power generation Accelerating Structures (CAS) Two Beam Acceleration Ultra low Emittances Alignment Vertical	Initial Structures (CAS)Fully loaded accel effic Freq&Current multiplDrive beam generationCombined beam current (12 GHz) Combined pulse length (12 GHz) Intensity stability Drive beam linac RF phase stabilityBeam Driven RF power generationPETS RF Power PETS Pulse length PETS ON/OFF Drive beam to RF efficiency Structure Structure Ref to beam transfer efficiencyAccelerating Structures (CAS)Structure Acc field Structure Breakdown rate PETS ON/OFFTwo Beam AccelerationPower producton and probe beam acceleration in Two beam module Drive to main beam timing stabilityUltra low EmittancesEmittance generation H/V Emittances Final-Doublet	Fully loaded accel effic%Drive beam generationCombined beam current (12 GHz)ACombined pulse length (12 GHz)nsecIntensity stability1.E-03Drive beam linac RF phase stabilityDeg (1GHz)PETS RF PowerMWWPETS Breakdown rate/mPETS Breakdown rate/mPETS ON/OFF-Drive beam to RF efficiency%RF pulse shape control%Accelerating Structures (CAS)Structure Flat Top Pulse length structures Rf to beam transfer efficiency%Two Beam AccelerationDrive to main beam timing stabilitypsecWith no main beam timing stabilitypsec%Ultra low EmittanceEmittance generation H/V mmitancesmmicronsAlignment ActicalQuad Main LinacmicronsVerticalQuad Main Linacmm>1 Hz	FundamentFully loaded accel effic%97Drive beam generationCombined beam current (12 GHz)A4.5*24=100Combined pulse length (12 GHz)nsec240Intensity stability1.E-030.75Drive beam linac RF phase stabilityDeg (1GHZ)0.05PETS RF PowerMWW130PETS Pulse lengthns170PETS Pulse lengthns170PETS Breakdown rate/m<1-10-7	Fully loaded accel effic%9795Freq&Current multipl-2*3*42*4Combined beam current (12 GHz)A4.5*24=1003.5*8=28Combined pulse length (12 GHz)nsec240140Intensity stability1.E-030.75<0.6	Fully loaded accel effic%9795CTF3Drive beam generationCombined beam current (12 GHz)A4.5724=1003.5%=28CTF3Combined bulse length (12 GHz)nsec240140CTF3Intensity stability1.Eq30.75< 0.6	Fully loaded accel effic%9795CTF3Drive beam generationCombined beam current (12 GHz) Combined pulse length (12 GHz)A4.5*24=1003.5*8=28CTF3Combined pulse length (12 GHz) Intensity stabilitynsec240140CTF3Drive beam linac RF phase stability Drive beam linac RF phase stability1.6-030.75<0.6		

CTF3



Technical system tests and simulations


**Feed**ibility

Цa





Item	Feasibility Issue	Unit	Nominal	Āchieved	How	Feasibility	Comments
	Fully loaded accel effic	%	97	95	CTF3		
	Freq&Current multipl	-	2*3*4	2*4	CTF3	<b>V</b>	Novel scheme fully demonstrated in CTF3 in spite of lower current since beam dynamics more sensitive than nominal
Drive beam	Combined beam current (12 GHz)	Α	4.5*24=100	3.5*8=28	CTF3		due to lower energy (250MeV/2Gev)
generation	Combined pulse length (12 GHz)	nsec	240	140	CTF3	$\sim$	
	Intensity stability	1.E-03	0.75	< 0.6	CTF3		End of DBA. To be demonstrated for combined beam in 2011
	Drive beam linac RF phase stability	Deg (1GHZ)	0.05	0.035	CTF3, XFEL	$\checkmark$	Achieved in CTF3, XFEL design



RF pulse at output

Dipole modes suppressed by slotted iris damping (first dipole's Q factor < 20) and HOM frequency detuning



High current, full-loaded linac operation


- 95 % RF to beam efficiency measured
- No instabilities




## Achievements – Drive Beam Generation

R. Corsini, CLIC Collaboration Working Meeting, 9 May 2012









Streak camera images of the beam, illustrating the bunch combination process in the ring

## Achievements – Drive Beam Generation




#### Beam recombination


- Factor 4 OK
- Factor 8
  - basic principle demonstrated
  - need improvement (pulse shape, stability, losses, emittance)




Best results in CLEX for factor 4:  $\varepsilon_{H}$ = 250 um  $\varepsilon_{V}$ = 140 um for factor 8:  $\varepsilon_{H}$ = 640 um  $\varepsilon_{V}$ = 170 um

Different turns are ~ ok, no unknown effects Emittance increase due to non perfect orbit








• PETS operation to power levels (about 250 MW) well above CLIC goal, at nominal CLIC pulse length.



- First successful test of PETS with on-off mechanism
- Measured gradient in two-beam acceleration test 145 MV/m (CLIC nominal gradient of 100 MV/m)
- Nine PETS tanks installed in the Test Beam Line (TBL), 21 A decelerated by ~ 26%, matching well with expectations














# CTF3 highlights - 2011



## **CTF3** Stability

R. Corsini, CLIC Collaboration Working Meeting, 9 May 2012










Nine PETS tanks installed and commissioned in 2011 (13 PETS installed in 2012)

**TBL** line in **CLEX** 


Full beam transport to end-of-line spectrometer, stable beam

Power produced (70 MW/PETS) fully consistent with drive beam current (21 A) and measured deceleration.





Beam deceleration, measured in spectrometer and compared with expectations




More than half a GW of 12 GHz power!










PETS operated routinely above 200 MW peak RF power

providing reliably pulses ~ 100 MW peak to accelerating structure.

About twice the power needed to demonstrate 100 MV/m acceleration in a two-beam experiment with TD24 structure.








Two-Beam Acceleration demonstration in TBTS

Up to 145 MV/m measured gradient


Good agreement with expectations (power vs. gradient)





Maximum stable probe beam acceleration measured: 31 MeV

Corresponding to a gradient of 145 MV/m










- kicks on horizontal and vertical planes between 0.02 and 0.2 mrad;
- kicks corresponding to a transverse momentum between 10 and 40 keV/c (measurements at NLCTA within 30 keV/c, Dolgashev et al., LINAC 2004);


Break-down kicks & Break-down physics/statistics

W. Farabolini, A. Palaia























PETS, forward RF







#### Demonstration of PETS of-off mechanism


- Considered a feasibility issue
- Ability to:
- Switch off power from individual PETS to accelerating structure in case of breakdown

Power

- Reduce substantially power in PETS, to cope with PETS breakdowns
- PETS on-off principle fully tested
- Conditioned at high power
   (135 MW nominal) by recirculation







Amplitude

800

frequency, GHz

600

200






#### CTF3 Achievements – What is still missing for feasibility studies – Drive Beam Generation







#### CTF3 Achievements – What is still missing for feasibility studies – CLEX







## Problems in 2011 – Actions:


- TWT availability: still working with 2 SHB only plus day-to-day power fluctuations, mainly working with 3 GHz beam for most of the year One TWT back from repair, one to be sent soon, should have 3 available in Autumn
- Difficult DL set-up after last stop suspect misaligned quadrupole (+ radiation alarm problem) Measure and realign DL quad(s) & BPMs
- Unbalanced RF injection bump in CR Modify RF network


## Start of operation in 2012:

- Early operation (February-March) for TERA RF tests, PHIN all goals met
- Beam in CTF3 linac in March, CLEX closed in April
- Problem with Modulator-klystron availability, reliability: it was the main cause of delays this year (slow start-up, had to replace a few tubes, frequent trips in some). Mixture of old equipment, bad luck and lack of manpower, should try to correct at least this last one.
- Lots of time spent on injector optimization (beam up to girder 10, half-linac), very good beam but not enough beam-time to keep the schedule about 1 month delay.









S. Verdu-Andres & TERA group




Preliminary **BDR** evaluation

P <sub>in</sub>	Es	E <sup>test cell</sup> 0	E <sup>linac cell</sup> 0	<b>T</b> <sub>pulse</sub>	T <sub>flat-top</sub>	$\mathbf{f}_{rep}$	<b>t</b> <sub>measure</sub>	# <sub>FC</sub>	BDR <sub>FC</sub>	# <sub>RE</sub>	BDR <sub>RE</sub>
[kW]	[MV/m]	[MV/m]	[MV/m]	[µs]	[µs]	[Hz]	[s]	[]	[bpp/m]	[]	[bpp/m]
770	365	56		3.5	2.2	50	26104			19	8·10 <sup>-4</sup>
980	415	64		3.5	2.2	50	7661			40	5.5.10-3
900	400	60		3.5	2.2	50	4755			11	2.4.10-3
770	365	56		3.5	2.2	50	10402			11	1.1.10-3
160	168	26	37	3.5	2.2	50	367417	33	1.10-4	0	<mark>&lt;3·10⁻</mark> 6
~500	~290	44		3.5	2.2	50	73333			4 6	6-9.10-5
~900	~400	61		3.5	2.2	50	3615			6	1.8.10-3
~900	~400	61		2.8	1.5	50	27924			14	5.3.10-4
~900	~400	61		2.3	~1.2	50	50938			8	1.7.10-4
~700	~350			3.5	2.2	50	18052			3	1.8.10-4





#### March 2012: Lifetime studies of Cs<sub>3</sub>Sb cathodes with green light, about 2 weeks








### Delay Loop:

Measure and realign DL quad(s)


- → Done. Two quads around DL injection region were found to be misaligned by 800 um in vertical and were realigned. Several BPMs were also misaligned (mainly in H) by up to a few mm with respect to the known positions supposedly in the database. When entering the new values, we discovered that (database corruption?) the calibration values were all at zero. ⇒ Database corrected.
- → Together with the improved setting of the linac, this resulted in a fast DL loop set-up to full transmission, ½ day (it took 2-3 weeks last year) with better orbit and more acceptance.









## Delay Loop dispersion & transport...



## Beam through CR...



-3.5



占



## Program

- TERA run for medical accelerator test
- PHIN photoinjector tests
- Improve beam quality: emittance, beam current (losses), bunch length, reproducibility, long & medium term stability, current & phase jitter – especially for factor 8
  - It's a goal in itself, but will also ease all other experimental goals
  - Improve existing feedbacks, develop & deploy new ones
  - increase beam repetition rate
  - Correct/cross-calibrate BPMs, improve DB phase diagnostics (BPRs, phase monitors) ح

#### • TBTS


- PETS on/off:
  - Measure break-down rates in different conditions (recirculation high-power, nominal on and off)
- New accelerating structures with wake-field monitors INSTALLED IN SUMMER
- BD measurements & BD kicks measurements, wake-field monitor tests
- RF pulse shaping tests
- TBL
  - RF power production: 12 to 13 PETS tanks, from 20 A towards 30 A
  - further improve precision of current, energy, bunch length & RF power measurements
  - Reach more than 1/3 deceleration
- Drive beam phase monitor tests, DB phase stability studies



## Drive Beam feed-forward & feedback (WP CTF3-002)

R. Corsini, CLIC Collaboration Working Meeting, 9 May 2012











- The location of all the components was determined. The electronics will be installed next to MKS15. Total cable length from the monitor to the most distant kicker will be below 30m
- The 1st phase monitor should arrive at CERN any day
- Technical (re)design of the line modifications is progressing
- Need to fabricate the connecting vacuum chamber components (bellows, replacement chambers)
- 2 additional correctors will be installed to assure sufficient steering capabilities
- Installation in the tunnel should take place within a few weeks











# TBL beyond 2012 (CTF3-003)

R. Corsini, CLIC Collaboration Working Meeting, 9 May 2012



Upgrade TBL to a test facility relevant for CLIC TDR work

- <u>12 GHz power production for structure conditioning</u>
- Working experience with a real decelerator
- Beam dynamics studies, pulse shaping, feedbacks, etc


#### Timeline:

- Last batch of PETS will be adapted to high-power testing (using internal recirculation)
- One (or two slots) tested at beginning of 2013
- Gradual increase of slots to 4-8 slots and rep rate to 25-50 Hz






<u>S. Doebert</u>









Status:

modified PETS with input coupler and mini-tank designed


Next steps: fabrication drawings for PETS, complete integration study for accelerating structure Missing resources in mechanical engineering



# Two Beam Modules in CLEX (CTF3-004)

R. Corsini, CLIC Collaboration Working Meeting, 9 May 2012






Schematic layout of CLIC Modules in CLEX



















- To improve: beam current (losses), emittance, bunch length, reproducibility, long & medium term stability, current & phase jitter especially for factor 8
- It's a goal in itself, but will also ease all other experimental goals.
- First 3-4 months of operation: need systematic studies on relevant issues. A large part of them can be performed with a 3 GHz beam (but...)
  - Injector set-up: min energy spread & bunch length (need new measurements, like energy spread scan?), current flatness. Reference signals established. 1-2 weeks.
  - Linac: RF set-up, references. Transverse optics (girder 10, CT line, girder 5?). 1 week.
  - Chicane & CT line: Prepare a few optics with lower R56, optics checks (kick, dispersion), matching. Bunch length measurements. 2 weeks.
  - DL: Orbit & matching, new references (misalignment?). Bunch length measurements. 2 weeks.
  - CR: Closed orbit correction, orbit closure, ring length, isochronicity (bunch length measurements), matching, dispersion (no combination). Combination set-up (factor 4). 2-3 weeks.
  - TL2, CLEX: optics studies (matching, dispersion, emittance, bunch length measurements...).
     1-2 weeks.
  - Set-up of 1.5 GHz beam, repeat all studies. Set-up of combination factor 8. 2-3 weeks.





• In parallel:

## Interesting the second

- Improve existing feedbacks, develop & deploy new ones.
- Correct/cross-calibrate BPMs, improve DB phase diagnostics (BPRs).
- Improve/develop operation software.
- Define, document and put in place operational procedures.
- ...





- PETS on/off:
  - Basic demonstration done. Need some time to condition above nominal in recirculation mode (in the shadow of new structures conditioning...).
  - Measure break-down rates in different conditions (recirculation high-power, nominal on, nominal off).
- Structures:
  - Conditioning. Questions: how aggressive should we be? How much time can we dedicate to that? What rep rate will be available? When will CALIFES be available to check power calibrations?
  - In the shadow of conditioning: prepare tools for BD studies (analysis, flash-box signals...)
  - BD measurements (exploit flash-box) & BD kicks measurements, wake-field monitor tests.
  - RF pulse shaping tests.

N.B.: CTF3 being limited in rep rate, some RF studies are better carried out in the stand-alone test stand (need common analysis – AND superposition of BD rate regimes).
 However, the added value of CTF3 is the possibility to study the whole system (e.g., PETS BDs

induced by structure BDs, etc...)






- RF power production: 12 to 13 PETS tanks, from 20 A to 30 A
  - Improve precision of current, energy, bunch length & RF power measurements further
  - Reach more than 1/3 deceleration
  - Drive beam phase stability monitoring
- Dispersion free steering, optics studies also extend to high current/large deceleration
- Possibly, a new PETS prototype for TBL+ to be tested before the end of the year (input coupler, mini-tank, PETS On/Off)














Alexandra Andersson, Frank Tecker, Piotr Skowronski





		M10 M11 M12 M13 M13 M14 M15 M16 M17 M18			M35 M36 M37 M37 M38 M38 M38 M38 M38 M38 M42 M42 M43 M43 M43	M46 M47 M47 M49 M51 M51 M52 M53 M53 M55 M57 M57	
		<	EuCA	RD		<b>→</b>	
		2010	2011		2012	2013	2014
est Modı	ule			3 0 1 0 3			
hase 3	ТО						
9.2	2 Design of NCLinac hardware for test module		M24				
9.2	2 Prototype components for CLIC module prepared				M36		
	Phase 3 Design						
	Phase 3 Procurement				(TD26	with all features + girde	rs)
	Phase 3: Component validation				(mainly for RF st	ructures, TD24 )	
	Phase 3 Assembly						
	Phase 3 Installation						
	Phase 3 Test						
Phase 4	Т1 Т0 Т0						
	Phase 4 Design						
	Phase 4 Procurement						
	Phase 4 Assembly						
	phase 4 Installation						
	Phase 4 Test						

<u>G. Riddone</u>



R. Corsini, CLIC Collaboration Working Meeting, 9 May 2012



## Problems:

- TWT availability still working with 2 (out of 3) SHB only
   plus day-to-day power fluctuations
   => Mainly working with 3 GHz beam for most of the year
- Difficult DL set-up after last stop


   suspect misaligned quadrupole (+ radiation alarm problem)

Eventually able to get good recombination (current record), but:

- Bad pulse shape (phase switches?)
- Still limited acceptance -> stability was improved, but it is still not good enough
- DL quads measured and realigned

Future work:

• Work on phase switches, gun current compensation, back to 3 TWTs, improve trajectories







- Phase monitor installation: summer 2012
  - $\rightarrow$  get experience with phase monitor r/o
  - $\rightarrow$  digitisation of signals
  - $\rightarrow$  develop + test firmware
- Kicker installation: winter 2012/3
- Amplifier ready: winter 2012/3
  - $\rightarrow$  test kickers: spring 2013
  - → system tests: spring/summer 2013




## Introduction to CTF3



## CTF3 is a scaled model of CLIC RF power source

It was built partly re-using existing infrastructure (LPI)


- Compromises on parameters in order to make it affordable
- In some cases issues are more difficult than in CLIC








Item	Feasibility Issue	Unit	Nominal	Āchieved	How	Feasibility	Comments	
	Fully loaded accel effic	%	97	95	CTF3			
	Freq&Current multipl	-	2*3*4	2*4	CTF3	<b>V</b>	Novel scheme fully demonstrated in CTF3 in spite of lower current since beam dynamics more sensitive than nominal	
Drive beam	Combined beam current (12 GHz)	Α	4.5*24=100	3.5*8=28	CTF3	$\checkmark$	due to lower energy (250MeV/2Gev)	
generation	Combined pulse length (12 GHz)	nsec	240	140	CTF3	$\sim$		
	Intensity stability	1.E-03	0.75	< 0.6	CTF3		End of DBA. To be demonstrated for combined beam in 2011	
	Drive beam linac RF phase stability	Deg (1GHZ)	0.05	0.035	CTF3, XFEL	$\checkmark$	Achieved in CTF3, XFEL design	








0.99
















### Measurements in TL2 - uncombined




- Improve measurements
- Correct dispersion (linear, nonlinear)
- Correct multi-turn orbit
- Control beta-beating

End 2011 ?

### **Beam recombination - Emittance**

Best results in CLEX for factor 4:  $\varepsilon_{H}$ = 250 um  $\varepsilon_{V}$ = 140 um for factor 8:  $\varepsilon_{H}$ = 640 um  $\varepsilon_{V}$ = 170 um

Different turns are ~ ok, no unknown effects Emittance increase due to non perfect combination






## Achievements – Drive Beam Generation


R. Corsini, CLIC Collaboration Working Meeting, 9 May 2012



## Vertical



## Horizontal



## Emittance – last measurements in CLEX

- No time for optimization
- Main issue: different trajectories for DL & bypass beams and ring orbit closure (differences of the order of  $1 \sigma$ )
  - Vertical:
  - Horizontal:

main effect from DL, small effect from ring ring closure is dominant


• Similar Twiss parameters for factor 4 and factor 8 combination (small betatron mismatch)

<u>F. Tecker, P. Skowronski,</u> <u>S. Doebert, R. Lillestol</u>





## Beam profile during emittance measurements







### **Beam recombination – Bunch lenght**


nominal in CLEX 1 mm sigma


In the past, well below 1 mm sigma measured at the end of the linac (tuned chicane)

Recent results (preliminary): 1.5 to 4 mm sigma for CR and CLEX (natural chicane)

## Combiner ring


turn 1, 3 data for each timing






#### CLEX

5 bunches per measurement, 3 data for each timing












## Achievements – Drive Beam Generation


R. Corsini, CLIC Collaboration Working Meeting, 9 May 2012












<u>T. Persson</u>

6<sup>th</sup> December 2011








 $6^{\text{th}}$  December 2011

































## PETS On-Off operation – high current, high power






R. Corsini, CLIC Collaboration Working Meeting, 9 May 2012

^ ^-++\0\/0/++-^ ^

XSG hawkmoth



Steffen Doebert, Reidar Lillestol










# Break-down kicks

#### Andrea Palaia, Wilfrid Farabolini, Javier Barranco




Measured on OTR screen CA.MTV0790 (~4.9 m from the accelerating structure).














# **Gun current Correction**

R. Corsini, CLIC Collaboration Working Meeting, 9 May 2012



\_ O X

7500






# **Compensation of phase switches**

R. Corsini, CLIC Collaboration Working Meeting, 9 May 2012








# Optics studies, orbit correction

R. Corsini, CLIC Collaboration Working Meeting, 9 May 2012









What do we learn in CTF3, relevant for the CLIC RF power source ?								
A non-exha	ustive list	© easier	☺ more difficult					
System	quantity/issue	CTF3	CLIC					
Injector/linac	bunch charge current pulse length phase coding frequency transverse stability	2-3 nC 3.5 - 4.5 A 1.4 μs same <b>3 GHz</b> about the same - CTF	7.7 nC 4.2 A 140 μs 1 GHz F3 ``too stable ´´					
Delay loop/ring	final current beam energy combination CSR, wakes Deflector instability	30 A 150 MeV 2 - 4 worse in CTF3 (lower about the same	110 A 2.4 GeV 2 - 3, 4 • energy)					
Power production (PETS)	-	23 mm ≈ 1 m > 135 MW 140 ns (240 with recir	23 mm 23 cm 135 MW culation) 240 ns					
Decelerator	Fractional loss Final energy wakes, stability beam envelope	50-60 % 70 MeV	70 MeV240 MeVsomehow ``masked´´ in CTF3					

In general, most of unwanted effects are equivalent or worse in CTF3 because of the low energy, however in CLIC the beam power is much larger (heating, activation, machine protection)

Needed tolerances on the final drive beam parameters (phase, current, energy stability...) are more stringent in CLIC – some could be demonstrated in CTF3 as well