



CTC Activity Report



→ DR SC Wiggler	P. Ferracin et al.
→ Survey & Alignment	H. Mainaud et al.
→ Quad Stability	K. Artoos et al.
→ Two-Beam module development	G. Riddone et al.
Warm Magnet Prototypes	M. Modena et al.
→ Beam Instrumentation	T. Lefevre et al.
Collimation, Masks and Beam Dumps	V. Vlachoudis et al.
Controls	M. Draper et al.
RF Systems (1 GHz klystrons & DB cavities, DR RF)	E. Jensen et al.
→ Powering (Modulators, magnet converters)	D. Nisbet et al.
Vacuum Systems	C. Garion et al.
Magnetic stray Fields Measurements	S. Russenschuck et al.
→ DR Extraction System	M. Barnes et al.
Creation of a "CLIC technology center@CERN"	F. Bertinelli et al.




Two Beam module program

- Objectives
 - assemble a 1-0-0-4 configuration in the lab for:
 - a) validation of integration studies; access to components; sequence of installation...
 - b) choice of materials and components (girder material...)
 - c) metrology before and after a transport
 - d) intense measurement program on thermal behaviour
 - e) showcase: the present idea is to show during a council week the module assembly in the entry hall of building 60
 - f) create a natural deadline for contributions from other activities: (vacuum, alignment, quad stabilization, magnets, instrumentation)

CLIC two-beam module



**Baseline for
Conceptual
Design
Review**



Two-beam module prototypes (B169)


Assembly and Integration

Test modules in the LAB. 4 modules 1-0-0-4:

Type 0: assembly under way


Type 1: Integration study under way:
MBQ stabilization unit needed to finalize MB
supporting system.

Type 4: Integration study started:
MBQ stabilization unit needed



Two-beam module prototypes (B169)

Type 0





Two-beam module prototypes (B169)

Type 0

Final brazing of:

- 1st stack made of 4 AS: completed
- 2+2 RF network for 1st TM0
- Manifolds for AS #5

Accelerating structures



RF network



COMPLETED

1st stack



Manifolds for AS #5

Two-beam module prototypes (B169)

Type 0 RF system




Two-beam module prototypes (B169) Type 0 technical systems




Two-beam module prototypes (B169)


Validation tests



- The aim of prototype modules is to prove the feasibility of the proposed technical solutions for the different systems (pre-alignment, stabilization, cooling and vacuum systems)
- **Alignment tests successfully performed**
- Thermal tests to validate thermo-mechanical models previously developed: heaters will be used to reproduce heat dissipation due to RF power
- **Thermal tests in preparation**



IPAC12 paper




CLIC: Two-beam module prototype (CLEX) – Integration and procurement

Test modules in the CLEX. Integration of the first T0 is under way. Procurement of main components launched (girders and accelerating structures)


STATUS:

- AS: under fabrication
- PETS: under fabrication by CIEMAT
- DBQ: Cockcroft of Danfysik, preliminary integration done. Final integration after the design of supporting system
- RF network: design and integration under way
- Slim tank: design and integration under way



Two-beam module prototype (CLEX) Accelerating structure

TD26 CC SiC (*4 accelerating structures for the module* to be tested with beam and RF in the CLIC Experimental Area)



Disks (about 30 each ac. structure)

Vacuum manifolds: housing damping material

Other technical systems: cooling, alignment integrated




- Metrology and Active Pre-alignment





CLIC pre-alignment studies

On the two beam modules prototypes...

- ✓ cWPS sensors and actuators validated (see next slide)
- ✓ Articulation concept validated for both solutions of supporting (see next slide)
- ✓ 13 oWPS installed, to be validated.
- ✓ Alignment systems developed by NIKHEF (optical based Raschain) integrated (installation foreseen in June 2012)
- ✓ Validation of the fiducialisation strategy under progress
- ✓ Software in order to acquire sensors and pilot actuators developed under labview ok.
- ✓ Control algorithms ready
- ✓ Micro triangulation developed and validated.




Installation of 13 oWPS




Integration of NIKHEF alignment systems



Development of micro triangulation



Control software




Regulation

CLIC pre-alignment studies

Latest results on the two beam modules prototypes...

Performance of the sensors




	WPS	INCLINOMETER
Noise (peak to peak)	5 μm	3 μrad
Standard deviation over 15s	0.6 μm	1 μrad
Repeatability	1 μm	2-3 μrad
Reproducibility	2-3 μm	5 μrad
Interchangeability	2-3 μm	4-5 μrad

Performance of the articulation point


3 DOF linkage (Slave versus Master)	Boostec	Micro-Contrôle
Vertical Translation	1-2 μm	3-5 μm
Horizontal Translation	1-2 μm	2-3 μm
Roll	1 μrad	2 μrad

CLIC pre-alignment studies

Development of high resolution cam movers...





5DOF test bench reinstalled in ISR 8.



5DOF repositioning in less than 3 iterations
below 1 μm



Development of a smaller cam mover (for type 1 MB quad) under progress





- **Quadrupole Stability**

- Water cooling 4 l/min
- With magnetic field on
- With hybrid circuit



Figure

Value

R.m.s @ 1 Hz magnet

0.5 nm (during the day)

R.m.s @ 1 Hz ground


6.3 nm

R.m.s. attenuation ratio




~13

R.m.s @ 1 Hz objective

1.5 nm




- X-y guide « blocks » roll + longitudinal
- Increases lateral stiffness by factor 500, increases band width without resonances to ~ 100 Hz
- Introduces a stiff support for nano metrology
- cross check with interferometer






Stabilisation Radiation tests 2012



19

- Contact with RAD WG
- **SEU tests in the H4IRAD test stand at CERN planned for August**
- Several components under evaluation. Larger community working on same problems
- Sensitivity simulation of controller to changes in the components
- remark from RAD WG: **Essential for CLIC: obtain more complete and sure expected radiation values.**
- Available shielding for electronics in the CLIC tunnel ????





Laboratoire d'Annecy-le-Vieux
de Physique des Particules




Update on Final Focus stabilisation studies in Annecy

Andrea JEREMIE





In2p3

FF stabilisation results




Attenuation up to 50dB
between 1,5-100Hz




RMS ground at 4 Hz: 5 nm
 RMS on foot at 4Hz: 0,6nm
 (FF aim: 0,2nm at 4Hz)
 RMS ratio: 8,3


Control scheme for FF quad stabilisation





Experimental setup



Matlab and dSPACE ControlDesk
 For monitoring and analysis



Active foot with
 sensors



dSPACE
 Real time hardware for
 Rapid Control Prototyping






Amplifiers, filters input/output
 board for signal conditioning

Sensor type	Electromagnetic Geophone	Piezoelectric Accelerometer
Model	GURALP CMG-6T	Wilcoxon 731A
Company	Geosig	MEGGITT
Output signal	Velocity (X,Y,Z)	Z Acceleration
Sensitivity	2398 V/m/s	10 V/g
Bandwidth [Hz]	[0.033-100]	[0.05-500]



- Magnets

CLIC QD0 Main Parameters		Prototype (Iron yoke length of 100 mm)	Nominal magnet (Iron yoke length of ~ 2500 mm)
Max. Gradient (computed)	[T/m]	552	615
Magnet aperture	[mm]	8.25	8.25
Tunability		32÷100%	32÷100%
GEOMETRY			
Total length	[mm]	273	2600
Width	[mm]	468	518
Height	[mm]	424	424
Total mass	kg	~ 200	~2700
COILS			
Conductor size	[mm]	4x4	4x4
N. of turns		324 (18x18)	324 (18x18)
Average turn length	[m]	0.586	5.786
Total coils (4) mass	[kg]	107.2	1060.8
ELECT.PARAMETERS			
Ampereturns per pole	[A]	5000	5000
Current	[A]	15.4	15.4
Current density	[A/mm ²]	1	1
Total resistance	[mOhm]	896	8838
Total voltage	[V]	13.8	136.4
Total power	[W]	213	2150






ASTeC Report for CLIC-UK

Jim Clarke on behalf of all ASTeC &
Technology Department staff contributing to
CLIC-UK

STFC Daresbury Laboratory, UK

CERN-UK Review, 9th May 2012



Tuneability



Low energy end more demanding in terms of adjustable range of magnet





High Strength Quad Design



UNITS

Length	mm
Area density	A/mm
Field strength	A/m
Potential	Wb/m ²
Conductivity	S/m
Source density	A/mm ²
Power	W
Force	N
Energy	J
Mass	kg

PROBLEM DATA
 C:\Documents\CLC\BD-55-625-62-38 of
 Quadratic elements
 1/2 symmetry
 Vector potential
 Magnetic fields
 No mesh
 5 regions




UNITS


Length	mm
Area density	A/mm
Field strength	A/m
Potential	Wb/m ²
Conductivity	S/m
Source density	A/mm ²
Power	W
Force	N
Energy	J
Mass	kg

PROBLEM DATA
 C:\Documents\CLC\BD-55-625-62-38 of
 Quadratic elements
 1/2 symmetry
 Vector potential
 Magnetic fields
 No mesh
 5 regions


Basic Engineering Concept



Engineering




Fully Open






Fully Closed

PM Block secured to steel yoke



Permanent Magnets






- Instrumentation




Cold test of the cavity BPM prototype



Monopole-mode
"REF" resonator




Dipole-mode
"BPM" resonator
& waveguide




- Stainless steel prototype cavity BPM for CTF3
- Cold test carried out before brazing – mechanical improvement identified
- Dipole mode frequency within 5 MHz of the design value of 15 GHz
- Q-values and coupling close to expected (~250)
- Reference cavity: frequency off by +2 GHz, Reduced the diameter by 0.98 mm to correct it
- Cavity has been **successfully brazed** and leak-tested
- Next steps: vacuum test with feedthroughs, repeat RF measurements
- Foreseen to be tested in TBTS@CTF3**

Low cross-coupling
out of the box: -41
dB average

Trc1 S12 dB Mag 5 dB / Ref.-45 dB Cal
Trc2 S14 dB Mag 5 dB / Ref.-45 dB Cal
Trc3 S32 dB Mag 5 dB / Ref.-45 dB Cal
Trc4 S34 dB Mag 5 dB / Ref.-45 dB Cal




Frequency vs. temperature variation: 250 kHz/K





Cold test of the Stripline BPM prototype




Striplines BPM for the CLIC decelerator

- High current 100A – high bunch frequency 12GHz
- In the vicinity of an RF structure producing 100MW @12GHz
- Temporal resolution of 10ns
- 2 micron resolution over an aperture of 23mm (accurate calibration)
- Transverse mode damped by SiC absorber



Stripline BPM has been assembled

RF Characterization and linearity checks have started







Design of ODR Chamber for CESR-TA




Observing Optical Diffraction Radiation angular distribution to measure Beam size





Electron beam direction



Integration of Chamber in the L3 straight section @ CESR-TA




Simulation of the optical distribution



Replacement chamber

Slit-mask assembly







1. Califes Facility — E-O Bunch Profile Monitor using spectral decoding

Development of a sub-ps time resolution bunch length monitor

1. Overall EO system for CTF3 is designed
2. Laser system and optics arrived
3. Control system design completed, all cables and optical fibres installed
4. Optical synchronization system designed, transfer lines for laser and OTR designed
5. Laser laboratory under preparation, camera and motors being delivered
6. Two vacuum chambers are being designed



2. Activities at STFC Daresbury Laboratory

Spectral Upconversion Techniques - Convert the far-IR \rightarrow mid-IR spectrum to an optical spectrum

- Bandwidth reduction 1mm - 10 μ m \rightarrow 800nm - 740nm

2011/12 experiments at Daresbury (Manchester Univ collaborating)

Laser-generated THz pulses as mimic of electron bunch

- Experiments underway May 2012




3. Activities at University of Dundee

EO Detection solution in thin films & 2D structures

Nano-structured materials

Materials, Photonics & Smart Systems (MAPS) Group at Dundee

Fabrication & Applications of Nanocomposites





3 separate nanosecond laser systems (wavelengths - 355, 532 and 1064 nm) in place for materials processing, during 2011

Picosecond (Coherent Talisker ULTRA 355-04) system installed May 2012
Operates at same 3 wavelengths

Pulsewidth <15ps with an average power of up to 4W at 355nm, 8W at 532nm, and 16W at 1064nm.

First tests on new system planned for early June 2012






CLIC Beam loss monitoring



1. CDR Baseline Choice: Ionization Chambers

- Adequate (dynamic range, sensitivity), BUT expensive, 1 per quadrupole means >50,000.
- Investigate Alternative Technologies for the Two Beam Modules e.g. Cherenkov Fibers
- REF: CLIC BI CDR chapter & IPAC 2010 WEPEB074

2. Development of Analytical Model for Cherenkov Light Signal in Fibers



Must Consider probability of :

1.trapping of produced photons inside the fiber, P_t


2.trapped photons exiting the fiber end face, P_e

3.trapped photons exiting the end face within acceptance cone
 $P_{e,a}$

$$P_{e,a} \propto \cos^{-1} \left[\frac{\beta \sqrt{n_{co}^2 - NA} - \cos \alpha}{\sin \alpha \sqrt{\beta^2 n_{co}^2 - 1}} \right] \quad NA = \sqrt{n_{co}^2 - n_{cl}^2}$$


Several papers already exist (but conflicting theories) → Developed our own model ~ 200 lines code (J. V)

- Signal depends on:
 - Angle of incoming radiation alpha α ,
 - Velocity of charged particle beta: β
 - Refractive indices of fiber core and cladding
 - Fiber diameter



3. Verification of Model for Cherenkov Light Signal in Fibers

- Experiments at CERN Test Beam Lines (T9 East Hall, H6A, SPS North Area)
- Good Agreement between Experimental and Model




Left: Results for the angular dependency of the photon yield in a fiber with:
-d=0.365mm
-NA=0.22

- (FLUKA simulations for Optical photon production also in good agreement with Model / experimental data)
- REF: Masters thesis (May 2012) by J. Van Hoorne,
- & Journal papers (hopefully) to be published.

4. Determine Cherenkov Fiber Signal for CLIC Two Beam Modules




1. FLUKA to simulate loss scenarios and calculate **angular and velocity distribution** of secondary particle shower at fiber locations




FLUKA Representation of Two Beam Modules Beamline Components. Charged particle distributions calculated at blue lines.

2. Use analytical model to predict signal (or 'trapped photons') for a given fiber type and various loss scenarios. Determined dynamic range, sensitivity requirements of photon detectors.

Example : Loss at 2.4 GeV :



▪ REF: webpc171, IPAC 2011



CLIC Beam loss monitoring



Longitudinal Position Resolution - Fibers


- 100m fibers, Long bunch trains (60m)
 - NOT a problem for machine protection purposes: Onset of a destructive loss always detected**
 - Location of onset of destructive loss can be found with rise time of photo-detector signal
 - Standard Operational Losses: Some localised detectors per fiber could be used to measure the loss structure over a train and compared with signal from fiber to determine loss structure over 100m accelerator. ..

Cross Talk (All Monitor Types)

- Desirable to distinguish between a failure loss from each of the beams
- Spatial Distribution of prompt Absorbed Dose (Gy) from FLUKA Simulations:

Drive Beam: 1.0% of bunch train hits aperture restriction


Main Beam: 0.01% of bunch train hits aperture restriction



- Loss of 1.0% in DB provokes similar signal as a loss of 0.01% of MB in region close to MB quadrupole.
- Compare signals from both fibers each side to distinguish Main and Drive Beam losses.**
- In any case: **NOT a Machine Protection Issue – Dangerous loss would never go unnoticed**

Fibers at CTF3

- Installation of fiber at TBL (2012)*
 - Achievable longitudinal position resolution, with long bunch trains using ‘forward’ (downstream) and ‘backward’ (upstream) trapped photons
 - Comparison of Fiber with localized detectors (ACEMs)
 - Suitability of Silicon Photomultipliers as a photodetector for fibres
- Preliminary Results at CLEX(TBTS) (in 2011) Used for:*
 - First observation of Cherenkov Signal from Fiber
 - See whether cross talk can be studied at TBTS (it probably can't – probe beam too low intensity)
 - Decide on diameter for fibers to be used in CLEX Hall. (< 200um sufficient)
 - Confirm production of ‘upstream’ and ‘downstream’ photons in fiber






- Damping Ring Extraction Equipment
 - Stripline kickers
 - Pulser (Inductive Adder)



Present Status of Inductive Adder (IA) Development

- Components and devices ordered for prototyping an IA
- Tests of main components on-going or scheduled:
 - Pulse Capacitors
 - Semiconductor Switches and Gate Drivers
 - Transformer cores (April, by CERN TE/MS?)
- 3-D modelling of the IA stack commenced
 - Mechanical and electrical design of the IA stack: housing of transformer cores, feedthroughs, PCBs, etc.




3D Model of one layer of IA !



Sample transformer cores



Capacitor test






Present Status of Inductive Adder Development & Planning

- The stripline odd mode characteristic impedance may not be matched to the impedance of the inductive adder, resulting in increased settling time for ripple and hence increased demands on the IA.
- Also the IA design for the CLIC 1 GHz baseline is more demanding than for the 2 GHz option.
- In addition, although the IA design for CLIC DR is the main goal of the current R&D, **the prototype IA is also being designed to meet the specifications of ATF test facilities** (e.g. increased voltage w.r.t. CLIC DR).
- 2012 goal is to have tested 2 or 3 layers of IA and ordered significant quantity of components for one-stack.
- 2013 goal is to build and test one stack and order components for a 2nd stack.
- **2014 goal is to test in a facility (with beam).**

Settling time of the kicker voltage pulse as function of stripline impedance. IA = CVS, Delay of IA + cable delay = 10 ns; time delay of stripline = 10 ns; load = 50 Ω .





Status Of Development of Striplines

- ✓ Cross section of striplines studies to achieve:
 - Characteristic impedance = 50 Ω
 - Excellent field homogeneity
- ✓ Possibility to test CLIC DR striplines in ATF & ALBA
 - ALBA parameters presently being defined
- ✓ Beam coupling impedance:
 - Presently being studied


TABLE OF SPECIFICATIONS FOR CLIC DR & PDR, ATF2 AND ALBA

PARAMETER	CLIC DR	CLIC PDR	ATF2	ALBA
Beam energy (GeV)	2.86	2.86	1.30	3.00
Total kick deflection angle (mrad)	1.5	2.0	5.0	
Deflection	horizontal	horizontal	horizontal	
Minimum aperture (mm)	20	40	12	12
Beam pipe range (mm)	20 - 30	40 - 50	20 - 30	20 - 30
Effective length (m)	1.7	3.4	1.3	1.3
Field rise time (μ s)	0.56 ^A /1.0 ^B	0.43 ^A /1.0 ^B	< 160	
Field fall time (ns)	0.56 ^A /1.0 ^B	0.43 ^A /1.0 ^B	NA	
Pulse flat top duration (ns)	900 ^A /160 ^B	900 ^A /160 ^B	280 - 300	
Flat top reproducibility (ns)	$\pm 1 \times 10^{-4}$	$\pm 1 \times 10^{-4}$	$\pm 1 \times 10^{-4}$	
Injection stability (per system)	$\pm 2 \times 10^{-3}$	$\pm 2 \times 10^{-2}$	$\pm 2 \times 10^{-3}$	
Extraction stability (per system)	$\pm 2 \times 10^{-4}$	$\pm 2 \times 10^{-3}$	$\pm 2 \times 10^{-4}$	
Injection field inhomogeneity (%)	$\pm 0.1^2$	$\pm 0.1^2$	$\pm 0.01^3$	
Extraction field inhomogeneity (%)	$\pm 0.01^1$	$\pm 0.1^2$	$\pm 0.01^3$	
Repetition rate (Hz)	50	50	50	
Vacuum (mbar)	10^{-10}	10^{-10}	10^{-10}	10^{-10}
Pulse voltage per stripline (kV)	± 12.5	± 17.0	± 15.0	
Stripline pulse current [50 Ω load] (A)	± 250	± 340	± 300	
Peak beam current (A)	110 ^A /120 ^B	50 ^A /70 ^B		50
Minimum bunch spacing (ns)	1.0 ^A /0.5 ^B	1.0 ^A /0.5 ^B		2.0
Bunch length (ps)	6.0 ^A /5.3 ^B	1.0 ^A /1.4 ^B		20.0
Mode matched to 50 Ω characteristic impedance	even	even	odd	
Longitudinal beam coupling impedance (Ω)	< 0.05n	< 0.05n	< 0.05n	
Transverse beam coupling impedance (k Ω /m)	< 200	< 200	< 200	

¹over 1 mm radius
²over 3.5 mm radius
³over 0.6 mm radius

^A1GHz baseline
^B2GHz baseline


STRIPLINE KICKER



- **Even mode:** same polarity on electrodes.
- **Odd mode:** opposite polarity on electrodes.

GEOMETRIC PARAMETERS OF THE CROSS SECTION

PARAMETER	CLIC DR	CLIC PDR	ATF2	ALBA
Kicker radius (mm)	24.6	51.1	24.6	
Aperture (mm)	20	40	20	
Electrode height (mm)	24.2	65.0	16.2	
Electrode edge length (mm)	4.9	5.0	5.0	
Electrode edge angle ($^\circ$)	45	45	45	
Even mode impedance (Ω)	50.4	50.0	69.7	
Odd mode impedance (Ω)	37.3	36.2	49.7	
Field homogeneity (%)	$\pm 0.01^1$ $\pm 0.1^2$	$\pm 0.08^2$	$\pm 0.01^3$	
Calculated longitudinal beam impedance (Ω)	20.3	24.6	38.2	





Present Stripline Planning


- 1) Complete the stripline design, by June 2012:
 - a) **2D kicker design to optimize the cross section of ATF2/ALBA stripline prototype;**
 - b) 3D design to study the integrated field homogeneity and beam coupling impedance.
- 2) Beam dynamics study, to analyze the impact of the kicker on the beam behavior (ATF2 and CLIC).**
- 3) Manufacturing of the stripline kicker, from June to December 2012.
- 4) Calibration and lab test at CERN, from January to March 2013. It will include:
 - a) Verification of dimensions, including tapering;
 - b) Vacuum compatibility;
 - c) Longitudinal and transverse beam coupling impedance measurements;
 - d) Field homogeneity measurements.
- 5) Possible installation of striplines at ALBA, from June to September 2013
- 6) Possible test of stripline at ALBA, from October to December 2013.
- 7) Installation of striplines at ATF2, from June to September 2014?
- 8) Test of striplines at ATF2, with inductive adder, from October to December 2014?



- Powering
 - Modulator Development

■ Technology challenges

**Pulse to pulse reproducibility:
10 to 100ppm**



Modulator and voltage measurement reproducibility **never achieved before!**

AC power quality optimization

More than 1600 modulators pulsing synchronously! Utility grid power fluctuation minimized (~1%) – tough charger design

Machine availability

With more than 1600 modulators, reliability, modularity & redundancy must be optimized for maximum accelerator availability

Modulator topology selection considering:

- Efficiency maximization (max. power limited)
- Reproducibility
- Constant power consumption
- Satisfactory accelerator availability

**Need for a global approach!
Different solutions must be explored (transformer based, fully solid state, HV & LV solutions)**

■ Survey of European Universities and institutions

Universities	Application			PFS Development			Capacitor Charger Development	
	HV	short pulses	Long pulses	pulse Transfo	bouncer	SW stack	AFE	Resonant topologies
Strathclyde University (UK)	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>						
Loughborough University (UK)	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>		<input checked="" type="checkbox"/>		<input checked="" type="checkbox"/>		
Ecole Polytechnique Paris	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>						
Research Centre Karlsruhe (DE)	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>			<input checked="" type="checkbox"/>		<input checked="" type="checkbox"/>
Université de Pau (FR)	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>				<input checked="" type="checkbox"/>		
Eindhoven (NL)	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>		<input checked="" type="checkbox"/>		<input checked="" type="checkbox"/>		
Oxford (UK)	<input checked="" type="checkbox"/>			<input checked="" type="checkbox"/>				
EPFL (CH)							<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
ETH (CH)	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
Nottingham (UK)	<input checked="" type="checkbox"/>		<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>		<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
Institutions	HV	short pulses	Long pulses	pulse Transfo	bouncer	SW stack	AFE	Resonant topologies
Desy (DE)	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>		<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>		<input checked="" type="checkbox"/>
PSI (CH)	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>				<input checked="" type="checkbox"/>		
ESS (SE)	<input checked="" type="checkbox"/>		<input checked="" type="checkbox"/>					

Preparation of collaboration agreements with ETHZ, Nottingham, Laval (Canada) and SLAC in preparation



Summary

- Wide-spread technology development program for CLIC in place.
Not only paper studies, but to a large fraction targeting real hardware and functional prototypes:
 - Will serve for beam tests (CTF3, ATF, CESR-TA...)
 - are qualified in laboratory measurements
 - will become part of future installations (DB injector)
- Based on a large collaborative efforts
- Major milestone in 2012/2013:
 - achievement of full TBA modules in the lab including measurement programs
 - planned review of TBA modules in spring 2013
- **Personal Objective for the rest of 2012:**
 - **Create additional effort for magnetic measurements and for fs-timing distribution**