CLIC workshop, 16-18 October 2007

*Working group " Two beam hardware and integration"* 

# Test module in the two beam test stand

Khurshid Alam, AB-RF

17.10.2007

K. Alam, CLIC workshop, October 16-18, 2007

# Content

- Introduction
- Organization
- Components
- Phases of layout
- Layout progress
- Schedule


#### Location

Two-beam test stand in CLEX building




K. Alam, CLIC workshop, October 16-18, 2007

#### Location



K. Oc

#### Two-beam test stand



Two Beam Test stand comprises one of modules of CLIC

#### Principle objectives of two-beam test stand:

High-power test of PETS - first full pulse length tests of CLIC (lengthened) prototypes

12 GHz high-power test of accelerating structures

Measurement of kick from rf breakdown

High-power test of PETS on/off mechanism

Operation of CLIC module

Must be built to be flexible and easily reconfigured

K. Alam, CLIC V October 16-18, 2007

### Organisation for the 2bts module

- CERN: RF Design
- CERN: mechanical design of PETS and ac. structures + rf components
- CERN and Pakistan, HMC-3, National Centre for Physics:
  - design of the overall layout and integration,
  - design, fabrication, installation and commissioning of the experimental vessels and related subsystems

#### Components/sub-systems

#### • PETS

- *RF components (loads, hybrids, directional couplers, attenuator, waveguides,...)*
- Tanks (PETS tank and Acc. Structure tank)
- PETS External Assembly support
- PETS Internal Support inside the tank
- ON-OFF Mechanism of PETS
- Under Slung Crane
- Other sub-systems
  - Cooling system
  - Vacuum system (10<sup>-8</sup> mbar)


# Main Tasks


- Fabrication of the structures
- Layout design suiting best RF performance.
- PETS assembly within +/-15 microns
- Construction of External PETS assembly stand
- Construction of Internal PETS assembly stand
- Construction of tank with a base plate welded inside
- Design and construction of PETS On-Off Mechanism.
- Design and construction of an under slung crane to handle the equipment of 2BTS module.

### Phases of Layout

- Phase 1: PETS and loads (no accelerating structures) → mid 2008
- Phase 2: PETS and one accelerating structure → end 2008
- Phase 3: PETS and a series of accelerating structure (towards clic module) → 2009

# Layout





#### PETS

In its final configuration, PETS comprises eight octants separated by the damping slots.

Each of the slots is equipped with HOM damping loads.





Sample (200 mm) successfully fabricated.

Next step: fabrication of a 1 m bar

# PETS Assembly

PETS assembly is to be done in two stages.


#### Stage-1


In stage one PETS are to be assembled on the external assembling support stand along with cooling circuit. The PETS are to be assembled in +/-15 microns.

#### Stage-2

In this stage the PETS assembly is to be assembled on the internal support and then the whole structure is to be rolled inside the tank by 04 Nos. of bearings present at the 04 corners.

#### **External and Internal Supports**








External PETS assembly support (temporary)


Internal PETS assembly support (permanent in the tank)


#### **External** Assembling of PETS













Step-8: Place the centering element Place the other bars in the same way and screw the cooling circuit with the bars.

K. Alam, CLIC workshop, October 16-18, 2007 Put the top Half Ring and screw it with bottom half ring.


Fix the couplers by screwing it with PETS /

Use these screws to fix the whole assembly against transverse misalignment.

UCLODEL 10-18, 2007

#### PETS assembly on Internal Support


#### Step-1



## Step-2


#### STEP-2

When placed on the adjustment bolts, then check if it is properly placed, if not then use the adjusting bolts for the alignment, for the horizontal and vertical alignment as well.




K. Alam, CLIC workshop, October 16-18, 2007

### Step-3




#### **Under Slung Crane**


An under slung crane is required in the building where 2BTS is to be installed as follows;




#### **Cross-Section View**



#### On-Off Mechanism of PETS (a possible solution)





#### PETS On-off mechanism



The plunger has to move inside the cavity with the external force to shut off the power.


Cavity along the PETS






The power gets off when all the 8 Nos. of plungers move inside the circular longitudinal cavity as shown above.


K. Alam, CLIC workshop, October 16-18, 2007 When the power is on, all the 8 Nos. of plungers are in the transverse cavities but don't interfere with the circular longitudinal cavity as shown above.



#### Deflection results




#### Stresses results



### Conclusions

- Progress on the test module in agreement with the schedule
  - PETS assembly strategy will be tested at the end of 2007
  - tank and components needed for phase 1 will be delivered to CERN in march 2007
- Main beam:
  - tank is under study
  - closer CLIC module configuration to be studied (alignment and stabilization features to be integrated)



K. Alam, CLIC workshop, October 16-18, 2007