


# CLIC Main Beam Transfer Lines

A. Latina, L. Rinolfi






## Components to be aligned for $e^-$



	RF Cavities	Magnets	BPM and other BI
DC gun for $e^-$	2	4	4
Bunching system for $e^-$	6	4	4
Pre-injector linac for $e^-$	10	10	5
Injector linac for $e^-$ and $e^+$	26	112	30
BC1 for $e^-$	1	4	3
Booster linac for $e^-$ and $e^+$	75	300	100
RTML for $e^-$	0	1600	800
Turn around for $e^-$	0	600	50
BC2 for $e^-$	60	4	4
<b>TOTAL</b>	<b>180</b>	<b>2638</b>	<b>1000</b>

Alignment  
precision :  
**0.1 mm**




## Components to be aligned for $e^+$



	RF Cavities	Magnets	BPM and other BI
Thermionic gun for $e^-$	2	4	4
Bunching system for $e^-$	6	4	4
Positron Drive beam linac for $e^-$	24	74	30
Pre-Injector linac for $e^+$	10	10	5
BC1 for $e^+$	1	4	3
RTML for $e^+$	0	1600	800
Turn around for $e^+$	0	600	50
BC2 for $e^+$	60	4	4
<b>TOTAL</b>	<b>103</b>	<b>2300</b>	<b>900</b>

Alignment  
precision :  
**0.1 mm**

The Injector linac and the Booster linac are common for  $e^-$  and  $e^+$  beams  $\Rightarrow$  Components have been already counted on the previous  $e^-$  Table



## Components to be aligned for e<sup>-</sup> and e<sup>+</sup>



(without PDR and DR)



	RF Cavities	Magnets	BPM and other BI	
For e <sup>-</sup> beam (including both common linacs)	180	2638	1000	
For e <sup>+</sup> beam (without the Injector and the Booster Linacs)	103	2300	900	
<b>GRAND TOTAL</b>	<b>283</b>	<b>4938</b>	<b>1900</b>	<b>= 7121</b>

Alignment precision : **0.1 mm**

For the RF cavities => **stabilized water at 30 °C**

For the magnets => **demineralized water**

# Civil engineering layout



Total length ~ 1.2 km  
 If possible on CERN Preveessin site close to power substation  
 Power consumption and cooling requirements ~ 10 MW  
 Deeper tunnel to put main beam injectors into Molasse for better stability ?