



**High
Luminosity
LHC**

CERN Activity on SC links and Cold Powering Systems

**2nd Joint Hi-Lumi LHC-LARP Annual Meeting
14 November 2012**

Amalia Ballarino, CERN



The HiLumi LHC Design Study (a sub-system of HL-LHC) is co-funded by the European Commission within the Framework Programme 7 Capacities Specific Programme, Grant Agreement 284404.



Objective of the meeting

- To present and discuss the activity performed during the year 2012 within the Tasks of the WP 6
- To discuss and organize the future activity
- To agree on future main milestones

The activity of WP6 officially starts in
November 2012

Which means that we are ahead of schedule...

PRESENTATIONS

- Introduction (A. Ballarino)
- SC link activity at CERN (A. Ballarino)
- Cryogenics for cold powering system at LHC (U. Wagner)
- Distribution feedbox and proposed cryogenic layout (Y. Yang)
- Energy deposition studies (F. Broggi)
- Conclusion, future activities (All)

Introduction

Progress on SC activity at CERN

Hi-Lumi FP7 WP6

Design study

Task 1
Coordination
CERN/INFN

Task 2
Cryogenics
CERN

Task 3
Electr. Transf.
Cryostat
Univ. South

Task 4
Energy Dep.
Material
INFN

CERN activity Design study

Integration

Civil engineering

Interfaces
(mech, vacuum, electr)

Vacuum

SC cables/SC link

Cryostat of SC link

Current leads

Protection

CERN activity


- Prototypes construction
- Cryostat
- Prototypes test

- System design
- Series specification
- Series construction
- Integration
- Operation

Fluka team




Where in the LHC ?




LHC P7

Point 7




Underground installation
Two links each about 500 m long
48 cables rated at 600 A per link

LHC P1 and P5



Surface installation
Two links each about 300 m long
Cables rated at up to 200 kA per link

Point 5



Ouvrages LHC

CMS

Introduction

Progress on SC activity at CERN

Activity in the year 2012

- CERN:

- 1) Development and qualification of **MgB₂ wires** in close collaboration with Columbus Superconductors. Successful test in July 2012 of first PIT round wire with homogeneous superconducting properties.
- 2) Design and assembly of a novel **test station** for the measurement of 20 m long high-current (up to 20 kA) superconducting links in a variable temperature range.
- 3) Conceptual study, assembly and test at 4.2 K of novel **MgB₂ and HTS (YBCO and BSCCO) cables**

- CERN:


- 1) Study of cryogenic options for the cooling of the LHC superconducting links
- 2) Preliminary integration studies in the LHC machine
- 3) Study of powering layouts for the LHC Hi-Lumi Triplets

Powering


- Input from optics and magnets:
- **4** quadrupoles (**$I=17.3$ kA** – Max current for Nb₃Sn)
- +
- **1** trim on Q1 (**$I=1$ kA**) and **1** separate trim on Q3 (**$I=1$ kA**)
- +
- **1** trim on Q2a (**$I=0.2$ kA**) and **1** separate trim on Q2b (**$I=0.2$ kA**)
- **1** separation dipole (**$I=11$ kA**)
- **Corrector package** – to be defined

June 2012: $I_{\text{quad}} = 16.44$ kA, $I_{\text{dipole}} = 9.2$ kA


Powering layout (1/3)



Powering layout (2/3)





Powering layout (3/3)




P7 – SC Link (48×600 A)

Twisted-pair cables made from tapes

MgB ₂	: 3.7 × 0.67 mm ²
BSCCO 2223	: 4 × 0.2 mm ²
YBCO	: 4 × 0.1 mm ²




P7 – SC Link (48×600 A)



Measurements performed on cable lengths of 2 m


P7 – SC Link (48×600 A)






$\Phi = 40$




30 kA
~2 kg/m
~ 150 m_{HTS}/m_{cable}




P7 – SC Link (48×600 A)



P1 and P5




$\Phi = 75$



$\Phi = 70$

27 cables 6000 A
48 cables 600 A
 $I_{\text{tot}} = 190 \text{ kA @ } 20 \text{ K}$
($\sim 2 \times 95 \text{ kA}$)


$3 \times 6 \text{ kA}$




$\Phi = 15.5$




$24 \times 6000 \text{ A}$
 $42 \times 600 \text{ A}$
 $I_{\text{tot}} = 169 \text{ kA @ } 20 \text{ K}$
($\sim 2 \times 84.5 \text{ kA}$)



Characterization of MgB₂ wire







Refrigerator: 6 kW @ 4.5 K
 (18 kW for test of LHC magnets)
 25 000 LHe Dewar

CERN Novel Test Station


RT



CERN Novel Test Station




Nexans cryostat



H ~ 4 m




CERN Novel Test Station



Completely assembled, ready for cool-down

Timeline



Deliverable and Milestones (2013)

- D6.1 Preliminary report on cooling options for the cold powering system (Task 6.2) **M18**
- D6.2 Preliminary report on results of thermo-electrical studies (Task 6.3) **M24**



cern.ch