


ILC Global Operations & Availability


Sebastian Schätzel (DESY)

Frühjahrstagung des Fachverbandes Teilchenphysik
der Deutschen Physikalischen Gesellschaft
Dortmund, 29. März 2006



- Assessment of ILC availability: Monte Carlo simulation
- How the global design is driven by availability considerations
- Benchmarking of the simulation

ILC Baseline Layout




- $E_{\text{CMS}} = 500 \text{ GeV}$
- 2 collision points (2mrad, 20mrad crossing angle)
- 2 linac tunnels (main+service)
- e^+ from conversion of undulator photons, + auxiliary e^+ source
- damping rings: 6.6km, 2 stacked rings for e^+ (electron cloud)

Baseline configuration document (BCD):

http://www.linearcollider.org/wiki/doku.php?id=bcd:bcd_home

ILC Baseline Layout



What is the uptime of this machine?

Monte Carlo Simulation

(Tom Himel, SLAC)

calculates ILC uptime from component failures

<http://www-project.slac.stanford.edu/ilc/acceldev/ops/avail/default.htm>

Detailed component list:

magnets, power supplies, vacuum pumps, etc.

Stochastic approach: generate component failures

every component has a mean-time-between-failures (MTBF)
and mean-time-to-repair

Failures degrade ILC performance:


examples:

| failure | ILC performance |
|----------------------------|----------------------|
| klystron | reduced linac energy |
| quadrupole magnet in linac | reduced luminosity |
| quadrupole magnet in DR | broken ILC |

machine “down” if: luminosity $\mathcal{L} < 0.5 \mathcal{L}_{\text{nominal}}$ or $E_{\text{CMS}} < 500 \text{ GeV}$
(or DR HV requirements not met)


Example Simulation

broken components



ILC state
up

down



up


Repair & Recovery

Different repair scenarios (component dependent):

- “hot repairs” (during ILC running), main linac tunnel access needed, no access needed
- **example:** a service tunnel reduces accesses

Recovery of beam (“tune time”):


- *time to recover well-tuned beam in a section is proportional to the time this section was **without beam** (typically 10%)*
- **example:** e^- damping ring failure
if e^+ created independently of e^- → can keep e^+ beam
→ faster ILC recovery

 global ILC layout

Machine development:


every ILC section needs 1% (damping rings: 2%) of total simulation time for improvement studies

Recovery Example




- e^+ damping ring failure

Recovery Example



- e^+ damping ring failure
- e^+ side down


Recovery Example



- can still run e^- side
- maintain stable running
- machine studies

- e^+ damping ring failure
- e^+ side down

Recovery Example




can still run e^- side

- maintain stable running
- machine studies

- e^+ damping ring repaired and tuned

Recovery Example




can still run e^- side

- maintain stable running
- machine studies

- e^+ damping ring repaired and tuned
- e^+ main linac tuned

Recovery Example




can still run e^- side

- maintain stable running
- machine studies

- e^+ damping ring repaired and tuned
- e^+ main linac tuned
- e^+ beam delivery system tuned

Recovery Example



can still run e^- side

- maintain stable running
- machine studies

- e^+ damping ring repaired and tuned
- e^+ main linac tuned
- e^+ beam delivery system tuned
- IP region tuned

→ ILC back up and running

Simulation Output

- total ILC downtime
- downtime per component
- downtime per accelerator section

Optimise:

- make components more reliable
- add spare components (redundancy)
- change global layout

Goal: ILC should deliver luminosity ~85% of the time


How 85% uptime is achieved

- 3% energy overhead in main linac; low energy linacs: 5%
(5 GeV damping ring injector, e^+ accelerator to 250 MeV, ...)
- 1 hot-swappable spare klystron/modulator per low energy linac
- klystrons and electronics in service tunnel can be hot-swapped,
(not so in main linac tunnel)
- dumps and shielding in accelerator sections: people can work
with beam in upstream section
- many more details (see BCD)

Critical Components

| Device | Improvement factor A that gives 17% downtime for 2 tunnel undulator e+ source | Downtime (%) due to these devices for 2 tunnel undulator e+ source with strong keep_alive | Improvement factor B for 1 tunnel undulator e+ source, 6% energy overhead | Improvement factor C for 1 tunnel undulator e+ source, 3% energy overhead | Nominal MTBF (hours) |
|----------------------------------|--|---|--|--|----------------------|
| magnets - water cooled | 20 | 0.4 | 20 | 20 | 1,000,000 |
| power supply controllers | 10 | 0.6 | 50 | 50 | 100,000 |
| flow switches | 10 | 0.5 | 10 | 10 | 250,000 |
| water instrumentation near pump | 10 | 0.2 | 10 | 30 | 30,000 |
| power supplies | 5 | 0.2 | 5 | 5 | 200,000 |
| kicker pulser | 5 | 0.3 | 5 | 5 | 100,000 |
| coupler interlock sensors | 5 | 0.2 | 5 | 5 | 1,000,000 |
| collimators and beam stoppers | 5 | 0.3 | 5 | 5 | 100,000 |
| all electronics modules | 3 | 1.0 | 10 | 10 | 100,000 |
| AC breakers < 500 kW | | 0.8 | 10 | 10 | 360,000 |
| vacuum valve controllers | | 1.1 | 5 | 5 | 190,000 |
| regional MPS system | | 1.1 | 5 | 5 | 5,000 |
| power supply - corrector | | 0.9 | 3 | 3 | 400,000 |
| vacuum valves | | 0.8 | 3 | 3 | 1,000,000 |
| water pumps | | 0.4 | 3 | 3 | 120,000 |
| modulator | | 0.4 | | 3 | 50,000 |
| klystron - linac | | 0.8 | | 5 | 40,000 |
| coupler interlock electronics | | 0.4 | | 5 | 1,000,000 |
| vacuum pumps | | 0.9 | | | 10,000,000 |
| controls backbone | | 0.8 | | | 300,000 |
| additional linac energy overhead | | | 3% | | 18 3% |

Downtime per ILC section



large contributions (>10%) from

- e⁺ source (transport line)
- e⁻ linac (split by undulator)
- damping rings
- cryo plant

Auxiliary e^+ Source

| positron source | ILC uptime |
|---------------------|------------|
| undulator | 69% |
| undulator+auxiliary | 78% |
| conventional | 80% |


undulator w/o aux. source leads to reduced uptime because of e^+/e^- arm coupling (recovery and machine development)

auxiliary positron source:


- stand-by conventional source of low intensity ($\sim 10\%$)
- 2h switch-over time
- required intensity driven by sensitivity of Beam Position Monitors

Example:

e^- damping ring failure:
without aux. source:



with aux. source:



Service Tunnel

for high availability need access to RF, modulators, power supplies, and electronics while linac is running

| Tunnel configuration | Simulated % time integrating luminosity under normal running conditions | Simulated % time integrating luminosity when commissioning* |
|---|---|---|
| a single tunnel without robotic repair | 64% | 25% |
| a single tunnel with robotic repair | 73% | Not simulated |
| two tunnels where the support tunnel is always accessible | 78% | 46% |
| two tunnels where the support tunnel is only accessible when the RF is turned off | 72% | Not simulated |

*MTBFs halved, required machine development time doubled

Service Tunnel

pros:

- significant increase in uptime, especially for commissioning
- (some) electronics do not have to be radiation-hard
- higher availability → shorter ILC running (save on running cost)

cons:

- **expensive to build:** increases total ILC construction cost by a few %
O(€100M)
- improved uptime can be achieved for 1 tunnel by additional redundancy
- service tunnel radiation-safe?
(radiation leaking in from main tunnel through connecting tunnels?)

Baseline: 2 tunnels (but still a debated subject)

decision might in the end depend on site location:

- local construction cost (tunnel depth)
- local safety regulations

Benchmarking

- simulation has built-in philosophies (e.g., recovery algorithm) based on SLAC experience
- no SLC operation data for comparison available (detailed log book)

Is the simulation close to reality?

→ 2 comparisons: HERA and PEP-II

focusing on:


assumption that recovery time proportional to time without beam

The largest contribution is from tuning of the IP region (=luminosity tuning) because both beams are needed.

HERA Comparison

ep storage ring,
DESY


time since
last collisions




HERA: No correlation

PEP-II Comparison


(J Nelson, SLAC)



e^+e^- storage ring, SLAC



PEP-II Comparison (J Nelson, SLAC)



no clear trend

Benchmarking Results

- no justification of tune-time proportionality from benchmarking
- simulation with fixed average tune-time is different:
Example: positron source comparison

| | Description | time integrating lum (%) | time scheduled MD (%) |
|---------------------------|---------------------------|--------------------------------|-----------------------------|
| proportional tune-time | conventional | 81.8 | 4.4 |
| | undulator | 68.1 | 12.0 |
| fixed tune-time | conv. fixed tune-time | 82.5 | 5.3 |
| | undulator fixed tune-time | 74.1 | 12.4 |

remaining difference due to machine development

Summary & Conclusions

- For the first time an accelerator is constructed with quantitative global availability assessment.
- Availability considerations have big (costly) impact on global ILC layout:
 - 2 tunnels favoured.
- Key components have to be made more reliable.
- Simulation must be improved, e.g., benchmarking suggestive of different recovery algorithm.

Downtime per ILC system

