

Design, construction and commissioning of a 15 kW CO₂ evaporative cooling system for particle physics detectors, lessons learnt and perspectives for further development

P. Tropea

J. Daguin, A. D'Auria, J. Godlewski, M. Ostrega, J. Noite, S. Pavis P.
Petagna, H. Postema, B. Verlaat, L. Zwalinski

TIPP2014 2-6 June 2014
Amsterdam

Content

- CO₂ evaporative cooling in HEP: why and how?
- The challenges for a “big system”
- The project strategy: full scale prototype @ TIF
- Design & construction of TIF plant
- Performances of the TIF system
- Lessons learnt & design changes to final system
- Possible scaling up strategy
- Conclusions

CO₂ cooling for particle physics detectors

Why?

High cooling efficiency & low material budget!



- large latent heat of evaporation (small thermal contacts)
- low liquid viscosity (small pressure drops=small pipes)
- high heat transfer coefficient & thermal stability
- operating temperature range (+20/-40°C)

Environment & cost

- Radiation hard
- Not electrically conductive, not flammable
- Environmental impact & cost much lower than any fluorocarbon!

How?

The 2PACL operating principle, born in Nikhef for AMS Tracker and LHCb Velo



CO₂ cooling in HEP applications

Numerous CO₂ cooling systems being designed & put in operation for HEP experiments @ CERN and other institutes

Ranges of evaporating T -40 to +15°C

Ranges of cooling power 100 W to 15 kW



Experiment	Project name	Operating Temperature	Cooling power
ATLAS	SR1	-30 C	2kW
	IBL	-40 C	2x3.3kW
CMS	TIF	-20 C	15kW
	Pixel phase 1	-20 C	2x15kW
General purpose ATLAS & CMS	CORA	-30 C	2kW
ATLAS & Belle	MARCO	-40 C	1kW
ATLAS & CMS & LHCb ILC-PPC	TRACI	-20/-30 C	100W

L. Zwalinski's talk
in this session


This talk

The CMS PIXEL Phase I upgrade

125 M silicon pixels (x2 wrt present)

- 4 Barrel layers
- 3 Forwards discs on each side

To be installed in 2016 – 2017
extended year end technical stop



MOTIVATION

On detector cooling requirements

Pipe wall max T = -15°C (-19°C out)

- Sufficient margin wrt -2°C on sensors, used for power calculations
- Sufficient margin on operation, i.e. away from CO₂ dryout

Independent T for FPIX and BPIX

Cooling power 15 kW

Barrel 6 kW + Forwards 3kW + Heat leaks along pipes 1÷2 kW + margin


CHALLENGES

- Most powerful system ever built with 2PACL operating principle
- -20°C evaporating T
- Full redundancy
- Fully proven system ready well ahead of the detector arrival

The project strategy

FULL BUILT-IN REDUNDANCY: 2 FULL POWER COOLING SYSTEMS (15 kW)


CMS Pixel CO₂ Cooling System



FULL SCALE PROTOTYPE BUILT & TESTED
IN ADVANCE: TIF



The TIF cooling plant

1 Plant, 1 Manifold, 1 Accumulator: modularity & accessibility (cold boxes)
Transfer lines between plant and accumulator: tri-axial vacuum insulated as in CMS environment



The construction


- Component specification:
-40 °C & 110 bar service pressure (proof testing @ 157 bar as per PED)
- Industrial standards: off the shelf components, proven tightness (welds or Swagelok VCR)
- Long term lifetime based on previous experience: LEWA membrane pump as on LHCb VELO cooling
- Strict QA on welds: 100% visual inspection, 10% X-rays



LEWA membrane pump

- 150 g/s liquid CO₂
- -40 to +15°C operating T
- Remote head
- Frequency driver (+Remote stroke adjustment)

The control system



Huge effort on standards common to all cooling & gas systems from the group, see also L. Zwalinski's talk in this session

- ETHERNET IP field network to connect independent system elements.
- Schneider PLC runs about 7 control loops, 180 I/Os
- User interface is based on a SCADA built on Siemens WinCC OA. The control software conforms to the UNICOS CPC6

Commissioning

Phase I


- Checkout
- Calibration of instrumentation
- Functional tests: component by component

Phase II: nominal performances

- Small dummy load (4x 2 kW)
- Stability of T varying flow or load nominal performances





Phase III: exploring the limits

- “Big” dummy load (15 kW)
- Stability of T varying flow, load: maximum performances & exploring the limits!



Accumulator performances

Phase I






Cooling spiral: coiled pipe inside the accumulator
The CO₂ vapour condenses around the pipe


Heat exchanger: Plate heat exchanger installed on top of the accumulator
The CO₂ vapour condenses inside the HEX

Membrane pump performances


Phase I



Nominal conditions: 1 cooling loop




4 parallel loops operation




Towards full performance validation

-20 °C setpoint




Phase III
15 kW dummy
load, 120 g/s flow
rate

+15 °C setpoint



Increasing power: -20°C, max flow



Phase III



What's next? Tomorrow...

Lessons learnt for final system

- Heat exchanger instead of spiral for accumulator: simplify design, accessible component
- Pump remote head: good choice! Add stroke adjustment for fine regulation instead of bypass valve (which are a nightmare)
- QA on welds: save time in verification applying a very strict welding procedure, quality improvements!
- Think about testing without detector: 15 kW dummy load into manifold



What's next? The day after tomorrow


- Present 15 kW cooling plant designed around largest single head pump from LEWA, no other similar pumps available on the market
- These pumps are available in 2 and 3 head version
- This would result in 30 kW and 45 kW plants
- Experience with TIF system design in close collaboration between detector and cooling team to be continued!

Modularity of systems
and collaboration
between teams are the
baseline for bigger
systems!



Conclusions

- TIF cooling plant has proven to be a great test bench to develop a new and big system
- The testing will now continue concentrating on the detector mock-up systems newly installed
- Lessons learnt from this project can be used further!
- Looking forward to the installation in CMS of the final system at the end of LS1



Backup


...

The CMS Pix phase I upgrade cooling

Today: liquid C_6F_{14}
 Low thermal capacity ($\approx 1 \text{ KJ.Kg}^{-1}.K^{-1}$)
 High density ($\approx 1,7 \text{ kg.l}^{-1}$)
 "Big" pipes (3.0 mm ID / 0.3 mm thick)


Tomorrow: evaporative CO_2
 Enhanced thermal capacity ($\approx 2 \text{ KJ.Kg}^{-1}.K^{-1}$)
 Lower density ($\approx 1.0 \text{ kg.l}^{-1}$)
 Much smaller pipes (1.6 mm ID / 0.05 mm thick)

Current BPIX Services





$\eta < 2.2$: weight = 16.9 Kg (3 layer)

Upgraded BPIX Services



$\eta < 2.2$: weight = 6.5 Kg (4 layer)




Barrel Pixel cooling details

Main Cooling Line	Main Mass Flow [g/s]	Detector Layer	Detector Cooling Loop	Mass Flow [g/s]	Irradiated Standby Power Operation (ISB) @ 15°C									Irradiated High Luminosity Power Operation (IHL) @ -20°C								
					Power [W]	Capillary ?P [bar]	Detector ?P [bar]	Return ?P [bar]	Detector ?T [°C]	Hotspot [°C]	Xout	Xdry	Xdiff	Power [W]	Capillary ?P [bar]	Detector ?P [bar]	Return ?P [bar]	Detector ?T [°C]	Hotspot [°C]	Xout	Xdry	Xdiff
+ZML1	2.91	Layer #1	L1D1PN	1.46	145.48	9.96	0.53	0.24	0.56	16.47	0.56	0.57	0.01	212.61	8.95	1.04	0.33	2.26	-16.11	0.51	0.65	0.14
			L1D2PF	1.46	145.48	9.96	0.53	0.24	0.56	16.47	0.56	0.57	0.01	212.61	8.95	1.04	0.33	2.26	-16.11	0.51	0.65	0.14
+ZML2	7.04	Layer #2	L2D2PN	3.52	224.13	7.50	2.46	0.59	2.14	18.15	0.35	0.36	0.01	278.49	6.68	2.62	0.84	4.93	-13.24	0.27	0.49	0.22
			L2D1PF	3.52	224.13	7.50	2.46	0.59	2.14	18.15	0.35	0.36	0.01	278.49	6.68	2.62	0.84	4.93	-13.24	0.27	0.49	0.22
+ZML3	8.40	Layer #3	L3D2PN	2.10	184.50	9.41	1.33	0.33	1.23	16.96	0.49	0.52	0.03	221.47	8.43	1.75	0.50	3.04	-15.74	0.37	0.62	0.25
			L3D3PF	2.10	184.50	9.41	1.33	0.33	1.23	16.96	0.49	0.52	0.03	221.47	8.43	1.75	0.50	3.04	-15.74	0.37	0.62	0.25
			L3D4PN	2.10	175.41	9.50	1.30	0.33	1.18	16.90	0.47	0.52	0.05	210.97	8.51	1.67	0.51	2.91	-15.89	0.35	0.63	0.28
			L3D1PF	2.10	175.41	9.50	1.30	0.33	1.18	16.90	0.47	0.52	0.05	210.97	8.51	1.67	0.51	2.91	-15.89	0.35	0.63	0.28
+ZML4	7.72	Layer #4	L4D1PN	1.93	177.54	9.43	1.79	0.31	1.63	17.27	0.51	0.55	0.04	204.35	8.49	2.15	0.47	3.85	-15.06	0.37	0.66	0.29
			L4D4PF	1.93	177.54	9.43	1.79	0.31	1.63	17.27	0.51	0.55	0.04	204.35	8.49	2.15	0.47	3.85	-15.06	0.37	0.66	0.29
			L4D3PN	1.93	169.41	10.08	1.40	0.30	1.30	17.00	0.49	0.54	0.05	195.23	9.06	1.68	0.45	3.17	-15.72	0.35	0.65	0.30
			L4D2PF	1.93	169.41	10.08	1.40	0.30	1.30	17.00	0.49	0.54	0.05	195.23	9.06	1.68	0.45	3.17	-15.72	0.35	0.65	0.30
-ZML1	5.35	Layer #1	L1D2MN	2.67	187.92	9.15	0.93	0.42	0.88	17.06	0.39	0.39	0	277.89	8.19	1.29	0.78	3.14	-14.64	0.36	0.49	0.13
			L1D1MF	2.67	187.92	9.15	0.93	0.42	0.88	17.06	0.39	0.39	0	277.89	8.19	1.29	0.78	3.14	-14.64	0.36	0.49	0.13
-ZML2	4.92	Layer #2	L2D1MN	2.46	199.50	8.57	1.78	0.44	1.63	17.48	0.45	0.47	0.02	247.95	7.70	2.19	0.66	4.14	-14.33	0.35	0.58	0.23
			L2D2MF	2.46	199.50	8.57	1.78	0.44	1.63	17.48	0.45	0.47	0.02	247.95	7.70	2.19	0.66	4.14	-14.33	0.35	0.58	0.23
-ZML3	8.41	Layer #3	L3D1MN	2.10	157.23	9.72	1.21	0.31	1.10	16.75	0.42	0.54	0.12	189.95	8.69	1.53	0.46	2.63	-16.30	0.31	0.65	0.34
			L3D4MF	2.10	157.23	9.72	1.21	0.31	1.10	16.75	0.42	0.54	0.12	189.95	8.69	1.53	0.46	2.63	-16.30	0.31	0.65	0.34
			L3D3MN	2.10	189.95	9.42	1.33	0.34	1.22	16.97	0.49	0.52	0.03	221.47	8.44	1.74	0.53	3.04	-15.70	0.37	0.62	0.25
			L3D2MF	2.10	189.95	9.42	1.33	0.34	1.22	16.97	0.49	0.52	0.03	221.47	8.44	1.74	0.53	3.04	-15.70	0.37	0.62	0.25
-ZML4	7.14	Layer #4	L4D2MN	1.78	169.41	9.77	1.33	0.29	1.25	16.94	0.53	0.56	0.03	195.23	8.82	1.65	0.44	3.12	-15.78	0.38	0.66	0.28
			L4D3MF	1.78	169.41	9.77	1.33	0.29	1.25	16.94	0.53	0.56	0.03	195.23	8.82	1.65	0.44	3.12	-15.78	0.38	0.66	0.28
			L4D4MN	1.78	161.29	9.84	1.29	0.28	1.21	16.88	0.51	0.57	0.06	186.12	8.89	1.58	0.42	2.97	-15.97	0.36	0.67	0.31
			L4D1MF	1.78	161.29	9.84	1.29	0.28	1.21	16.88	0.51	0.57	0.06	186.12	8.89	1.58	0.42	2.97	-15.97	0.36	0.67	0.31

TOTAL 51.88 4283.54

5283.47

Single loop performances



T set point change at full power!

Phase III

