



**CNGS target operation and
modified design**

*8th International Workshop on
neutrino beams & instrumentation
(NBI2012) 6th-10th November 2012*

M. Calviani

Acknowledgments


- ▶ The present talk is based on the work of many people at CERN, which were involved in the conception/design/operation of the CNGS target
- ▶ L. Bruno, D. Grenier, O. Aberle, A. Ferrari, P. Sala, R. Losito, C. Maglioni, M. Delonca, A. P. Bernardes, N. T. Vuong, M. Meddahi, K. Cornelis, K. Elsener, E. Gschwendtner, J. Wenninger, I. Efthymiopoulos, CRS4, and many others.


- ▶ Introduction to beam parameters
- ▶ Review of CNGS target design
- ▶ Selected issues encountered during the operation of the CNGS target
- ▶ Preparation of the CNGS spare target
- ▶ Conclusions

- ▶ **400 GeV/c** primary beam momentum, 2 fast extraction every 6 seconds
- ▶ Nominal beam intensity **$2 \times 2.4 \times 10^{13}$ p+/pulse** in **10.5 μ s**, interleaved by **50 ms**
 - ▶ Ultimate beam intensity $\sim 2 \times 3.5 \times 10^{13}$ p+/pulse
- ▶ Nominal beam power **~ 500 kW**
 - ▶ Ultimate beam power ~ 750 kW
- ▶ $1 \sigma_{x,y}$ beam on target: **0.53 mm**
- ▶ Beam divergence at focal point: $0.053(\sigma_x) - 0.03(\sigma_y)$ mrad

Review of the CNGS design

- ▶ The CNGS target unit is conceived as a **static sealed system filled with 0.5 bar of He**
 - ▶ 130 cm long graphite target ($\sim 3 \lambda_L$)
 - ▶ Cooling of target rods by **radiation** towards the Al tube and partly by **convection**
 - ▶ Target revolver flushed with air which keep Al temperature $< 100^\circ\text{C}$





- ▶ Tube has **annular fins** to enhance the convective heat transfer
 - ▶ Ni-coated Be window (380/630 μm), e-welded to Al
- ▶ **Target rods** installed on a **carbon support structure** with holes in order to increase the thermal exchange





5 UNITS ARE INSTALLED IN A SINGLE MAGAZINE

1. **Graphite** target with baseline geometry under **He**
 1. 2020PT Carbone Lorraine
 2. Best understood carbon ($\rho=1.76 \text{ g/cm}^3$) → **standard target**
2. **Carbon** target with baseline geometry under **He**
 1. Sintered carbon SC24 by Sintec Keramik
3. **C-C composite** target with baseline geometry under **He**
 1. Aerolor A035 Carbone Lorraine
4. **Graphite** target with baseline geometry under **vacuum**
 1. 2020PT Carbone Lorraine
 2. Vacuum for possible concern of stress cycling on the Be windows from thermal expansion of gas
5. **“Safe” target**: graphite target with all 5 mm diameter rods under He


CNGS target unit as built

- ▶ 5 units (1 active + 4 in-situ spares) are hosted in a target magazine
- ▶ An additional spare magazine is available




$T_{\text{graphite}} \sim 990 \text{ }^{\circ}\text{C}$
 $T_{\text{C-C}} \sim 375 \text{ }^{\circ}\text{C}$
 $T_{\text{He}} \sim 365 \text{ }^{\circ}\text{C}$

Target assembly and shielding cooling




- ▶ Two air streams in the TS, not affected by each other (3600 m³/h)
 - ▶ Vertical airflow parallel to the fins of the target assembly → **TARGET**
 - ▶ ~6 kW to evacuate
 - ▶ $T_{av} = 85/93.5 \text{ } ^\circ\text{C}$
 - ▶ Horizontal airflow parallel to the fins of the shielding → **SHIELDING**
 - ▶ ~15 kW (~13 kW side wall shielding)
 - ▶ $T_{avsh} = 40-300 \text{ } ^\circ\text{C}$




CNGS Target Assembly
CFD Cooling and Ventilation Simulation
linear inlet flow

Target unit as built and installed in CNGS



Stresses on the CNGS target rods


- ▶ Critical point in the design for CNGS was the **resistance to off-axis beams**
 - ▶ Worst loading (1.5 mm OA, ultimate intensity, cold target, no damping)
 - ▶ Temperature increase & boundary conditions → dynamic stresses on rods → rapid transversal vibration
 - ▶ Stassi ratio **always lower than 0.7 for a single bunch**




- ▶ Effect of the 2nd extraction:
 - ▶ Time for equilibrium > bunch spacing → 1st bunch effect still present when 2nd bunch comes
 - ▶ ~32 Mpa at 1.5 mm OA → **Stassi ratio 0.89**

- ▶ Cumulated POT on target up to now: **$1.76 \cdot 10^{20}$ POT**
 - ▶ **~1.5 DPA** expected (averaged around 0.3 mm) at the end of 2012 for the first three rods

- ▶ Operation at high temperature:
 - ▶ Minimization of shrinkage and reduction of thermal conductivity
 - ▶ Favour annealing and reduction of imperfection




Target rotation system failure




- ▶ 2009: unexpected **increased torque in the magazine rotation motor**
- ▶ April 2009 → in-situ inspection of the target via remote-controlled webcam endoscopy
- ▶ All bearings has signs of **rust**, now all of them **do not move**
 - ▶ Measured torque of $\geq 30 \text{ N}^*\text{m}$ vs. design value of $8 \text{ N}^*\text{m}$

Bearing irradiation and observation



- ▶ Original bearings:
 - ▶ Martensitic SS440C (inner and outer races)
 - ▶ Martensitic SS X46Cr13 (balls)
 - ▶ **Tested at CNGS during 2009/2010**




- ▶ Significant **rust/pitting corrosion** present (10 N*m estimated torque)
- ▶ Low grade of X46Cr13 likely the cause of observed failure (no alloying elements, low Cr/high C content)
- ▶ **Ceramic ($\text{Si}_3\text{Ni}_4/\text{ZrO}_2$) bearings presently under test**



- ▶ Two runs with **LHC-type bunches** has been performed:
 - ▶ CNGS-type beam: 2100 bunches @ $1 \cdot 10^{10}$ p/bunch, 5 ns bunch spacing, 2 extraction (50ms)
 - ▶ LHC-type beam: 16 bunches @ $1 \cdot 10^{11}$ p/bunch, 100 ns bunch spacing, 4 batches
- ▶ Thermo mechanical analysis proven that:
 - ▶ Batch spacing has no significant effect on the target cooling
 - ▶ Bunching/batching structure has no effect on the wave propagation and on the quasi-static stresses




Max ΔT (instantaneous) ~ 45 K




Max ΔT steady state ~ 114 K

Preparation of a CNGS spare target

- ▶ During the study of the bunched beam operation we started worrying about the **status of the target**
 - ▶ The **same since first beam in 2006** (6 years of running)!
 - ▶ Corrosion of ball bearings for the magazine rotation **do not allow anymore to user the spare targets**: 4 magazine lost!
- ▶ Needed to guarantee **whole 2012 operation!**
- ▶ Preparation of the **spare CNGS target**:
 - ▶ Installation of a single magazine
 - ▶ Completely remote installation





CNGS spare target



CNGS spare target ready for installation

©D. Grenier (EN/STI)

CNGS spare target



- ▶ New CNGS spare target – completely **remotely handled**

- ▶ Spallation reactions in C: production of variety of particles including ^1H , ^2H and ^3H
 - ▶ The least energetic can stop in the target giving rise to an **hydrogen build-up**
- ▶ FLUKA simulations: for $1.2 \cdot 10^{20}$ POT \rightarrow **$3.5 \cdot 10^{21}$ H** atoms produced up to know (safety factor 2/3x)
- ▶ Assuming all H atoms desorbed from target solid structures:
 - ▶ **~65-195 ml** of atomic H at atmospheric pressure
 - ▶ **~0.4-1.1% H_2** in the target box
 - ▶ Target pressure ~ 1.2 bar during operation
 - ▶ Max resistance of Be windows at the extremities ~ 2 bar

Explosion risk analysis

- ▶ During **operation**:
 - ▶ Overpressure in case of explosion remains quite low (~2-3 bars)
 - ▶ Risk real only in case of a dramatic failure of one window
 - ▶ Spread of contaminated powder in close vicinity (horn?)

- ▶ During **maintenance**:
 - ▶ The low temperature reduce the risks and the associated overpressure
 - ▶ No special precautions needed





Figure 1. Influence of the temperature on the explosion limits of hydrogen-air mixtures, measured at atmospheric pressure according to DIN 51649 [8]

Failed Be window picture

- ▶ No analysis done for the moment due to the very high residual dose rate



- ▶ **CNGS target successfully operating since 2006**
 - ▶ It has received up to $1.76 \cdot 10^{20}$ POT up to now, out of the approved $2.25 \cdot 10^{20}$ POT – no target exchange needed
- ▶ Target design has drawn experience from past CERN fixed targets, with **increased challenges due to high proton beam power** (750 kW \rightarrow 1.5 MW possible)
- ▶ Operational issues encountered in operation are similar to those observed at other high power neutrino facilities
- ▶ A **spare target has been prepared** in case of a possible target failure – complete remote handled
 - ▶ Useful experience for future new targets