

LHC Superconducting Cavities

P. Maesen

CWRF2008, 25 March'08




Content




- Presentation
- Building
- Low level & full power tests
- Problems
- Installation in LHC PT 4
- Commissioning
- Status & conclusions



Presentation



- Module main parameters
 - 4 single cell cavities Cryo-module
 - Modular design from 2 to 6 cavities
 - Cell-to-cell distance $3\lambda/2$ at 400 MHz
 - 3 main He connections : L He inlet, gas outlet and warm recovery line
 - Cone extremities He capillaries
 - Temperature probes redundancy
 - 150 W static losses at 4.5 Kelvin
 - 2 ion pumps at each ends with vacuum valves
 - Second beam tube inside cryostat, 420 mm spacing






Presentation




- Cavities main parameters
 - 1-2 μm Niobium film sputtered on 3 mm Co Cavity
 - Cavity length $\lambda/2$
 - $R/Q = 44 \Omega$, 300mm diameter beam tube
 - Acceleration field : 1 MV at injection & 2 MV at high energy
 - 300 kW CW Main Coupler with polarization, variable antenna length : $10000 < \text{Ext } Q > 200000$
 - External tuner motor, range 400.790 MHz \pm 90 kHz
 - 4 SC HOMs of 2 types ; dipole and broad band
 - 80 liters of L He at 4.5 Kelvin in He tank
 - He dome for safety valve & He level probe


Building



- Copper 400 MHz single cell cavity
 - 4 HOMs



- In its He tank
 - Vapor / liquid separation vessel




From bare Co cavity :


- Chemical treatment, rinsing
- Niobium sputtering
- Pure water rinsing
- Cavity validation in vertical cryostat by measurement of Q/Eacc. Half of them with He processing
- He tank welding
- Mounting in frame
- Tuning by plastic deformation
- Vacuum tightness



Building



- Assembling 4 Cavities and accessories in Clean Room



Low level & full power test




- Transfer of modules to radiation safe bunker
- Connections with cryogenic, RF, controls, e- stoppers

RF From
Klystron

He gas
return

Wave
Guide



Electron
Stopper



Low level & full power test



- Module Cool down in SM18
 - Measurement of frequency and tuner range




- Q ext versus power coupler position
- Calibration of antenna signal




Low level & full power test

- Conditioning to coupler full power 300kW CW.
- Raising acceleration field to 1.5 times nominal






Low level & full power test




- Dipole Mode (TE111) HOM damping efficiency




Low level & full power test



- Broad-band HOMs for higher modes



Problems




- Tuning range: too high natural frequency of half of the cavities
 - Despite warm plastic deformation, after a series of thermal cycling, some of the cavities went back to a too high frequency at rest



- Corrected by adjustable tuning springs compensation

Problems



OUUUUPS !


- Broken Tuner bellow during tests
 - Due to bad design
 - Found good ones certified by life test
 - Replaced just in time

Please don't
look here !

Fatigue break
down

- He domes to be modified
 - Old LEP design
 - Modified by longer tubing and replacing several seals by welding





QRL Extension

3 modules in
LHC PT 4




Commissioning



- Interlocks full check (4weeks)
 - 300 kW main coupler very sensible !
 - Remember : in case of ceramic break down, pollution of the whole module to be replaced !
 - Fast RF shut off with vacuum increase, arc detectors, He pressure, RP alarm, RF zone access etc.
- Careful setting up of cryogenic processes (2w)
- Modules cooling down (24hrs)
 - But lost already 4 times all the He through safety valves !



Commissioning



- Conditioning
 - On one module, almost no degassing, just a few quenches, 2 min for recovering
 - On the other one, 1 week of conditioning per cavity
 - Parallel operation, 16 klystrons for 16 cavities
- Low level tuning and amplitude loops closed
- As well as Klystron polar loop


SUCCESS



Commissioning




Remote conditioning
up to 2 MV





Status & conclusions



- 4 Modules installed in LHC PT4 Sept '06
- Fully connected mid '07
- Cool down of 2 Modules Nov '07
 - Special care on cryo safety devices & process control
 - Successful validation in full power and field Feb '08
 - Modules warm now with sector 4-5 for Triplets
- Cool down of the 2 other ones foreseen June '08
- Beam commissioning ..'08



Acknowledgement



- All AB/RF group members participating
- AT/ACR , AT/VAC and TS/RP
- AB/ATB group, Transport
- Enrico Chiaveri, Oliver Aberle, Raymond Hanni and Roberto Losito

REFERENCES

- D. Boussard et al., "The LHC superconducting cavities", PAC'99, New York, 1999.
- R. Losito, E. Chiaveri, J. Tuckmantel, S. Calatroni, D. Valuch, "Report on Superconducting RF Activities at CERN in 2001/2003", SRF Workshop 2003
- E. Montesinos, "Construction and Processing of the Variable RF Power Couplers for the LHC Superconducting Cavities", SRF 2007
- L. Arnaudon, M. Disdier, P. Maesen, M. Prax "Control of the LHC 400 MHz RF system (ACS)", EPAC'2004, Lucerne, Switzerland, July 2004.
- E. Haebel, V. Rodel, F. Gerigk, CERN, Z.T. Zhao, IHEP, Beijing, P.R. China "The Higher-Order Mode Dampers of the 400 MHz Superconducting LHC Cavities", CERN-SL-98-008 RF.
- S. Claudet, et al.. "The cryogenics system in pt 4: possible options", LHC Project Workshop Chamonix XIV, CERN, Geneva, Switzerland, 17-21 Jan 2005.
- P. Maesen, E. Ciapala and G. Pechaud, "Final tests and commissioning of the 400 MHz LHC superconducting cavities", SRF 2007