


## The ATLAS barrel and end-cap SCT commissioning at CERN


1. Goals of the SR1 commissioning
2. The SR1 assembly area and infrastructure
3. Barrel reception
  - a) Individual barrel studies
4. Barrel integration and combined tests
  - a) Barrel SCT integration steps - insertion into the TRT
  - b) Combined studies of the SCT-TRT
  - c) The barrel SCT-TRT in ATLAS and future steps
5. The SCT end-cap assemblies
  - a) Individual EC-A and EC-C studies
  - b) Integration into their thermal enclosure
  - c) Future studies
6. Conclusions and next steps

A. Clark, SCT subsystem, ATLAS Collaboration  
6th "Hiroshima" Symposium, Carmel, 11-15 September, 2006

(see other talks by M. Tyndel and U. Parzefall)



# The ATLAS Inner Detector





**Forward (Endcap):** 2 x 9 disks  
 1976 wedge-shaped modules  
 4x132, 4x92 and 1x52 Si modules.  
 1976 wedge-shaped modules  
 Strip pitch ~ 80 $\mu$ m.

**EC-A assembled NIKHEF  $\Rightarrow$  SR1**  
**EC-C Liverpool  $\Rightarrow$  SR1**

**4 barrels - 384, 480, 576 & 672 modules  
 Si modules. Each module has 4 single-  
 sided p-in-n detectors, ~ 64mm square  
 768 strips @ 80 $\mu$ m.**

**Barrels assembled  
 in Oxford  $\Rightarrow$  SR1**



# 1. Goals of the SR1 commissioning

## Detector tests/ integration

Reception tests of barrels and end-caps

SCT standalone tests

- Online checks (eg. SCT characterization, pickup test,...)

Complete integration of barrels and EC

Combined noise and X-talk tests

- Common TDAQ readout of SCT and TRT
- Noise tests within SCT and on SCT from TRT
- Testing with the heater system and cooling operational
- Feedback of readout cycle to FE noise

Cosmic ray studies

## Learning to operate the detector

Operation

- Run infrastructure requirements (e.g. detector cooling, PS, environmental)?
- Cooling performance
- Startup, operation, hardware monitoring procedures
- Monitoring

DAQ

- Change standalone operation  $\Rightarrow$  combined readout
- Synchronization issues, data handling
- Tools for monitoring, detector timing, etc.


DCS

- Supply system *operation and stability* (PS, cooling, gas, environmental, ...)
- **Learning what needs to be improved & debugged** (e.g. C3F8 filters, reliability, safety ...)

Lead by H. Pernegger with R. Apsimon, T. Jones, N. Hessey + many others  
AUS, CH, CZ, D, ES, JP, NO, NL, PL, SW, SLO, UK, US



## 2. The SR1 Cleanroom test facility at CERN



**600 m<sup>2</sup> cleanroom  
~ Class 2000**

- 1: External area for electronics racks, LV+HV power, ROD readout (up to 55 racks)
- 2: Control room (2a), workshop (2b)
- 3: SCT test enclosure. Test ~ 700 modules (~ 10<sup>6</sup> channels) simultaneously
- 4: Pixel assembly area (now expanded)
- 5: Large space for 4-barrel assembly, EC-A, EC-C tests
- 6: TRT Endcap assembly and testing
- 7: TRT Barrel assembly and testing
- 8. Evaporative cooling plant



**Transport - lesson - outstanding success**

- a) Environment controlled, air-sprung
- b) Spring suspension, nested containers
- c) Monitor  $x, y$  &  $z$  acceleration, temp, RH%, pressure




### 3a: Reception Tests at SR1 for each Barrel and End-cap

EC-C at SR1



Barrel 6 at SR1 -14.6.05








Item	Delivery	Reception tests
Barrel 6	6.2005	(Oxford)
Barrel 5	7.2005	CERN
Barrel 4	8.2005	(Oxford)
Barrel 3	1.2005	CERN
EC-A (NL)	21.4.06	22.06.06
EC-C (UK)	23.2.06	24.03.06

#### Reception tests include:

- Full visual inspection and photographic summary, check for component movement
- Leak test and repair of all cooling circuits
- Full “continuity check” of all modules
  - confirms module functionality (not analogue performance)
- Alignment check of all disks (forward)
- Limited cold tests -  $\sim 10^{\circ}\text{C}$  or  $-12^{\circ}\text{C}$  coolant at CERN, colder at assembly sites
- *Comparison with data at assembly site*



### 3b. Reception Tests at SR1 for each Barrel and End-cap




**Example: Barrel services**

- power services
- cooling
- optical readout
- DCS



### 3c. Individual Tests at SR1 for barrels 3 and 5



#### Infrastructure:

1. SR1 test enclosure
2. Evaporative cooling
3. HV +LV power and readout for 700 modules
4.  $10^6$  channels read out, dew point  $< -40^\circ\text{C}$ .
5. - “Final” Detector Control System (DCS)  
- “Final” detector readout, including full opto-readout  
- “Final” DAQ

#### Basic Electronic Tests

- Establish Communication, optimise Opto settings

#### Digital Electronic Tests

- Verify Communication

#### Analogue Electronic Tests

- Measure Gain, Offset, Noise, Noise Occupancy
- Look for Time Structure
- Detect excess noise possibly related to high frequency, synchronous triggers

**Module supply and sensor currents (an issue)**

Module temperatures and other DCS monitoring




### 3d. Individual Tests at SR1 for barrels 3 and 5.




Test of individual cooling loops - DCS

Temperature map for Barrel 3



2-d map of mean module temperatures for B3



Temperature Profile for B3



B3 temperature profile along stave from entry to exit averaged over all staves.



### 3e. Individual Tests at SR1 for barrels 3 and 5.



Barrel	Total Channels	Not bonded	Dead	Not Reachable	Part bonded	Noisy	Other	Total Defects
3	589824	180	357	384	91	460	11	1483
4	737280	55	245	256	16	242	27	841
5	884736	173	770	256	97	492	30	1818
6	1032192	385	2513	640	197	1936	49	5720
<b>Total</b>	<b>3244032</b>	<b>793</b>	<b>3885</b>	<b>1536</b>	<b>401</b>	<b>3130</b>	<b>117</b>	<b>9862</b>

**99.8% working channels**



## 4a. 4-barrel integration




**B6 ⇒ thermal enclosure - 22.7.05**

**B5 ⇒ B6 + thermal enclosure - 12.8.05**

**B4 ⇒ B5 + B6 + thermal enclosure - 06.9.05**

**(not shown)**



**B3 ⇒ B4-6 + thermal enclosure - 20.09.2005**

*Started after Barrel 6 tests*



## 4b. 4-barrel integration

Service time dominated by service handling

~ 10% inserting

~ 60% moving services and cooling capillaries at end of barrels - risks+ lessons



~ 30% sealing thermal enclosure bulkheads

<b>Barrel ends assy</b>	Days			Days	
Mount final Interlinks (in parallel)	1		Mount pixel supports	0.5	23.5
Remove kapton tape from LMTs (200mm)	2	2	Mount handling points	0.5	24
Check harness pairs are correct	0.5	2.5	Survey barrel ends	1	25
Label each harness pair	0	2.5	Try Pixel master jig	1	26
Check & label the R/O fibre bunches	0.5	3	Take footprint of Pixel supports	3	29
Checkrouting of DCS wire bunches	0	3	Mount ITE/seal penetrations	1	30
Check & label capillaries	0.5	3.5	Mount, connect Cooling Ref Disc (CRD)	2	32
Seal LMTs into grommets	5	8.5	Mount and seal end covers	1	33
Mount central part of bulkhead	0.5	9	Sub Total	33	
JST crimps heater cables (in parallel)	2		Test the Thermal Enclosure	2	35
Seal opt. fibers into grommets	2	11	)		
Seal DCS wires	1.5	12.5	<b>Prepare SCT for insertion</b>		
Set capillaries to HEX models	1	13.5	Mount the reinforcement rings	0.5	35.5
Seal capillaries into grommets	1	14.5	Mount the ISSS	1	36.5
Bend & insulate capillaries	2	16.5	Arrange services for insertion	5	41.5
Mount exhaust spiders	2	18.5	Check envelope	0.5	42
Leak test cooling spiders	2	20.5	Dismount service support wheel	0.5	42.5
Mount N2 supply /exhaust pipes	0.5	21	Prepare cradle for "travel"	0.5	43
Mount and seal rear part of bulkhead	1	22	Sub Total	8	
Mount additional TE ext. Temp DCS sensors	1	23	Total	43	


(from R. Apsimon / H. Pernegger)



## 4c. Integrating the SCT and TRT barrels - 17.02.2006



**Integration and cabling for combined tests of SCT and TRT (next slide)**



### Detector connection:

- ◆ TRT power, readout cables, gas/cooling
- ◆ Heat spreader between SCT , TRT services
- ◆ Fold out SCT services +connection + leak test (LMT->Cooling->fibres)

### Cleanliness:

- ◆ Fibres and capillaries

### Reliability:

- ◆ **4 of 88 harnesses required repair**

Time: ~ 5 weeks for 1/8 TRT + 1/4 SCT


- ◆ Including time to resolve minor problems



## 4d. Combined barrel SCT+TRT test - *goals*

**SCT (468 modules) - readout 12 ROD, 1 TIM, 1 LIP**

View from outside  
towards Side A



**3 trigger scintillators**

**TRT - 2 x ~ 6600 channels (1/8 TRT) 9 ROD readouts**

*Important experience for preparation for pit installation  
(discuss only SCT aspects)*

**Operation:**

- Experience of detector operation
- Test detector supply systems
- Development of standalone & combined monitoring tools
- Commission and test combined readout and trigger
- Commission offline SW chain

**Detector performance:**

- Test 4 SCT barrels together
- Operation with TRT
- Grounding for SCT and TRT
- Synchronous operation
- X-talk and noise

*Collect cosmics for efficiency & tracking studies*




## 4e. Combined barrel SCT+TRT test - DCS issues

### DCS crucial to reliable and safe operation - an essential test bed

- Cooling system monitoring
- Environmental monitoring
- PS control and monitoring
- Interlock safety system
- Startup procedure defined
- Implementation of FSM and latest PVSS ongoing
- Database issues - DCS configuration, conditions - much to do
- Archiving into COOL (read by Athena)
- Learn what needs to be improved (e.g. mandatory filter cooling)

Significant experience and improvements made - both control and monitor functions



## 4f. Combined barrel SCT+TRT test - DAQ

### Multi-ROD Crate (not yet multiple crates)

- TRT uses RodCrateDaq
- SCT uses SCTDAQ

### DAQ event building

### SCT uses Slink based readout


- 12 ROD/BOCs in 1ROD crate)
- 3 FILARs (12 Slink channels) in 1 ROS

### TRT uses VME-ethernet based readout

- 2 ROD Crates: 6&3 RODS inside

### Exercised full functionality of calibration and data collection

*ongoing - much experience*



### Issues include

- Synchronisation
- Monitoring
- Start of run issues (data base)

### Data base issues important

- SCT and TRT conditions data bases
- SCT and TRT configuration data bases
- Start of run issues
- Reliability


Transition	SCT	TRT	Monitor
Boot	O(1min)	O(10sec)	O(1.5min)
Configure	O(2min)	O(10sec)	O(2min)
Start	O(10sec)	O(10sec)	O(30sec)

e.g. start of run timing



## 4g. Combined barrel SCT+TRT test - monitoring

- Detector specific histograms +
- 1) monitor synchronization of LVL1 and BC IDs of different detectors
  - 2) monitor hits for any track collection, calculate residuals etc
  - 3) monitors matching of TRT and SCT segments




Developed for TRT, SCT also inserted





## 4h. Combined barrel SCT+TRT test - module timing with cosmics





Timing coincidence  
between module sides  
for each module  
(BOC Tx coarse scan (32 bcos))



## 4i. Combined barrel SCT+TRT test - SCT noise


- First full test after 4-barrel assembly
- Number of extra defects found in tested sectors):
  - 4 interrupted LMT lines - repaired
  - 3 of 468 modules with opto anomalies (redundancy, no channels lost)
  - 2 non-readable FE chips (dead Vcsel?)
- **Functional channels ~ 99.8% (+0.03%)**
- Noise threshold and occupancy scans made:
  - with/without TRT
  - as function of trigger rate
  - with/without cooling and heaters
  - with different grounding schemes
  - effect of noise in adjacent time slots
  - Possible common mode effects
- **No evidence of increased noise in any tests**



Run 3102	Top	Bot
B3	$4.56e-5$	$4.14e-5$
B4	$3.41e-5$	$4.03e-5$
B5	$4.17e-5$	$4.27e-5$
B6	$6.63e-5$	$4.95e-5$



## 4j. Combined barrel SCT+TRT test - cosmic tracks




~ 450K events recorded


**Full ID reconstruction chain tested with cosmics**

- Final data decoding in place
- Tracking with no vertex constraint
- Extensive use of information from ConDB
- Fixes in SCT detector description done

Cosmic simulation also available



## 4k. Combined barrel SCT+TRT test - SCT performance



### Simulation:

- Perfect alignment:  $\mu \sim 0 \mu\text{m} \Rightarrow \sigma = 55 \mu\text{m}$


### Expected precision:

modules: 100  $\mu\text{m}$  ( $r\phi$ ,  $z$ ), 500  $\mu\text{m}$   
 Barrels: 100  $\mu\text{m}$  ( $r\phi$ ,  $z$  and  $R$ )



- Overall efficiency > 99% (in spec)
- Resolution better than obtained with the expected level of misalignment
- Alignment studies ongoing - promising results

## Preliminary


### SCT efficiency per layer (average per side)



## 4I. Installation of ID - 24-25.08.2005



## 4m. Installation of ID - 24-25.08.2005





**Next challenges:**

- service connection,
- repeat noise studies
- cosmic studies
- understanding/operation



## 5a: End Cap: EC-A and EC-C integration and studies

- A. Arrival and Reception Tests
- B. Final Assembly Stage
  - Preparing and fitting Rear Support
  - Transfer to cantilever stand
  - Move to integration position
  - Fit Inner Thermal Enclosure (ITE)
  - Seal ITE and fit front membranes
  - Complete services feed through area
  - Transfer weight of EC to stand
  - Fit Outer Thermal Enclosure (OTE) including heaters etc.
- C. Testing inside Thermal Enclosure
- D. Integration with TRT
- E. Combined Testing with TRT



## 5b: End Cap: EC-A and EC-C integration and studies

Task	EC-C	EC-A
A. Arrival and Reception Tests	23 <sup>rd</sup> Feb (Lvpl)	21 <sup>st</sup> Apr (Nikhef)
B. Final Assembly Stage <ul style="list-style-type: none"> <li>- Preparing and fitting Rear Support</li> <li>- Transfer to cantilever stand</li> <li>(- Investigation of electrical problems)</li> <li>- Move to integration position</li> <li>- Fit Inner Thermal Enclosure (ITE)</li> <li>- Seal ITE and fit front membranes</li> <li>- Complete services feed through area</li> <li>- Transfer weight of EC to stand</li> <li>- Fit Outer Thermal Enclosure (OTE)</li> </ul>	done ↓	done ↓ ongoing ↓
C. Testing inside Thermal Enclosure <ul style="list-style-type: none"> <li>- Leak tightness, octant with cooling</li> </ul>	ongoing-1st results	
D. Integration with TRT - ~5 weeks	mid-Sept (28.09.06)	~ mid-Oct
E. Combined Testing with TRT	mid-Oct	~ mid-Nov






## 5c: End Cap: EC-A and EC-C - reception tests

- Comparison of digital and analog tests with assembly lab
  - ◆ Noise
  - ◆ Gain
  - ◆ Offset
  - ◆ Nmask, pipeline, bypass etc.
  - ◆ Bad channels
  - ◆ Module currents, high voltage behavior  
(CIS modules in general OK up to ~250V)
- Performance was seen to be the same as before shipping:

EC-C, disk 3, quadrant 1



Unlike EC-C, EC-A had all modules tested cold during the reception tests:



## 6: Conclusions and Outlook

### Conclusions:

- ◆ Work continuing
- ◆ Many small problems found, but no accidents, no show-stoppers
- ◆ Enormous task ahead and operation in pit next major challenge

### Outlook Barrel SCT

- ◆ Expect ~35 days to cable TRT and ~75 days to cable SCT in pit
- ◆ To be followed by full continuity tests, cooling tests
- ◆ Then full functionality tests on all SCT modules (“warm”?) from ~01.07
- ◆ To be followed by cosmic ray studies - ID then ID+CAL

### Outlook Endcap SCT - EC-A and EC-C

- ◆ Integration SCT-TRT
  - EC-C 09.06 - 10.06
  - EC-A 10.06 - 11.06
- ◆ Combined SCT-TRT tests
  - EC-C mid 10.06 - end 12.06
  - EC-A mid 11.06 - end 01.07
  - Tests will be made in parallel using independent setups
  - Will use 1/4 of SCT, 1/12 of TRT
- ◆ Expect transfer to pit from ~end 01.07 with functional tests from ~04.07



## Backup Slide- List of observed anomalies

### ■ DAQ

- ◆ SCT opto setting needed more frequent adjustment then expected
- ◆ 3 channels return “000” hits occasionally
- ◆ Desynchronizations in sub-detector readout

### ■ DCS and supply systems

- ◆ Hardwired interlock system implemented for TRT in SR after cooling incident + modified TRT DCS software for better reliability
- ◆ Reading from humidity sensors on SCT barrels too high
- ◆ Remote access to DCS system not ideal in SR

### ■ Cooling system

- ◆ One capillary suddenly blocked - cleared, but points out necessity of filters and (during connection) clean environment
- ◆ Also observed some (still unexplained) flow differences
- ◆ 1 inlet regulator failed - replaced
- ◆ PLC module for back pressure sensor failed - replaced
- ◆ Compressor engine needed additional fan to have adequate cooling
- ◆ Few occasions when high “chilled” water temperatures prevented C3F8 cooling operation

(courtesy H. Pernegger)



## Backup Slide - backplane resistance

- Glue composition:
  - ◆ Endcap - Tra-Duct 129-4
  - ◆ Barrel - Eotite p-10228
- Resistance of ~2000 endcap modules and ~ 600 barrel modules checked
  - ◆ No bias connections have lost
  - ◆ Barrel modules appear more affected than endcap modules
  - ◆ No clear evidence of environmental influence
  - ◆ Over period May-July 06, no evidence of deterioration
- Module performance is not affected by high R in early running
- Remedial action on all or some modules?
  - ◆ Evidence that sustained biasing at 350V cures most modules
  - ◆ Evidence that forward biasing ( $\sim 100 \mu\text{A}$ ) cures most modules
  - ◆ Small number of modules not fully cured by either of these operations
- *Post-irradiation, there will naturally be a high current, so will it be self-curing?*
- The cause of the high R is not fully established

