



The Henryk Niewodniczański
Institute of Nuclear Physics
Polish Academy of Sciences

TIARA and IFJ PAN



Mid-term meeting of the TIARA-PL group

Kraków, 27th September 2012

Prof. Marek Jeżabek

Director General



- General information
- Accelerator activities at IFJ
 - Accelerator infrastructure
 - Projects
 - Scientific and technical staff
- IFJ PAN and accelerator projects
 - Large scale projects
 - Small scale projects
 - Future accelerator projects
- TIARA and IFJ PAN





- ❖ 444 personnel
- ❖ Prof. 37, Assoc. Prof. 36, Ph.D. 128
- ❖ PhD studies – 77 students
- ❖ Interdisciplinary PhD studies
(by AGH University of Science
and Technology)
 - 6 students from the Institute
- ❖ 6 divisions: 27 departments
- ❖ centres of excellence
- ❖ centres of advanced technology
- ❖ 4 accredited laboratories
- ❖ Equipment and Scientific
Infrastructure Construction Division





The Henryk Niewodniczański Institute of Nuclear Physics
Polish Academy of Sciences

Main Research Fields

Particle physics and astrophysics

Nuclear and strong interactions physics

Condensed matter physics

Interdisciplinary and applied research

Theoretical physics

General information

The Henryk Niewodniczański Institute of Nuclear Physics
Polish Academy of Sciences
Kraków, Poland







- **cyclotron AIC-144**
 - proton beam energy: 60 MeV
 - Proton Radiotherapy of Eye Melanoma
- **cyclotron Proteus C-235**
 - National Centre for Hadron Radiotherapy
 - under construction (2013)
- **neutron generator**
 - 14 MeV
- **VdG high stability**
 - 2.5 MeV





Proton Radiotherapy of Eye Melanoma

- cyclotron AIC-144,
- proton beam 60 MeV



Accelerator activities at IFJ

Projects: Medical



cyclotron Proteus C-235

Weight	220 t
External yoke diameter	4,34 m
Średnica nabiegunników	2,1 m
Magnetic structure	4 spiral magnetic sectors
Maximal magnetic field	3,1 T
Maximal current in main coil	800 A
frequency	106 MHz
Voltage	50 - 100 kV
Extraction system	4 harmonic coil in the centre, passive magnetic field corrector, electrostatic deflector
Extraction factor	70%
Beam current at 235 MeV	1 - 300 nA
Ion source	Internal, PIG type
Power consumption (of full system)	1,3 MW

National Center for Hadron Radiotherapy

PL | EN HOME NEWS PARTNERS NEWSLETTER LINKS CONTACT



National Consortium for Hadron Radiotherapy

13 September 2006 document establishing the National Consortium for Hadron Radiotherapy signed.

Members of the consortium, coordinated by the Institute of Nuclear Physics PAN, are 10 major Polish scientific and medical institutions.

2 August 2010 - ceremonial signing of an agreement for the supply of cyclotron Proteus C-235 with the technical infrastructure to create a National Center for Hadron Radiotherapy

Projects

EU Structural Project: "National Center for Hadron Radiotherapy - Phase II: Cyclotron Center Bronowice - Gantry Room"

EU Structural Project: "National Center for Hadron Radiotherapy - Phase I: Cyclotron Center Bronowice"

Internal Project: Proton Radiotherapy of

Accelerator activities at IFJ

Projects: Medical



Fundamental Physics Research Program at the Bronowice Cyclotron Centre

See: <http://experimentsccb.ifj.edu.pl/>

Details will be given by prof. A. Maj
(tomorrow, this conference)



CCB physics program

- dynamics of a few-nucleon systems and physics of nuclear clusters
- measurements of collective, high-energy excitations in nuclei (e.g., giant nuclear resonances)
- high resolution gamma-ray spectroscopy of nuclei produced in the process of proton-induced fission and spallation,
- tests of elements of the modern detection systems (SPIRAL2, FAIR),
- development of the new treatment planning systems for hadron radiotherapy,
- new methods for dosimetry and diagnostics of the proton beam

Accelerator activities at IFJ

Projects: Scientific



Fast neutron generator 14 MeV IGN-14

Research on the neutron transport physics

- determination of the neutron parameters of geological media
- investigation of the thermal neutron scattering in hydrogenous media (hydrogen bound in molecules)
- dependence of the thermal neutron parameters of materials on temperature
- test properties of diamond detectors, (spectrometric measurements of the α particles.

Continuous regime:	neutron yield:	5×10^8 n/s
	ion current:	$\sim 50 \mu\text{A}$ (do $100 \mu\text{A}$)
	duration:	25 to 1000 μs (step 1)
Pulsed regime: Neutron burst:	repetition:	0.3 to 100 ms (step 0.1)
	neutron yield during the pulse:	5×10^9 n/s
Target:	T/Ti,	max. activity 170 GBq
H.F. ion source:		50 MHz
Pulsed extraction voltage:		variable up to 4 kV
Accelerating voltage:		max. 125 kV + 50 kV
Two measuring lines:		^3He detectors
Monitors:		BF_3 detector in paraffin, Scintillation fast neutron probe
Thermostatic chamber for samples:		(0 - 70) $^{\circ}\text{C}$

Accelerator activities at IFJ

Projects: Scientific



Van de Graaff Accelerator

Model	High Voltage Engineering, type KN-3000
Energy range:	2.5 MeV for protons and He ⁺ ions, 5 MeV for α particles
Stability:	0.3%
Beam current:	2 - 100 μ A (protons and He ⁺)
Beam diameter:	1mm (FWHM)

Accelerator is equipped in three beam lines,
dedicated to nuclear analytical methods like
PIXE/PIGE and RBS/channeling.

Applications:

- Environmental studies
- bio-medical research
- material engineering.

Accelerator activities at IFJ

Projects: Scientific





- **Finished projects**

- T2K, J-PARC Tokai, Krakow/J-PARC, 2007 – 2009
- **LHC, CERN Geneva / Krakow, 2005 – 2012**
- ATLAS, CERN Geneva, 2004 – 2009, 2010-2012

- **Ongoing projects:**

- **European XFEL, DESY Hamburg, 2009 – 2015**
- Cherenkov Telescope Array (CTA), 2008 – 2013
- Wendelstein 7 – X, IPP Greifswald, 2007 – 2013

- **Future projects**

- **LHC shutdown, CERN Geneva, 2013 – 2014**



LHC – ELQA, 2005 – 2009, 2011 - 2012

Engineering & prototyping

Design and construction of movable **measuring equipment and accessories**

The main task of the IFJ PAN groups was to verify the electrical circuits of all superconducting magnets in the LHC machine during installation phase and hardware commissioning phase. The complexity of electrical circuits and huge distances in the tunnel required building of movable measuring equipment. 46 mobile units of 6 types were built. All the measuring units were computer controlled by means of the dedicated software application (LabView) and connected to Oracle data base.

Currently an upgrade of the measuring equipment is performed at IFJ PAN.



IFJ PAN and international accelerator projects

Large scale projects



LHC – ELQA, 2005 – 2009, 2011 - 2012

Programming & web applications

Programming of the Electrical Quality Assurance equipment creating web applications

The ELQA measuring units were controlled by computers with dedicated LabView software (left). Data gathered during measurements were accessible via web applications (centre, right). Oracle database was used as central point of the software system. An upgrade of the software is currently performed at IFJ PAN.

ELQA Activities Page

Activities table with columns: Activity, Date, Author, Test, Status. Includes a 'Follow up comments' section with a table of activity details.

Test comments

Activity	Date	Author	Test	Status
980001001	2008-01-15
980001002	2008-01-15
980001003	2008-01-15
980001004	2008-01-15
980001005	2008-01-15
980001006	2008-01-15
980001007	2008-01-15
980001008	2008-01-15
980001009	2008-01-15
980001010	2008-01-15
980001011	2008-01-15
980001012	2008-01-15
980001013	2008-01-15
980001014	2008-01-15
980001015	2008-01-15
980001016	2008-01-15
980001017	2008-01-15
980001018	2008-01-15
980001019	2008-01-15
980001020	2008-01-15

TP4 activities table

Activity	Date	Author	Test	Status
980001001	2008-01-15
980001002	2008-01-15
980001003	2008-01-15
980001004	2008-01-15
980001005	2008-01-15
980001006	2008-01-15
980001007	2008-01-15
980001008	2008-01-15
980001009	2008-01-15
980001010	2008-01-15
980001011	2008-01-15
980001012	2008-01-15
980001013	2008-01-15
980001014	2008-01-15
980001015	2008-01-15
980001016	2008-01-15
980001017	2008-01-15
980001018	2008-01-15
980001019	2008-01-15
980001020	2008-01-15

DOC results

TFM

RCB116-R1B2

Information about circuit

Circuit type: PCB4
Magnet Family: ORBIT CORRECTOR
Sector: 12
Powering subfactor: A12
Current lead A: DFLDS16R1.3
Current lead B: DFLDS16R1.4
Current lead positive: DFLDS16R1.3
Power converter: RFLA-16R1-R2H16-R1B2
Rack name: RFLA
Rack slot: 2.2
Circuit ref. R: 46.482 mΩ
Circuit ref. L: 6.000H
Circuit ref. C: unknown
Number of magnets: 1

Information about test conditions

Reference resistance: 99.75Ω
Reference inductance: Infinite
Reference capacitance: 0F
Number of samples: 50
Manual frequency: 50Hz
Maximal frequency: 50 MHz
Integration time: 500 ms
Voltage: 10 Vrms
Number of samples: 50
Measurement type: normal TFM
Comments of session: **ok**
Test for report: yes
Operator name: Włodow Odrobicz
Environment temperature: 20.0 °C
Environment humidity: 38 %
Testing session start time: 11-07-2008 13:48
Test result: **PASSED** change

Change FOR_REPORT status

Frequency [Hz]	Modulus [Ω]	Phase [°]	Model type	Parameter	Quality factor
10	232.73	67.6	RL	3.44	2.2
100	366.09	70.9	RL	1.94	2.9
1 k	28.13 k	57.7	RL	3.84	1.6
10 k	1.24 k	-60.5	RL	12.8	38.6

TFM Plot

Modulus [Ω] vs Frequency [Hz] and Phase [deg] vs Frequency [Hz].

TP4 results

HVQ

Information about circuit

Current lead A: DFLDS16R1.3
Current lead B: DFLDS16R1.4
Current lead positive: DFLDS16R1.3
Power converter: RFLA-16R1-R2H16-R1B2
Rack name: RFLA
Rack slot: 2.2
Circuit ref. R: 46.482 mΩ
Circuit ref. L: 6.000H
Circuit ref. C: unknown
Number of magnets: 1

Information about test conditions



Reference resistance: 99.75Ω
Reference inductance: Infinite
Reference capacitance: 0F
Number of samples: 50
Manual frequency: 50Hz
Maximal frequency: 50 MHz
Integration time: 500 ms
Voltage: 10 Vrms
Number of samples: 50
Measurement type: normal TFM
Comments of session: **ok**
Test for report: yes
Operator name: Włodow Odrobicz
Environment temperature: 20.0 °C
Environment humidity: 38 %
Testing session start time: 11-07-2008 14:19
Test result: **PASSED** change

HVQ overview

Plot of HVQ results vs Frequency [Hz].

HVQ test step

Plot of HVQ test step vs Frequency [Hz].



LHC – ELQA, 2005 – 2009

Quality Assurance

Electrical Quality Assurance of **electrical circuits** of LHC superconducting magnets



LHC assembly phase:

- 2500 electrical tests of 8 types
- tests performed on different configuration of the superconducting magnets
- 20 to 76 circuits or lines in terms of continuity, resistance and HV qualification
- 12000 tests to check nearly 1600 superconducting circuits at warm and cold

The measurement results were the base for CERN groups developing a new Quench Protection System.


IFJ PAN and international accelerator projects

Large scale projects

LHC – ELQA, 2005 – 2009


Quality Assurance

Quality Assurance of **interconnections of the LHC magnets**



- Pre-inspection of each single magnet on surface and in the tunnel (visual inspection of all magnet components and checking of beam lines by means of microwave reflectometry and endoscopy methods)
- Visual inspection of interconnections after orbital and ultra-sonic welding
- Microwave reflectometry measurements of the beam lines in series of connected magnets
- Final visual inspection just before the closure of each interconnection

Metallic chip (left) and plastic shaving found and removed during reflectometry and endoscopic (right) inspections of the beam lines



Non-conforming weld (left) and compensation bellow (right)



A plug-in module (PIM) damaged during a cool-down/warm-up thermal cycle of the magnets


In collaboration with CERN staff, the team worked out a method for the localization of damaged PIMs, that is two times more precise than that employed before.
The method could be used without opening the interconnections between magnets.

IFJ PAN and international accelerator projects

Large scale projects



IFJ PAN - LHC (2005 - 2014)



IFJ PAN and international accelerator projects
Large scale projects



IFJ PAN in-kind contribution to XFEL construction (2009 - 2015)




- 1) Performance of acceptance tests of **cavities** for a series of 840 units on DESY infrastructure and delivering the corresponding test reports
- 2) Performance of acceptance tests of **cryomodules** for a series of 103 units on DESY infrastructure and delivering the corresponding test reports
- 3) Performance of acceptance tests of **cold magnets** for a series of 103 units on DESY infrastructure and delivering the corresponding tests reports – common effort with DESY

IFJ PAN and international accelerator projects

Large scale projects

IFJ PAN – XFEL preparatory phase (2009 – 2012)

- design of the electronics for cold magnets test stands measurement and database preparation
- preparation of software or/and hardware for the test-stands
- elaboration of the test procedures and work instructions
- training of personnel and verification of procedures on the existing testing facility



Setup for tests of magnets (left), quadrupole inside the cryostat vessel (right)

IFJ PAN and international accelerator projects

Large scale projects

IFJ PAN – XFEL preparatory phase (2009 – 2012)



Tests of RF cavities at warm




Installation of RF cavities in
the vertical cryostat

IFJ PAN and international accelerator projects

Large scale projects

IFJ PAN – XFEL preparatory phase (2009 – 2012)



Longitudinal cross-sections of cryo-module




Transportation of the prototype cryomodule to the test stand

IFJ PAN and international accelerator projects

Large scale projects



IFJ PAN in-kind contribution to XFEL construction (2009 - 2015)



IFJ PAN and international accelerator projects
Large scale projects



Prospective contribution IFJ PAN to ESS

1) Magnets

- Superconducting quadrupole magnets tests (~100 magnets) - DAI
- Normal conducting quadrupole magnets tests (25 magnets in HEBT) - DAI
- Thermal study of superconducting magnets (Quench limits, heat transfer, magnet thermal optimization) - DAI/FA

2) Accelerating structures

- RF cavities tests (~220 RF cavities) - DAI
- RF modules tests (48 modules) - DAI

3) Beam diagnostics

- Beam parameters measurements - DAI/FA
- Accelerator protection system - DAI/FA

4) Beam dynamics

- DAI/FA

DAI - Division of Scientific Equipment and Infrastructure Construction ; FA – Accelerator Physics Section

IFJ PAN and international accelerator projects

Future accelerator projects: ESS



Possible future activities: SuperB

- Beam dynamics - DAI/FA
- Superconducting IR magnets - DAI/FA
- Normal conducting magnet testing - DAI
- Contribute to magnets design - DAI/FA
- Beam diagnostic - DAI/FA
- Polarimetry - DAI/FA
- RF cavities testing - DAI

DAI - Division of Scientific Equipment and Infrastructure Construction ; FA – Accelerator Physics Section

IFJ PAN and international accelerator projects

Future accelerator projects: SuperB



Projects:


- Proton Radiotherapy of Eye Melanoma, design and manufacture of components for the set-up, 2009 – 2012
- Belle 2 – design and manufacture of SVD mock-up, 2011 – 2012
- PRESPEC Collaboration, design and manufacture of mechanics for the finger detector, 2011 – 2012

IFJ PAN and other projects

Small scale projects



- Present
 - Infrastructure
 - Existing infrastructure
 - Dosimetry
 - Electronics
 - Mechanical projects
 - Staff
 - Team of skilled engineers and technicians
 - Local accelerators staff
- Future
 - Accelerator Physics Group
 - Beam dynamics
 - Beam diagnostics
 - Magnets
 - RF systems
 - New concepts (example: HTS superconductors)
 - Education



The Henryk Niewodniczański Institute of Nuclear Physics
Polish Academy of Sciences
Kraków, Poland



- IFJ groups contribute to major world experiments in particle physics, astrophysics and nuclear physics.
- New 250 MeV cyclotron (planned start 2013) will be used for experimental activities (nuclear physics, radiobiology) and radiotherapy of eye melanoma. Gantry will allow for treating pediatric patients.
- Biomedical research based on local infrastructure: eye protontherapy, VdG single proton irradiations, MRI, artificial heart
- Priorities for safely use of nuclear energy and for fusion projects (ITER, Greifswald)
- Income from accredited labs and export of engineers and technicians

Summary and Conclusions



BACKUP SLIDES

- Institutions in Poland (Cracow only):

1. ACK CYFRONET,
2. AGH-UST,
3. CUT,
4. IFJ PAN.

The above entities formed the national SuperB consortium (16. May 2011)

- Participants:

- 7.1 staff,
- 2.5 PhD students,
- 1 support



Courtesy M. Witek




- Main hardware contribution:
 - contribution to the Instrumental Flux Return (IFR) detector
 - ✓ current R&D work on SiPMs, electronics, mechanical construction and software;
 - ✓ application for funds after TDR– autumn 2012).
 - Substantial participation in the accelerator construction (2015).
 - Participation in the overall computing system.
- Main responsibilities:
 - Co-responsibility for the IFR detector,
 - Co-responsibility for the computing system,
 - Physics studies: CP and T violation in B meson and tau lepton decays
- Financing:
 - Application to NCN (Dec. 2012),
 - Very limited resources at home institutions,
 - One individual „diamond” grant.

Courtesy M. Witek



FDSL_2012_05_15




- Electron Cyclotron Resonance source (ECR)
- Low Energy Beam Transport (LEBT)
- Radio-Frequency Quadrupole (RFQ)
- Medium Energy Beam Transport (MEBT)
- Drift-Tube Linac (DTL)
- spoke resonator cavities (Spokes)
- elliptical cavities (Medium β)
- elliptical cavities (High β)
- High Energy Beam Transport (HEBT)

IFJ PAN and international accelerator projects

Future accelerator projects: ESS linear proton accelerator



FDSL_2012_05_15



	Length (m)	Input Energy (MeV)	Frequency (MHz)	Geometric β	# of Sections	Temperatura (K)
LEBT	2.05	0.075	-	-	-	300
RFQ	4.95	0.075	352.21	-	1	300
MEBT	3.53	3	352.21	-	-	300
DTL	32.58	3	352.21	-	1	300
Spoke	58.46	79	352.21	0.50	18 (2 cavities)	2
Medium β	113.84	201	704.42	0.70	16 (4 cavities)	2
High β	227.86	623	704.42	0.92	14 (8 cavities)	2
HEBT	158.66	2500	-	-	-	-

Reference: Conceptual Design Report (Feb. 2012)

The cavity geometrical beta can be defined by the cell length of $\beta_g \lambda / 2$, where λ is the RF free space wavelength.

IFJ PAN and international accelerator projects

Future accelerator projects: ESS linear proton accelerator