


New DCCTs for Personnel Protection in the SPS


BI Day 2012

Sébastien Thoulet BE-BI-PI



- INTRODUCTION
- MECHANICAL DESIGN
- ELECTRONICS DESIGN
- TIME DIAGRAM SEQUENCE
- HARDWARE COMMISSIONING
- PLANNING
- CONCLUSION & THANKS

- **Project** : Ion safety system in the North Hall (EDMS No. 1146023).
- For operational flexibility in the exploitation of CERN accelerators
 New scheme *in the same SPS* super cycle without limiting the number of charges transmitted (TAX absorbers/collimators) to the North Hall :
 ➡ Ions for the North Area + High Intensity protons for CNGS or LHC



➤ Hazards for the North Hall during this SPS super cycle ?

Human hazard to people working in the experimental areas

➡ Filling or timing error could cause the transmission of intense proton bunch instead of ions.

To protect against this eventuality :
An instrumented safety interlock is required.


➡ 2 DCCTs in BA5 :

Why DCCTs ?




Only precise instrument to measure number of charges independently of beam structure.

Which Role ?

Inhibit the chain extraction septum when the beam intensity in the SPS is $> 2E11$ charges.




- 2 DCCTs (made at CERN) installed in June 2012 dedicated for safety interlock with vacuum chamber , ceramic gap, ...
- 1 FBCT only used for additional monitoring not in the safety chain system (Currently not installed).




General layout :

- 2 systems (DCCTs) identical and completely independent for redundancy and safety reasons.
- Provisional location for test in BB50 with only 1 DCCT :
⇒ *Cable issues*



Layout for 1 DCCT:



In red:

Minimum system required to fulfill the specification (pure HW solution)



In green:

Monitoring, remote diagnose tools + acquisition (could in the future, according to noise level, replace Bergoz PCTs)

DCCT ranges distribution

Ranges	Scaling Factor [nb charges/V]	Full Scale [nb charges]
1	2 E13	1 E14
2	2 E12	1 E13
3	2 E11	1 E12
4	2 E10	1 E11

Operating Principle :



➤ To ensure a reliable measurement system :

To be sure of the DCCT's good state :

SELF CHECK DCCT :

Continuous Check : various status as current consumption, demodulation signal amplitude, etc.

Quick Check : Offset test and good response to different calibration pulses before beam injection. Storing the result Quick Check (OK or NOT OK) until next cycle.

MEASUREMENT :

Continuous Measurement : Beam measure on Range 3 and detection when $I_{beam} > 2e11$.

Connections between DCCT and Interlock System

2 signals (and their complementary) are delivered, via optocouplers, by each DCCT.


2 different types of transmission.

- **IN_CHECK_STATUS**


TRUE when the DCCT and the comparator are in check process (before each cycle)

- **LOW_IB_STATUS**

TRUE IF $I_b < 2 E_{11}$ charges
 AND check result OK
 AND IN_CHECK_STATUS FALSE






4 Cases



Location : BB5 with 1 DCCT

- Make a precise calibration of DCCT.
- Following system test :
 - Quick Check with timing.
 - Continuous measurement :
 - With a known current (calibration Generator) or with the Beam.
 - Check 2 signals state to Interlock :
 - IN CHECK STATUS
 - LOW IB STATUS



Signals view on Fesa Navigator

➤ Always ensure the reliability of the system against various events.

➔ Creation of list with possible anomalies that could occur and observation of the response on the self check system :

- Offset drift and noise outside given tolerance.
- Disconnected cables :
 - Range 3 DCCT
 - Calibration Pulses
 - Timing
 - Signals to Interlock
 - BCT Status (current consumption,...)
 - Etc...
- Power Supply on OFF :
How long to recover an operational system ?



- *March 2009* : Specification Draft
- *April 2010* : ECR 1075945 v1
- *Jan 2011* : Cable pulling for provisional location (BB5)
- *June 2011* : ECR 1075945 v2
- *Sept 2011-May 2012* : Mechanical
- *March - June 2012* : Electronic prototypes
- *June 2012* : Installation
- *Since August 2012* : Test of DCCT & Soft RT programme
- *Oct 2012* : Working document specification
- *Jan-Feb 2013* : Test with Interlock system

- *LS1* :
 - Cable pulling for final location (BA5)
 - Specification circulation for final approbation
 - Make final electronics
 - Installation of Fast BCT
 - Global System Commissioning (DCCT, interlock, power supply)

- *After LS1* :
 - Global System Commissioning with Beam
 - Experiment with Ions Beam in North Hall

DCCT's and electronics used were made at CERN.

These are the same as used normally but for this project the new challenge is safety and personnel protection.

➡ Simple & Reliable electronics

Now we are testing DCCT's and electronics prototypes to validate the principle.

➡ Make final electronics

Finally Global System Commissioning with Ions Beam.

➤ *Thanks to :*

- Specifications : Django Manglunki
- Mechanical : Thomas Sahner, Christophe Vuitton, Frédéric Camba, CERN Workshops
- Electronic : Patrick Odier, Jacques Longo, Romain Ruffieux
- Software : Lars Jensen
- Cables : Guillaume Gros