
Status Report of WLCG Tier-1 candidate for ALICE @ KISTI-GSDC

Sang-Un Ahn, for the GSDC Tier-1 Team sahn@kisti.re.kr

12th CERN-Korea Committee Meeting

























- Current Status
 - Resource: Nodes, Services and TAPE
 - Operation
 - Network
- Plan
 - Next Milestones
 - Pledges
 - Network upgrades
- Conclusion

GSDC Tier-1 Team

ROLE	Name	
Representative	Haeng Jin Jang	
	Heejun Yoon	
System Administration	Seunghee Lee	
	Gianni Mario Ricciardi	
Storage: Disk & Tape	Heejun Yoon	
Storage. Disk & Tape	Sang-Oh Park(*)	
Network	Hyeongwoo Park	
Network	KISTI support	
Power supply & Colling	KISTI support	
Grid Middleware	Il-Yeon Yeo	
Gilu Miluuleware	Sang-Un Ahn(*)	
ViAE cupport & Droduction	Sang-Un Ahn	
KiAF support & Production	Sul-Ah Ahn	
1 st June 2012		\$ 3\nu

^(*) New member from 1st June 2012



Activities

- In March, approved as a Tier-1 candidate for ALICE by WLCG Overview Board and acquired full membership for ALICE at ALICE Collaboration Board
- In June, the first demonstration plan for Tier-1 submitted to WLCG
 Management Board
 - The first one revised, then the second version has been prepared reflecting the comments by WLCG and our recent progress
- In August, agreement on the collaboration with KIT (DE) especially for TAPE library: set-up and test



Resources: Nodes & Services

CPUs

- Intel Xeon 12 physical cores -> 24 logical cores w/ HT per Worker Nodes (WN)
- Total ~1500 cores (~17k HepSpec06) dedicated to Tier-1: 62 WNs
- Capable to run ~1500 jobs (1 job per 1 logical core)

Disks

1000 TB disks: Hitachi + EMC²

Storage Element Status @ MonALISA

	AliEn SE	Statistics						Xrootd info					
SE Name	AliEn name	Size	Used	Free	Usage	No. of files	Туре	Size	Used	Free	Usage		
34. KISTI_GSDC - SE	ALICE::KISTI_GSDC::SE	100 TB	61.62 TB	38.38 TB	61.62%	1,424,411	FILE	101.8 TB	99.74 TB	2.033 TB	98%		
35. KISTI_GSDC - SE2	ALICE::KISTI_GSDC::SE2	966.8 TB	73.81 TB	893 TB	7.634%	1,914,528	FILE	966.8 TB	94.88 TB	871.9 TB	9.814%		

Services w/ gLite 3.2 middleware in production

- EMI migration in progress (plan to be submitted to WLCG GDB)
- 2 CEs, Top|site BDII, VOBOX, XROOTD (1 redirector and 9 pools)





Resources: TAPE


- TAPE library pre-test (File System + (un-)staging + XROOTD) completed
 - IBM test (Mar. 2012): GPFS+TSM+XROOTD
 - ORACLE test (Aug. 2012): QFS+SAM+XROOTD
- For cache (allows prompt access to archived data), additional disk pool (as a buffer) is required
 - Min. 200 TB; max. 400 TB for pA data delivered in coming Jan. Feb.
- IBM TAPE library will be delivered: installation and functioning test will be complete by the end of November
 - 1PB media capacity (extendable up to 3 PB)
 - Minimum 1.92 GB/s throughput (tape drive: read/write @ 240 MB/s)
 - Dual robot arms
 - 3 years maintenance support + recovery services within 24hrs







Operation

- On service for ALICE as WLCG Tier-1 candidate since March in 2012
 - Test-bed from October in 2010
 - Capable to run ~1500 jobs, >7000 jobs done everyday
 - Up to now, total 820k jobs performed successfully
 - Site Availability/Reliability reported monthly by WLCG MB since Aug. 2012













Network to LHCOPN

• 10Gbps connection is required to join LHC OPN (Optical Private Network) among Tier-0 (CERN) and other Tier-1s







Network Traffic Status

GLORIAD-KR – CERN

- 'Yearly' graph (1 Day Average)
- Correlation with # of active jobs

Dedicated 1Gbps established

Functional test

Incoming Traffic in bps
Outgoing Traffic in bps
Maximal 5 minutes Incoming Traffic
Maximal 5 minutes Outgoing Traffic

Internal network issue solved

Start of torrent-based ALICE package distribution service: Observed large incoming traffic (maximal 5 minutes) after





Next Milestones

KISTI-GSDC WLCG Tier I Demonstration Plan Roadmap

														v0. 4
SA	2012						2013							
OBJECTIVE	Aug	Sep	Oct	Nov	Dec	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep
LHC Schedule		рр А		AC pA				Long Shutdown I						
Setting-up of the Tape system (procurement, installation and configuration)														
Data transfer from CERN to KISTI::Tape at the required speed Archiving 10% of the ALICE Pb-Pb raw data														
Provide a precise plan for when 3Gbps (or higher) connectivity to CERN will be provided														
Present a plan for providing on-call services/support according to the Tier1 specifications														
Test of on-call services/support														
90% of the storage element availability (functional tests) for at least 2 months														
85% of the job capacity running for at least 2 months														
90% of the targeted WLCG Tier I services for at least 2 months														

- 1. TAPE library set-up and data transfer test (to be ready before pA): collab. with KIT (DE)
- 2. Complete 24 hours on-call service plan: shift scheme and notification (SMS, E-mail, etc.)
- 3. Tier-1 service stability test: demonstration at least 2 months(>90%)
- 4. Upgrading network bandwidth up to 10Gbps in order to join LHCOPN: first, 2Gbps by 2013



Pledged

Pledged resources

- Based on WLCG & ALICE Collaboration MoU
- Provides 2000 cores for Tier-1, 2PB for TAPE by 2014
- Meeting ALICE requirement by 2013

	Current	Pledged						
	(ALICE Req.)	2012	2013	2014				
CPUs	1,500 (2,000)	1,500	2,000	2,000				
Disk (TB)	1,000 (1,000)	1,000	1,000	1,000				
Tape (TB)	- (1,500)	700	1,500	2,000				



Network Upgrade

- In 2013, dedicated 2Gbps (current 1Gbps) established between KISTI-CERN
- Plan to upgrade to 10Gbps connection in a few years








Conclusion

- Demonstration of WLCG Tier-1 for ALICE is going well according to plan:
 - ALICE collaboration appreciated its progress of KISTI-GSDC as WLCG Tier-1 candidate (ALICE collaboration board in 12th Oct. 2012)
- For pA data, it is crucial that TAPE library has to be fully functioning by the end of this year
- Precise plan for upgrading network >3Gbps is mandatory to be integrated into LHCOPN





Thank you