



# MAX

MYRRHA ACCELERATOR eXPERIMENT  
RESEARCH & DEVELOPMENT PROGRAMME



# Euratom MAX project

## The MYRRHA Accelerator eXperiment R&D programme

**Frédéric BOULY**

*CNRS-IN2P3 / LPSC Grenoble, France*



**Jean-Luc BIARROTTE**

*CNRS-IN2P3 / IPN Orsay, France*

*EURATOM FP7 MAX project coordinator*





# MAX

MYRRHA ACCELERATOR eXPERIMENT  
RESEARCH & DEVELOPMENT PROGRAMME



# 1. Introduction

2. The MYRRHA accelerator concept
3. Some MAX recent achievements
4. Perspectives

## MYRRHA Project

**Multi-purpose hYbrid Research Reactor for High-tech Applications  
At Mol (Belgium)**

*Development, construction & commissioning of  
a new large fast neutron research infrastructure*

- ① **ADS demonstrator**
- ② **Fast neutron irradiation facility**
- ③ **Pilot plant for LFR technology**

# The MYRRHA accelerator: background

- **End 90's**: several collaborative R&D activities worldwide on ADS accelerators (*APT/AAA, TRASCO, etc. w/ especially a CEA/CNRS/INFN collaboration*)
- **2001**: “The European roadmap for developing ADS for Nuclear Waste Incineration”, European Technical Working Group on ADS (*chaired by C. Rubbia, ENEA*)
- **2002**: pre-design “**Myrrha Draft 1**” (*cyclotron 350 MeV*)
- **2002-2004**: MYRRHA is studied as one of the 3 reactor designs within the **PDS-XADS FP5 project** (coord. Framatome/AREVA) (*cyclotron turns into linac, first reliability analyses show a need for fault-tolerance capability*)




Figure 40 – Overall Layout for the Cyclotron XADS option.





Figure 1 – Schematic layout of the XADS accelerator in the linac option.


# The MYRRHA accelerator: background

- **2005:** updated pre-design “**Myrrha Draft 2**” (*linac 350 MeV*)
- **2005-2010:** MYRRHA is studied as the XT-ADS demo within the **EUROTRANS FP6 project** (coord. FZK) (*600 MeV linac conceptual design, R&D activities w/ focus on reliability*)



- **2010:** MYRRHA is on the ESFRI list, and officially supported by the Belgium government at a 40% level (*384M€, w/ 60M€ already engaged*)
- **2010-2014:** MYRRHA accelerator advanced design phase w/ support from the **EURATOM FP7 projects** (*MAX especially*)
- **2015-2019:** possible construction phase
- **2020-2023:** possible commissioning phase & progressive start-up

# MYRRHA within EURATOM FP7: 2010-2014




# The MAX project

**Goal:** deliver a consolidated reference layout of the MYRRHA linac with sufficient detail and adequate level of confidence in order to initiate in 2015 its engineering design and subsequent construction phase



<http://ipnweb.in2p3.fr/MAX/>



*WP1: Global accelerator design*

*WP2: Injector developments*

*WP3: Main linac developments*

*WP4: System optimisation*



# MAX

MYRRHA ACCELERATOR eXPERIMENT  
RESEARCH & DEVELOPMENT PROGRAMME



1. Introduction

**2. The MYRRHA accelerator concept**

3. Some MAX recent achievements

4. Perspectives




# MYRRHA as an ADS demonstrator

Demonstrate the physics and technology of an Accelerator Driven System (ADS) for transmuting long-lived radioactive waste

- Demonstrate the **ADS concept** (coupling accelerator + spallation source + power reactor)
- Demonstrate the **transmutation** (experimental assemblies)

**Main features of the ADS demo**

- 50-100 MWth power
- Highly-enriched MOX fuel
- Pb-Bi Eutectic coolant & target
- $k_{\text{eff}}$  around 0.95 in subcritical mode
- 600 MeV, 2.5 - 4 mA proton beam




# MYRRHA proton beam requirements

→ High power proton beam (up to 2.4 MW)

Proton energy	600 MeV
Peak beam current	0.1 to 4.0 mA
Repetition rate	1 to 250 Hz
Beam duty cycle	$10^{-4}$ to 1
Beam power stability	$< \pm 2\%$ on a time scale of 100ms
Beam footprint on reactor window	Circular $\varnothing 85\text{mm}$
Beam footprint stability	$< \pm 10\%$ on a time scale of 1s
# of allowed beam trips on reactor longer than 3 sec	10 maximum per 3-month operation period
# of allowed beam trips on reactor longer than 0.1 sec	100 maximum per day
# of allowed beam trips on reactor shorter than 0.1 sec	unlimited

# Panorama of high-power proton accelerators




# MYRRHA proton beam requirements

→ High power proton beam (up to 2.4 MW)

Proton energy	600 MeV
Peak beam current	0.1 to 4.0 mA
Repetition rate	1 to 250 Hz
Beam duty cycle	$10^{-4}$ to 1
Beam power stability	$< \pm 2\%$ on a time scale of 100ms
Beam footprint on reactor window	Circular $\varnothing 85\text{mm}$
Beam footprint stability	$< \pm 10\%$ on a time scale of 1s
# of allowed beam trips on reactor longer than 3 sec	10 maximum per 3-month operation period
# of allowed beam trips on reactor longer than 0.1 sec	100 maximum per day
# of allowed beam trips on reactor shorter than 0.1 sec	unlimited

→ Extreme reliability level

# The ADS reliability requirement




D. Vandeplassche, Proc. IPAC 2012

# The ADS reliability requirement


- ✱ **Beam trips longer than 3 sec** must be very rare:
  - To limit thermal stress & fatigue on the target window, reactor structures & fuel assemblies
  - To ensure a 80% availability – given the foreseen reactor start-up procedures
- ✱ **Present MYRRHA specifications:** <10 beam trips per 3-month operation period (i.e. MTBF > 250h) – derived from the PHENIX reactor operation analysis
  - Far above present HPPA accelerator performance – MTBF is a few hours at PSI or SNS
  - Far above present ADS specifications in US or Japan – based on simulations
- ✱ **In any case, reliability guidelines are needed for the ADS accelerator design:**
  - **Strong design** i.e. robust optics, simplicity, low thermal stress, operation margins...
  - **Repairability** (on-line where possible) and efficient maintenance schemes
  - **Redundancy** (serial where possible, or parallel) to be able to tolerate failures

# Strategy for a fault in the injector = parallel redundancy


## 1 Initial configuration




## 3 The failure is localized in injector



## 2 A failure is detected anywhere



## 4 Beam is resumed



# Strategy for a fault in the main linac = serial redundancy






Figure 12 : Transverse beam distribution at 220  $\mu$ s, in red are plotted the losses

- ❶ A failure is detected anywhere  
→ Beam is stopped by the MPS in injector at  $t_0$
- ❷ The fault is localized in a SC cavity RF loop  
→ Need for an efficient fault diagnostic system

- ❸ New  $V/\phi$  set-points are updated in cavities adjacent to the failed one  
→ Set-points determined via virtual accelerator application and/or at the commissioning phase



- ❹ The failed cavity is detuned (to avoid the beam loading effect)  
→ Using the Cold Tuning System





- ❺ Once steady state is reached, beam is resumed at  $t_1 < t_0 + 3\text{sec}$   
→ Failed RF cavity system to be repaired on-line if possible




# Layout of the MYRRHA linac


## INJECTOR BUILDING



*Section #1 (Spoke  $\beta \sim 0.35$  @ 352MHz)*



# Layout of the MYRRHA linac





# MAX


MYRRHA ACCELERATOR eXPERIMENT  
RESEARCH & DEVELOPMENT PROGRAMME



1. Background
2. The MYRRHA accelerator concept
- 3. Some MAX recent achievements**
4. Perspectives


# Low Energy Beam Transport (30 keV)

- LEBT conceptual design achieved - Detailed technical design & construction phase has started (SCK\*CEN + LPSC Grenoble)
- Source from Panttechnik: commissioning at SCK




R. Salemme et al., Proc. TC-ADS 2013

- Beam Physics research topic : Space-charge compensation regime



Space-charge compensation process

## Beam evolution




t = 20 μs

Impact of SSC rising time, courtesy of N. Chauvin CEA Saclay

# RFQ (30 keV – 1.5 MeV)


- Present reference = 4-rod structure at 176.1 MHz
- R&D at IAP Frankfurt on thermal effects
- Construction of RFQ 1-m prototype achieved (ready for high-power RF test)
- Next SCK\*CEN step will be to build the full RFQ



MAX RFQ 1 meter prototype

Parameter	EUROTRANS	MYRRHA	SARAF
$f$ [MHz]	352	176	176
$W_{in}$ [MeV] / $W_{out}$ [MeV]	0.05 / 3	0.03 / 1.5	0.02 / 1.5
$U$ [kV]	65	40	32.5
$E_{s,max} / E_k$	1.7	1	0.8
$\sigma_{min}$ [mm]	2.3	2.9	2.7
$m_{max}$	1.8	2.3	2.7
$g_{min}$ [mm]	2.6	3.6	3.7
$\epsilon_{in}^{t, n, rms}$ [ $\pi$ mm-mrad]	0.2	0.2	0.175
$\epsilon_{out}^{t, n, rms}$ [ $\pi$ mm-mrad]	0.21 / 0.20	0.22 / 0.22	0.19* / 0.19*
$\epsilon_{out}^{l, rms}$ [ $\pi$ keV-deg]	109	64.6	36*
$L$ [m]	4.3	4.0	3.8
$T$ [%] / $T_{10mA}$ [%]	~100 / ~100	~100 / ~100	95.5* / 92.3*
$R_p$ [k $\Omega$ m]	61 (MWS)	67 (after SARAF)	67 (meas.)
$P_c$ [kW/m]	69.8 (MWS, +20%)	23.5	15.8

\* Simulated by A. Bechtold using the RFQSim code without image effects or multipole effects.




M. Zhang et al., Proc. LINAC 2012

M. Vossberg et al., Proc. LINAC 2012


# CH booster (1.5 – 17 MeV)

- As compact as reasonably possible
- Presently based on the KONUS beam dynamics concept, but a safer alternative design is in-work




	$N_{gaps}$	$V_{eff}$ [MV]	$L_{cell}$ [m]	$\beta_{avg}$	$E_a$ [MV/m]	Upstream transv. focusing [T/m or T]
RB 1	2	0.15	0.10	0.06	1.56	-
RT-CH 1	10	1.03	0.54	0.06	1.91	(triplet) 44.5/43.5/44.5
RT-CH 2	10	1.14	0.66	0.08	1.72	(triplet) 47.0/48.0/47.0
RB 2	5	0.525	0.36	0.09	1.45	(triplet) 51.0/53.5/51.0
SC-CH 1	10	3.50	0.87	0.10	4.02	(solenoid) 2.50
SC-CH 2	9	3.98	1.01	0.13	3.94	(solenoid) 3.05
SC-CH 3	8	4.18	1.07	0.16	3.89	(solenoid) 3.50
SC-CH 4	7	4.09	1.07	0.18	3.82	(solenoid) 4.30

MYRRHA reference injector layout



MYRRHA alternative injector layout

- Construction of 176 MHz CH prototypes achieved (ready for tests)



M. Bush et al., Proc. SRF 2013


D. Mäder et al., Proc. SRF 2013



MAX RT CH prototype

# Medium Energy Beam Transport (17 MeV)

- Conceptual design of the doubled injector connection
- Preliminary definition of associated fast switching procedures



J-L. Biarrotte et al.,  
Proc. TC-ADS 2013

General layout of the MYRRHA MEBT, superimposed on a preliminary building layout




# Main superconducting linac (17 – 600 MeV)

- Design of the 230 metres SC linac incl. fault-tolerance capabilities
- Main concern = physics of beam halo during fault-recovery scenarios
- Generic R&D for spoke-type cavities
- Design of MYRRHA spoke cryomodule
- Prototyping of 2 MYRRHA spoke cavities is launched

M. El Yakoubi et al.,  
Proc. TC-ADS 2013

J-L. Biarrotte et al.,  
Proc. SRF 2013




MYRRHA spoke module & cavity overview

Main parameters of the MYRRHA linac

Section #	#1	#2	#3
$E_{input}$ (MeV)	17.0	80.8	184.2
$E_{output}$ (MeV)	80.8	184.2	600.0
Cav. Technology	Spoke	Elliptical	
Cav. freq. (MHz)	352.2	704.4	
Cavity optimal $\beta$	0.375	0.510	0.705
Nb of cells / cav.	2	5	5
Focusing type	NC quadrupole doublets		
Nb cav / cryom.	2	2	4
Total nb of cav.	48	34	60
Nominal $E_{acc}^*$ (MV/m)	6.4	8.2	11.0
Synch. phase (deg)	-40 to -18	-36 to -15	
4 mA beam load / cav. (kW)	1.5 to 8	2 to 17	14 to 32
Nominal Qpole gradients (T/m)	5.1 to 7.7	4.8 to 7.0	5.1 to 6.6
Section length (m)	73.0	63.9	100.8

\* $E_{acc}$  is given at optimal beta and normalized to  $L_{acc} = N_{gap} \cdot \beta \cdot \lambda / 2$




Cavity Frame Put on adjustable Posts






# Main superconducting linac (17 – 600 MeV)

- Demonstration of 700 MHz cavity CW RF operation in accelerator-like environment
- Present status = couplers conditioned, first 80kW 2K operation should come very soon




F. Bouly, M. El Yakoubi, et al., Proc. SRF 2013



# Main superconducting linac (17 – 600 MeV)



- Planned experiments on fast fault recovery schemes (w/ suited management of tuner, DLLRF)
- Model of superconducting cavity developed to study the fast fault-recovery feasibility
- Main concern = Physics of beam halo during fault-recovery scenarios
- Impact on RF power requirements (~70 % margins)



J-L. Biarrotte et al., Proc. SRF 2013


F. Bouly, thèse de doctorat, 2011

Fast set-point update strategy




# Beam simulations

- Reference source-to-target beam simulation
- Benchmarking activities (TraceWin, LORASR, Track)
- Monte Carlo error studies will start soon



- Definition of beam time structure & power control strategy



Reference MYRRHA beam time structure for 2.4 MW operation:



-> long 4mA blue pulses are sent to the reactor (mean power is adjusting with pulse length)  
 -> short red ones are sent to ISOL (creating 200us beam holes for reactor subcriticality monitoring)



J-L. Biarrotte et al.,  
 Proc. TC-ADS 2013

# ISOL@MYRRHA extraction (600 MeV)

- Conceptual design based on fast kicker
- 200us 4mA beam pulses at 250 Hz




		<b>ISOL@MYRRHA Extraction line</b>		
DRAWN BY		DRAWING TITLE		
Roberto Salenne		Front view		
CHECKED BY	DATE	SIZE	DRAWING NUMBER	REV
Dirk Vandeplassche	29/04/2013	A3	Part1	1
DESIGNED BY	DATE	SCALE	SHEET	
Dirk Vandeplassche		1:140	.1/1	

Preliminary layout of the ISOL@MYRRHA extraction zone


# High Energy Beam Transport (600 MeV)

- Preliminary design exists, incl. PSI-like 2.4 MW beam dump & raster scanning on target
- Interface with reactor to be further reworked



Beam distribution on spallation window

H. Sagnac et al., Proc. IPAC 2011



Layout of the MYRRHA beam lines to reactor & dump

# Systems, reliability

➤ SNS linac reliability model has been developed & successfully benchmarked with operation data


➤ MYRRHA linac reliability model is in-work

A. Pitigoï, Proc. TC-ADS 2013


➤ R&D on 700 MHz solid-state amplifiers

➤ Preliminary design of MYRRHA cryogenic plant

T. Junquera et al., Proc. SRF 2013



Local compensation sequence: basis for « COMP » fault tree



Proprietary Information

TRON DEVICES bernard DARGES





# MAX

MYRRHA ACCELERATOR eXPERIMENT  
RESEARCH & DEVELOPMENT PROGRAMME



1. Background
2. The MYRRHA accelerator concept
3. Some MAX recent achievements
4. Perspectives

# Conclusions & perspectives

- **The successful & reliable production of the MYRRHA high power & stable beam is a very interesting challenge**
  - Huge R&D investment is still needed to fully demonstrate the feasibility & prepare for construction
- **Present R&D is mainly dedicated to general design and developments on a few main primary components. It will need to be push further towards an engineering design phase**
  - Construction of a full injector demonstrator – started with the LEBT (SCK/LPSC)
  - Prototyping: CH-DTL & RFQ at IAP - 700 MHz experiment & spoke design at IPNO
- **MAX is going on until October 2014 (tbc)**
  - A possible follow up (2015-2018) is under study
- **Further implication from the SCK\*CEN side will be required if MYRRHA construction is to be launched in the 2/3 next years**
  - Nowadays, present SCK accelerator group is 3 people...





# MAX

MYRRHA ACCELERATOR eXPERIMENT  
RESEARCH & DEVELOPMENT PROGRAMME



## Thank You for your attention!

<http://ipnweb.in2p3.fr/MAX/>

<http://myrrha.sckcen.be/>

COORDINATOR

