

Crab Cavity Technical Coordination WG Kick-off meeting

Alick Macpherson
11 July 2012

5th Crab Cavity Workshop (14th-15th November)

Objectives of SPS Beam Test



- Crab cavities in LHC: robust functioning through entire LHC cycle
 - no effect on LHC beam during injection, ramp and squeeze.
- RF structures yet to be realized will be used for the LHC crab crossing.
- **Prototype tests with hadron beams are a pre-requisite**
 - Identify potential risks and mitigations to ensure the safety of the accelerator.
- **An essential milestone is to test a crab cavity in the SPS**
 - Verify crabbing can be achieved in a proton machine: **no showstoppers**
 - **Key Issues: Crabbing, machine protection, cavity transparency**

Crab Cavity Technical Coordination WG

Mandate of this working group

- **Prepare, organize, and run Crab Cavities beam tests in SPS.**
 - Coordinate infrastructure requirements for these beam tests
 - Handle the complete integration of these beam tests
 - Implement agreed validation program for Crab Cavity functionality @LHC
 - Identify common design and infrastructure elements that facilitate both the SPS tests and potential verification tests in LHC Pt 4
 - Set and maintain schedules for crab cavity beam tests
- **Provide relevant specifications [functional and technical]** that allow the LHC crab cavity project to proceed to a Technical Design Report and beyond.
- **Assess [in conjunction with Machine Protection] operational and machine safety risks** associated with crab cavity operation in LHC [&SPS]


Draft 10 years plan (27/10/11)




- **Machine:** Collimation & prepare for crab cavities & RF cryo system

- SM18 Vertical Test in 2015
- SPS Beam Test in 2016
- LHC Pt 4 Test in 2017

Draft 10 years plan (27/10/11)




4.5 K TCF20
at SPS Pt 4



• **Machine:** Collimation & prepare for crab cavities & RF cryo system


- SM18 Vertical Test in 2015
- SPS Beam Test in 2016
- LHC Pt 4 Test in 2017

Draft 10 years plan (27/10/11)



4.5 K TCF20
at SPS Pt 4


2K Subcooling at SPS Pt 4



• Machine: Collimation & prepare for crab cavities & RF cryo system

- SM18 Vertical Test in 2015
- SPS Beam Test in 2016
- LHC Pt 4 Test in 2017


Draft 10 years plan (27/10/11)



4.5 K TCF20
at SPS Pt 4

2K Subcooling at SPS Pt 4

COLDEX carbon coating
tests foreseen




• Machine: Collimation & prepare for crab cavities & RF cryo system

- SM18 Vertical Test in 2015
- SPS Beam Test in 2016
- LHC Pt 4 Test in 2017

Draft 10 years plan (27/10/11)




SM18 Tests



4.5 K TCF20
at SPS Pt 4

COLDEX carbon coating
tests foreseen


2K Subcooling at SPS Pt 4



• Machine: Collimation & prepare for crab cavities & RF cryo system


- SM18 Vertical Test in 2015
- SPS Beam Test in 2016
- LHC Pt 4 Test in 2017

Draft 10 years plan (27/10/11)




- SM18 Vertical Test in 2015
- SPS Beam Test in 2016
- LHC Pt 4 Test in 2017

Draft 10 years plan (27/10/11)




- SM18 Vertical Test in 2015
- SPS Beam Test in 2016
- LHC Pt 4 Test in 2017


Draft 10 years plan (27/10/11)




- SM18 Vertical Test in 2015
- SPS Beam Test in 2016
- LHC Pt 4 Test in 2017
- Issues
 - COLDEX testing in 2014-2015
 - SPS Installation 2015-2016 Xmas break




Schedule as from
5th Crab Cavity
Workshop




- 2015 not really feasible for SPS beam test
 - COLDEX till mid 2015. Removal time ~1.5 months => CC installation conflict
- **Possibility of installation independent of COLDEX**
 - Cryogenics: Must be close to SPS Pt 4
 - Vacuum: Requires new Y-Chamber.
 - Possibility of LHC compatible cryostat (420mm beam center separation)



Schedule as from 5th Crab Cavity Workshop



- 2015 not really feasible for SPS beam test
 - COLDEX till mid 2015. Removal time ~1.5 months => CC installation conflict
- **Possibility of installation independent of COLDEX**
 - Cryogenics: Must be close to SPS Pt 4
 - Vacuum: Requires new Y-Chamber.
 - Possibility of LHC compatible cryostat (420mm beam center separation)



KEY TO SYMBOLS


- Earthing point for vacuum chamber
- DAMPING RESISTORS**
- Short without fixation
- Short with fixation
- Long without fixation
- Long with fixation
- Insulated quick disconnect joint (enamelled flange on side carrying pointer)
- 200daN (enamelled flange on side carrying pointer)
- 200daN (Support (withstanding no force along the beam))
- Support insulated electrically from vacuum chamber
- Maximum offset in flexible element
- Displacement of special elements
 - H= Horizontal displacement
 - V= Vertical displacement
 - Initial position (basic fixed displacement)
 - After running-in (max. additional fixed displacement)
 - In service (max. additional displacement)
 - Remote control in service

Example shows that maximum total horizontal displacement in service will be 9+7+5=21mm

NOTA: VPSA, VPRS and VCHA, VCHB are insulated from vacuum chamber and earthed separately

APERTURE OF THE VACUUM CHAMBER

Vacuum chamber cross section with external nominal dimensions under vacuum.
t=wall thickness



QNT	DESCRIPTION	POS.	MAT.	SIENS./CLASS	OBSERVATIONS	REF./CERN
1	GNI	15		SPSLGSS0822		
1	VDBB	14		SPS8095000747		
1	V---	13		SPS		
1	VBBB	12		SPS8095003007		
1	VERK	11		SPS8095003024		
1	VKEA	10		SPSVCFEB0003		
1	V---	9		SPSVCFEB0007		
1	COLDEX	8				
1	V---	7		SPSVCFEB0003		
2	V---	6		SPSVCFEB0001		
1	WARM-PAC	5				
1	VBBA	4		SPS8095003006		
1	VWSB	3		SPS8094007487		
1	VDB-	2		SPSVCFEB0007		
1	VEQA	1		SPS8094007092		

DESIGN/ASS	SIENS./CLASS
LAYOUT D'INSTALLATION MACHINES LEP - SPS	DESIGNER: J. RAMILLON
SPS LSS4	VERSION: 2006
HALF PERIOD QDA 41710 - QFA 41810	SCALE: 1:10
DEMI PERIODE QDA 41710 - QFA 41810	APPROVED: N. GILBERT
	DATE: 2007-10-24
	PROJECT ENGINEER: AS BUILT
	PROJECT: SPS LSS4
	REF: SPS LSS4
	NO: 028
	SIZE: 0 F

IND.	DATE	NOM/NAME	ZONE	MODIFICATION
F	2007-10-11	J. RAMILLON		Change nomenclature
E	2006-06-15	J. RAMILLON		VERSION: 2006
D	2001-06-28	J. RAMILLON		Mise a jour (Shut Down 2001)
C	1999-03-26	J. RAMILLON		MIS A JOUR
B	1998-03-26	J. RAMILLON		MIS A JOUR
A	1995-09-14	J. RAMILLON		

People involved/contacted

Tobias Baer	Crab cavities/Machine Protection
Philippe Baudrenghien	RF low level
Krzysztof Brodzinski	Cryo
Rama Calaga	Crab Cavities
Paolo Chiggiato/ Vincent Baglin	Vacuum
Edmond Ciapala	RF
David McFarlane	Space and integration
Rhodri Jones	Beam Instrumentation
Alick Macpherson	Coordination
Elias Metral/Benoit Salvant	Beam dynamics/SPS
Eric Monteinos	RF power
Stefano Redaelli/Belen Salvachua	Collimation
Bruce Yee Rendon	Simulations
Joachim Tucmantel	Crab Cavities + RF
Rogelio Tomas	Optics issues
Frank Zimmermann	Crab Cavities+ measurements
Markus Zerlauth/Jorg Wenninger	Machine Protection

SPS BEAM TEST

CAVITY DESIGN

- SM18 Cavity Testing
- Needed: Review of functional specifications, design envelopes and performance parameters

CRYOSTAT

- Needed: Functional specification, and clarification of design and integration constraints

CRYOGENICS

- Refurbishment of TCF20 unit (4.5K System) ongoing, and capacity to be verified
- Sub-cooling unit (2K System) to be done in 2013, then commissioning
- Needed: More details on beam test layout and dynamic heat load

VACUUM

- Possible conflict with COLDEX Installation
 - May need to construct new Y chamber
- Needed: inputs/constraints on vacuum conditions required from RF team
 - eg is differential pumping needed

SPS BEAM TEST - II

OPTICS

- low intensity LHC beams in SPS: determine hardware + measurement conditions
- Location: Initial proposal = COLDEX location. (small Horizontal beta-function)
 - Local optics knobs: β -functions knobs if CC voltage not OK for SPS energy (26-450 GeV)
 - Alternative locations: RF, cryogenic and other infrastructure constraints.
- Needed: inputs/constraints for cavity functional specifications

IMPEDANCE AND INSTABILITIES

- Accurate knowledge of CC impedance and tolerances for HOM damping.
- SM18 + SPS tests: characterization CC impedance and damping to stay below instability thresholds.
- Needed: Input for layout constraints in SPS layout

LONG-RANGE BEAM-BEAM EFFECTS

- Effect of long-range beam-beam to be estimated using crabbed bunches and long-range beam-beam wires. Need to investigate the sensitivity at different tunes.

SPS BEAM TEST - III

RF NOISE, STABILITY AND CONTROLS

- Effect of RF noise on the beam emittance to be measured and understood.
- Definition of beam parameters: Tilt from crab cavity \geq horizontal beam size
 - normalized emittance $\sim 2 \mu\text{m} + E \sim 55 \text{ GeV}/c$ or $E > 120 \text{ GeV}/c$ and $I \sim 1 \times 10^{10}$
 - SPS emittance growth of about 20%/hr in coast but need $\sim 1\%/hr$
 - need to improve working point and or measurement process
- Parametric scan of RF noise amplitude and freq for evaluation of beam size evolution.
 - Aim: Establish final tolerances for the construction of the LHC crab cavities.

BEAM INSTRUMENTATION

- Most instrumentation in place or adaptable.
 - Exception: Streak camera to be developed could be ready for 2016
- Needed: understanding of what is required when.

SPS BEAM TEST - IV

COLLIMATION

- Proposal: Two collimators to be used [SLAC (not yet installed) + CERN (installed)]
 - Collimation in horizontal (crabbing plane).
 - Phase advance: SLAC -> almost no crabbing, CERN -> full crabbing
 - Collimation study: determine efficiency, beam losses + hierarchy.

MACHINE PROTECTION

- Issues due to fast voltage and phase failures; loss characteristics understood.
 - Induced RF trips studied to guarantee machine protection and to devise interlocks.

OPERATIONAL ASPECTS

- Cavity transparency in single-beam scenario: beam behaviour at “zero-voltage”
- beam loading and transient effects with and without RF feedback.
- Long term effects with crab cavities on coasting beams at various energies.

Next steps ...

- Identify/confirm participants
 - define/review relevant inputs for cavity functional specification
 - Draft functional specification for implementation of SPS Beam Test
 - Target date: end of year 2012
 - Outline location and schedule for SPS Beam tests
 - seek preliminary endorsement
 - Input from round table discussion
-
- Agree on next meeting time
 - Meetings to be managed via INDICO
 - WG website to be established