

Machine Protection Panel Workshop, March 2013

LHC BLM SYSTEM: HARDWARE CHANGES DURING LS1

Overview


- 2012 Performance summary
 - Main changes introduced
 - Interlocks and Faults analysis
- LS1 foreseen changes
 - Tunnel installation & Acquisition electronics
 - Surface installation & Processing electronics
 - Firmware modifications
 - Application additions
 - Commissioning

Listing main performance changes in 2012 run and fault statistics


LHC BLM SYSTEM: 2012 PERFORMANCE SUMMARY

Automatic/fast Collimator BBA

- New dedicated buffer for automatic and faster Collimator Beam Based Alignment
 - continuous transmission to collimation client
 - UDP packets at 12.5 Hz
 - deliver from each BLM detector a 82 ms integral
- Excellent diagnostic tool. Has been also used successfully to study :
 - the time evolution of the losses in IR7 and IR3 during the loss maps
 - halo diffusion and population



Standard 1 Hz data



Dedicated 12.5 Hz data

Plots courtesy of Belen Maria Salvachua Ferrando, Gianluca Valentino and Stefano Redaelli

LIC detectors development

- Development of the LIC detectors
 - Cover region between IC and SEM detectors
 - Part of strategy for the mitigation of the injection losses

- 1. Started with a first set of monitors for both beams
 - Investigate **behaviour** (and reliability)
 - Check correctness of the LIC's **conversion factor**
 - Check correctness of the calculated **thresholds**


- 2. Additional monitors added during the consecutive Technical Stops
 - Direct comparison with IC detectors

- Many issues with first batches
 - Several changes in the production and design parameters


- See Eduardo Nebot Del Busto's presentation in Evian 2012

Preventive system fault analysis

- Daily **automatic** analysis of the systems performance
 - Unavailability due to errors from optical link failures **increased**.
 - **Prototype** detector types were installed
 - Many **cards, detectors** and **cabling** have been exchanged in the shadow before affecting LHC availability.



Example of the daily optical link report





LHC Beam Operation Down Workshop 2012


courtesy A. Macpherson

Issue and Task Tracking

- Addition of JIRA project tracker
- Extensive use in 2012
 - register all **issues** occurred
 - track **tasks** for the Technical Stops and Shutdowns



Total Issues: 361 Statistic Type: Fix For Versions (all)




Total Issues: 376 Statistic Type: Components

Many thanks to BE/CO for providing the tool and support

Interlocked system faults

Summary of interlocked system faults
(Mar'12 - Mar'13)


Summary of interlocked system faults (Mar'12 - Mar'13)		
Type	#	%
SEU (surface)	1	3.23%
Power Supply Fail	1	3.23%
HV Power Supply Drop	4	12.90%
Connection Lost: CMW	5	16.13%
BLECF optical link issues	3	9.68%
BLETC optical link issues	8	25.81%
Other optical link issues	9	29.03%
Total	31	



All types of system faults

Summary of all system faults
(Mar'12 - Mar'13)

Summary of all system faults (Mar'12 - Mar'13)		
Type	#	%
SEU (surface)	3	4.29%
Power Supply Fail	1	1.43%
HV Power Supply Drop	4	5.71%
Connection Lost: CMW	6	8.57%
Sanity Error: CMW	9	12.86%
Sanity Error: IC	3	4.29%
Sanity Error: LIC	6	8.57%
Sanity Error: SEM	10	14.29%
BLECF optical link issues	7	10.00%
BLETC optical link issues	11	15.71%
Other optical link issues	10	14.29%
Total	70	




Listing main actions to be performed or developed in the system

LHC BLM SYSTEM: LS1 FORESEEN CHANGES

Modifications in the tunnel installation

ECRs in preparation

- Dismantle all detectors in the ARC and DS (~2500) and
- Dismantle 70% of the detectors in LSS (~1000)
 - in order to allow intervention in the interconnections
- Exchange 40 multiwire cables with the NES18 type
 - Reduce noise on 240 detectors
 - Continuation of campaign to exchange all noisy installations
- Relocate 816 detectors
 - New supports, cable extensions, cable trays needed
 - Improve protection
 - see Eduardo Nebot Del Busto's presentation for the reasons




New locations of the detectors

Modifications in the tunnel installation

ECR in preparation

- Exchange 360 acquisition crate **backplanes**
 - Improve stability, add features
- Modify 309 **signal** distribution boxes
 - Allow reset of the complete sector
- Installation/Connection to WorldFIP
 - Straight Section needs additional electronics
 - Allow remote access per card
- Add everywhere High Voltage divider boxes
 - Increase accuracy
- Modify 20 High Voltage distribution boxes
 - Add suppressor diodes and resistors
 - Only in areas with high losses



Improved backplane

➤ For more info see Ewald Effinger's presentation in 73th MPP




Modifications in the ACQ electronics

- Modify all BLECF modules (~700)
 - Change limit for the HV level detection flag
 - ▶ currently too restrictive for proper use by the SIS.
 - ▶ change detection level from 1370V to 950V
 - Change laser settings of the GOH
 - ▶ increase transmission power to give more margin of attenuation
 - ▶ add ~ 30% more power



Modifications in the surface installation

- Replacement of all racks
 - Add temperature regulated racks
 - Remove and disconnect **complete installation** (crates, cables, power etc)
 - Reconnection/replacement of all fibre patchcords (~1600 fibres)
- Modifications for apt interventions
 - Replacement of all rear connection cables
 - Allow direct access to power supplies and rear rack connections
- Add two new crates for possible future **Injection Inhibit** implementation
 - Install additional racks in P2 and P8
 - Separate problematic monitors for injection
 - see also Wolfgang Bartmann's presentation




Modifications in the TC electronics

- Maintenance of all processing modules (~400)
 - Fix or Replace ~ 20% of mezzanines
 - Clean-up of the optical adaptors and connectors
- Shuffle optical links
 - Expect to improve availability by removing common mode failure
 - 80% of optical link errors and failures were in LK: 1-2



Accumulation of dust on the connectors



Modification of the BLECS firmware

- Combiner and Survey firmware modifications:
 - Improve regular automatic **system checks**
 - ▶ block increase of input offset
 - ▶ add timeout for check completion
 - Improve **connectivity check**
 - ▶ Increase range of values allowed
 - Improve **Energy** value reception and logging
 - ▶ fast changes of energy values are propagated to the BLETC modules but not logged
 - Add compatibility with new CPUs
 - ▶ new VMEbus core with MBLT mode
 - ▶ new memory map optimized for block transfers
 - Preparation for the “**Injection Inhibit**” feature

Modification of the BLETC firmware

- Processing Module firmware modifications:
 - Improve **PM** and **UFO Buster** buffers
 - ▶ increase size to 43,690 samples per channel
 - Improve **XPOC** buffer
 - ▶ split data and triggers per beam (not sure yet if possible)
 - Improve data for **Collimation Beam Based Alignment**
 - ▶ increase data rate (not sure yet if possible)
 - Add compatibility with new CPUs
 - ▶ new VMEbus core with MBLT mode
 - ▶ New memory map optimized for block transfers

Application Improvement wishlist

- **Internal Parameters** application (BE/SW)
 - automatic fill of serials when a card is exchanged
 - step increase of connectivity check limits
- **System Status** application additions (BE/OP)
 - give global overview
 - provide system error cause
- **System Management** application (BE/OP and BE/CO)
 - Generate new monitors/parameters, Drive settings to electronics, Initiate/Abort checks
 - provide a clear procedure for actions to be taken
 - avoid errors due to complexity of the generic applications (generation, trim etc)
- **Monitor Factor** application (BE/OP)
 - show history
 - compare two points in time
 - roll back of changes (very useful for MDs, etc.)

Commissioning after LS1


- In short, equal to LHC start-up
 - Check all optical connections
 - Update all serial numbers
 - Check behaviour of each card
 - Calculate new Connectivity check limits
- Radiation Source measurements
 - ▶ First sector to be available already in Nov'13 !!
- Complete MPS checklist

Summary

- Most of the system will be completely re-installed
- All system modules will be modified and undergo maintenance
- Primarily the changes aim to **reduce failures and errors**
 - Optical links
 - HV power supply
 - Sanity checks
- Additional changes aim to improve
 - Remote control of cards and crates
 - Data collection and distribution
 - Improve ability to maintain the installation
- Complete re-commission will be necessary
 - Rad-source measurements
 - MPS checklist

THANK YOU

LHC BLM System Overview



Modifications on additional systems

- New design of the **BLM Direct Dump** system
 - Follow changes in the LHC Beam Dump system
- Deployment of new acquisition system for the Diamond detectors