



**CNGS Run 2007
and
Ensuring Safe and Reliable
Operation of CNGS as of 2008**

Edda Gschwendtner

On behalf the

CNGS Secondary Beam Working Group

Outline



- **Introduction to CNGS and OPERA**
- **CNGS Run 2007**
 - **Beam Performance**
 - **Results**
 - **Radiation Effects on Electronics**
- **Modifications for 2008**
 - **Strip-line**
 - **Shielding Modifications**
- **Operational Aspects**


CNGS Challenges




- **High Intensity, High Energy Proton Beam (500kW, 400GeV/c)**
 - *Proton beam: Tune!!*
 - Induced radioactivity
 - In components, shielding, fluids, etc...
 - Intervention on equipment ‘impossible’
 - Remote handling by overhead crane
 - Replace broken equipment, no repair
 - Human intervention only after long ‘cooling time’
 - Design of equipment: compromise
 - E.g. horn inner conductor: for neutrino yield: thin tube, for reliability: thick tube
- **Intense Short Beam Pulses, Small Beam Spot (up to 3.5×10^{13} per $10.5 \mu\text{s}$ extraction, $< 1 \text{ mm}$ spot)**
 - *Proton beam: Interlock!!*
 - Thermo mechanical shocks by energy deposition (designing target rods, thin windows, etc...)

→ **most challenging zone: Target Chamber** (target–horn–reflector)

CNGS Facility




OPERA




11th January 2008:

- 85202 bricks (out of 154000) are produced
- Production is stabilized at a rate of 3 drums/day (700 bricks).
→ Finished by 10th June 2008.

brick production/filling



Brick Assembly Machine, BAM



BAM in *Dark*
5 Piling/Pressing stations
1 Wrapping station




Brick Manipulator System, BMS

Drum loader
(1 drum = 234 bricks)

Emulsion Scanning Systems




CSd alignment & CSd brick connection



Brick films alignment


- 6 lines for alignment (crossing point)
- 1 line (inclined) for plate numbering




Scanning in Europe:

- **E**uropean **S**canning **S**ystem at 20 cm²/h
- at LNGS: CSd scanning for quick confirmation of neutrino interaction
- ~30 ESS distributed at 11 labs for scanning bricks to locate vertex interaction
→ Bari, Bern, Bologna, LNGS, Lyon, Napoli, Salerno, Neuchatel, Roma, LNF, Padova

Scanning in Japan:



CNGS Run 2007



Commissioning (week 38-40):

- Setting up of SC
- Interlock tests
- Extraction
- Horn/reflector tests
- Stripline modification
- Setting up of secondary beam
 - Alignment horn vs. target vs reflector
 - TBID calibrations
 - Study neutrino/antineutrino behavior
- Increase of intensity

→ Total: $0.5 \cdot 10^{17}$ pot

Physics run (week 41-43):

- Start Friday, October 5th, 5:30 pm
- Stop of beam 5 days prior than planned due to failures in the ventilation caused by radiation effects in the electronics
 - Many efforts and modifications for CV done
 - However, failure in switching to access mode in a safe manner

→ Total: $7.9 \cdot 10^{17}$ pot

CNGS Extraction and Transfer

courtesy of J. Wenninger



- **Extraction line and equipment very stable with respect to 2006.**
 - Setting of main magnets and major corrections fully reproducible.
 - Interlock settings for all dipoles and quadrupole converters reproducible.
- **Excellent beam stability**
 - All 23 BPM measurements are well within the design tolerance of $\pm 4\text{mm}$.
 - All extractions hit the target within tolerance (below $\pm 0.5\text{mm}$).
 - Stable beam losses.
- **Beam Intensity**
 - SC of 39.8s with 1 long FT, CNGS1, CNGS2, CNGS3, 1 MD
 - 45400 extractions in 23700 cycles.
 - Average intensity on target of $1.7 \cdot 10^{13}$ protons per extraction.
 - Maximum intensity: $2 \cdot 10^{13}$ protons per extraction.

File

Oct 01 17:03:04 SPS - CNGS1 SFTPRO1 - 0...

CNGS.TNM/Acquisition

(1 of 1 acquisitions)

User: SPS.USER.CNGS1 Time: 01.10.2007 17:03:03

BFCT

Extraction 1: **2 x 1.4E13pot/extr.**
Extraction 2:

Movable Monitor Pit 1


Extraction 1: 3.3658E-01
Extraction 2: 3.3637E-01

Movable Monitor Pit 2

Extraction 1: 1.1255E-02
Extraction 2: 1.1239E-02


Pit 1

Horizontal




• Pit 1: sensitive to target vs horn alignment

Vertical




Pit 2

Horizontal



• Pit 2: sensitive to beam vs target alignment



Vertical



Acquire Start Monitoring Stop Save Continuous Saving

/user/slops/data/2007/OP_DATA/CNGSMuonMonitors


Neutrino/Antineutrino Behavior




Comparison of measurements with first preliminary simulations:

- Earth magnetic field: 0.4 Gauss
- Shielding of iron wall of decay tube not yet included!
- deflection is bigger in simulations


First CNGS Neutrino Interaction inside an OPERA Brick



Events inside Bricks




Vertex found- quasi elastic event



CNGS Events inside Bricks



Event: 186970035



IP (micron)
2.03 μm
4.16 μm
3.05 μm
2.72 μm
14.89 μm

CNGS Run 2007 – Summary




- **Successful Repair and Modification of the Horn and Reflector in 2007**
(As a consequence of a water leak in the reflector cooling circuit in 2006)
 - **Restart of the CNGS facility as scheduled on 17 September 2007 for six weeks**
- **CNGS beam performance: very good**
 - In total: $8.5 \cdot 10^{17}$ protons on target
 - **38 OPERA events in bricks**
 - **More than 400 events from interactions outside OPERA detector**
- **Failures in the ventilation system due to radiation effects in electronic**
 - **Consequences on**
 - safety of installed equipment – possible temperature rise
 - access system – switch between beam and access mode
 - **Stop of CNGS beam 5 days ahead of time**
- **Other issue: Broken cable in one of the flexible junctions in the reflector striplines**


Modification 2008: Stripline Flexible Connection I



Function:
connect striplines
to transformer



Discovered on Reflector
August 2007



Twisted & brazed
cables, Ag-Cu.
Fatigue (pulses) on
strands plus force from
thermal expansion
stripline caused **cracks**
& fatigue failure.




Modification 2008: Stripline Flexible Connection II



New Design to ensure reliability

To horn/reflector


- Plates instead of twisted cables, no brazing
- Flexible part to absorb thermal expansion



- extended calculations (magnetic, thermal, fatigue)
- measurement of thermal expansion
- tests (prototype, metallurgy, installation, endurance)

→ Installation (horn & reflector):
May 2008


CNGS Electronics Layout



Present Situation: Expected Dose Levels



Gy/yr for a nominal CNGS year of $4.5 \cdot 10^{19}$ pot




A. Ferrari, L.Sarchiapone et al, 2007, FLUKA

Commercial electronics typically does not fail below 10 Gy

Present Situation: Expected High Energy Hadron Fluence



Energetic (> 20 MeV) hadron fluence ($\text{cm}^{-2} \text{yr}^{-1}$) for a nominal CNGS year of $4.5 \cdot 10^{19}$ pot



A. Ferrari, L.Sarchiapone et al, 2007, FLUKA

→ Single Event Effects on electronics (bit flip, single event upsets...)

Modifications 2008: Radiation on Electronics



- **Electronics with failures installed in Service Gallery TSG4 and Ventilation Chamber TCV4**
 - Direct view to target chamber (ventilation ducts, etc...)
 - Radiation levels there: too high for commercial components:
 - **No failures in electronics upstream of TSG4 in 'safe area'**
 - Radiation levels there: ok for beam intensities during 2007 run
 - However, failures probably would have happen for a longer CNGS run.
- **Move electronics out of downstream TSG4 and out of TCV4**
- **Create 'radiation safe' area**
- adding adequate shielding and move all the electronics in there
 - Address the sensitivity to radiation of the installed electronics and investigate upgrade possibilities to radiation-tolerant components
 - Assure a mean time between failures of at least 1 year → redundancy and preventive maintenance actions
 - Install radiation monitoring system for electronics as in LHC

→ **We aim for beam on 28 May 2008**


Ventilation Units in TSG4



TSG44

Electronics to be moved out

'Safe' Area for Electronics



Electronics Racks

Battery charger

Transformer

Switchboard

TSG4


Control Equipment in the CNGS Area:

Ventilation System, Crane, Fire Detectors, Transformers, Battery Charger, Switchboard, Ethernet,

Control for Target, Shutter, Decay Tube, Temperature Probes, Horn & Reflector Cooling system, Radiation Detector, Beam Instrumentation (BLMs, TBID, BFCT, BPMs)

New Shielding Layout


Radiation safe area
 Radiation reduction at order of $\sim 10^4$



CNGS Dose Measurements



measurement from 20/11/2007 (1 month after beam off) in $\mu\text{Sv/hr}$



* 40 cm from ventilation unit first floor/ground floor
 ** in the aisle/contact ventilation unit


- No work close to the “hot” areas in TCC4
- Planning and execution of the works in-situ
 - same procedures as with the horn repairs
 - Optimization of design and execution taking into account RP and safety constraints
 - Detailed planning of activities in parallel to dose planning
 - Supervision of the works/workers in-situ
 - use of appropriate materials for RP and waste handling

Operational Aspects




Strict access procedures:

- Minimum 1day waiting time for access
 - change to access mode in ventilation → reliable system!
 - RP: air and dust probes, dose map, etc...
- For any access to CNGS: shielding plugs must be opened (~2hrs).
- In case of horn/reflector/target exchange: remove entire shielding in TSG41 (1-2 weeks).
- In case of transformer exchange: remove all shielding in TSG4 (1-3 days)



Operational Aspects



Survey of Radiation on Electronics



→ dose, 1 MeV neutron equivalent fluence and high energy hadron fluence measurements:

- Last period of 2007 run: 2 RadMon monitors X
- 2008: > 5 RadMon distributed in CN GS area

Operational Aspects



- **Continuous radiation monitoring of prompt radiation, released radioactivity and induced radioactivity**
 - warning, interlocks
- **Ramses detectors:**
 - Stray radiation monitoring stations: gamma & neutron monitors
 - Induced activity monitors
 - Ventilation monitoring station: gas monitor & aerosol sampler
 - Hand & foot monitor
 - Tools & material controller
- **ARCON system**
- **Remote radiation survey mounted on overhead crane**



Operational Aspects



- In order to take into account the new shielding layout **update of**
 - Access procedures
 - Horn/target exchange procedures
 - Intervention/maintenance procedures
- **No significant changes in the operational aspects**
 - Main effect on time needed to remove additional shielding.
 - However, time-consuming manipulation only done when exchange of horns/target is planned.
 - Marginal compared to cool-down time.

Summary



- **Very good beam performance during CNGS run 2007**
- **Radiation effects in electronics**
 - Move electronics
 - Create 'radiation safe area' by adding shielding
- **Protection of humans, electronics and equipment is assured**
 - Updated access procedures, radiation monitors, preventive maintenance, shielding, interlocks



MANY THANKS!!!!

**to all people for their contributions to the
operation and shutdown activities of CNGS!**

**AB/OP - AB/CO - AB/PO – AB/ATB - RP/SL - PH/DT1
- TS/MME – TS/CV – TS/IC**



Spare Slides

OPERA Experiment





Basic unit: brick:

56 Pb sheets + 56 photographic films (emulsion sheets)

lead plates: massive target

emulsions: micrometric precision




10.2 x 12.7 x 7.5 cm³

Expected Neutron Fluence



1 MeV eq. neutron fluence ($\text{cm}^{-2} \text{yr}^{-1}$) for a nominal CNGS year of $4.5 \cdot 10^{19}$ pot



M. Brugger, A. Ferrari, L.Sarchiapone, 28.11.07, FLUKA

CNGS Performance



For CNGS performance, the main issues are

- the geodesic alignment wrt. Gran Sasso

Examples: effect on V_T cc events



horn off axis by 6mm	< 3%
reflector off axis by 30mm	< 3%
proton beam on target off axis by 1mm	< 3%
CNGS facility misaligned by 0.5mrad (beam 360m off)	< 3%

- the beam must hit the target very accurately
- horn and reflector tables NOT motorized

CERN NEUTRINOS TO GRAN SASSO

Underground structures at CERN


- █ Excavated
- █ Concreted
- █ Decay tube (2nd contract)



CNGS Proton Beam Parameters



Beam parameters	Nominal CNGS beam
Nominal energy [GeV]	400
Normalized emittance [μm]	H=12 V=7
Emittance [μm]	H=0.028 V= 0.016
Momentum spread $\Delta p/p$	0.07 % +/- 20%
# extractions per cycle	2 separated by 50 ms
Batch length [μs]	10.5
# of bunches per pulse	2100
Intensity per extraction [10^{13} p]	2.4
Bunch length [ns] (4σ)	2
Bunch spacing [ns]	5
Beta at focus [m]	hor.: 10 ; vert.: 20
Beam sizes at 400 GeV [mm]	0.5 mm
Beam divergence [mrad]	hor.: 0.05; vert.: 0.03



Expected beam performance: 4.5×10^{19} protons/year on target