



RF Commissioning

D. Jacquet and M. Gruwé




RF systems in a few words (I)

- A transverse dampers system
- ACCELERATING SYSTEM
- 4 HV bunkers containing:
 - the klystron modulators
 - the fast protection systems (crowbars)
 - the high voltage switches
 - and the klystron heater power supplies.
- 16 high power lines :
 - HV cables, klystron, circulators, RF load, wave guides and the high power couplers
- 16 superconducting cavities:
 - 8 per beam on each side of point 4, powered independently by the high power lines.
- Low level RF system...



RF systems in a few words (II)


- A sophisticated low level RF system (called cavity controller)
 - For each RF line:
 - RF Feedback
 - a Tuner Loop
 - a Klystron Ripple Loop
 - and a Conditioning system
 - => RF control for each cavity is independent.
- A beam Control system (generates the 400MHz signal for the cavity controllers)
 - For each ring:
 - Frequency Program
 - Phase Loop
 - Radial Loop
 - and Synchronization Loop
- An RF synchronization system implements the bunch into bucket transfer from the SPS into each LHC ring.




RF cryo

4 superconducting cavity modules made of four cavities.


=>The temperature of all four cavities in a module is not controlled independently. Each superconducting cavity module is connected to the QRL (4.5K).






Tests

- Power systems commissioning
- Superconducting cavities commissioning
- Klystrons & cavities feedback loops
- RF synchro & beam control
- Transverse Dampers




POWER SYSTEMS COMMISSIONING

- The individual high power RF systems have to be set to full power (short circuited).
 - The klystron power converters switch ON, and HV settings : done.
 - HV fast protection system, HV switch to individual klystron and klystron modulators : ongoing (one out of 4 is done).
 - Low level equipment set-up for open loop operation : done
 - Commissioning and calibration of high RF power equipment (modulator, RF drivers, klystrons, circulators, loads, directional couplers, ...): on going for 8 cavities, for the other 8 their collectors have to be replaced before the commissioning can start.




CAVITIES COMMISSIONING (I)

- Can start only when Power Commissioning has been completed
- Additional Services needed
 - Access system operational in "RF test mode" permitting RF in cavities
 - Cryogenic system commissioning completed (4.5 K): Cavities cooled down and pressure in the QRL headers stabilized, process control and procedures for cavity operation verified
 - Radiation monitors operational (RAMSES system commissioned)




CAVITIES COMMISSIONING (II)

- Low power verification and measurements:
 - Couplers and antennas.
- Controls:
 - Check the interlock, signal acquisition, analog multiplexers
 - Check the cavity tuning system and main couplers positioning system
 - Set up the control for coupler and cavity conditioning: feedback loops on cavity and main coupler vacuums, He pressure
- Tune the RF power with cold cavities.
- Pre-calibration measurements:
 - Antenna/Couplers/Klystrons/Tuners
- Conditioning of
 - the high power couplers up to full power
 - and the cavities up to full field
- Setting up of the tuning loop for each individual cavity





CAVITIES COMMISSIONING (III)

- Conditioning of the cavities (cleaning of the cavity surface):
 - A software (Labview) has been developed to automate the conditioning process: The cavity field is raised by small steps for different position of the couplers, until there is full power and full field in the cavities.
 - At this stage, operation team may be involved as the cavities can be conditioned in parallel and the procedure is automatic.
 - The conditioning of the cavities in sector 4-5 will start as soon as the cryo is ready.
 - The duration off the test is heavily linked to the cryo stability.
 Without cryo problem, it should take 1 week to prepare the cavities and one week/cavity for the conditioning.




KLYSTRONS & CAVITIES FEEDBACK LOOPS






KLYSTRONS & CAVITIES FEEDBACK LOOPS

- The remaining Low-Level RF activity can be carried-out only after the cavities and the main couplers in a module have been conditioned.
- For each of the 16 RF lines, the following tests have to be performed
 - Fine setting up of the tuner loop
 - Setting up the klystron polar loop (reduces klystron phase ripples)
 - Setting up the gain, notch and time constants of the RF feedback loop
 - Setting up the one turn feedback loop
 - Fine tuning of the "Switch/Protection module" threshold so that we do not trip the klystron on drive transients
 - A full set of measurements: loop responses etc.
- All the above depend on the actual loop delay, klystron response, cable/antenna attenuation so that they have to be customized for each line.



KLYSTRONS & CAVITIES FEEDBACK LOOPS

- ⇒ This tests require a very specific expertise: it is not likely that OP could provide any help. The needed software will be provided by the RF team, probably using Labview.
- ⇒2 weeks per cavity are needed
- ⇒ Once all lines are commissioned, a global low-level adjustment will be performed(1 week).



RF SYNCHRO & BEAM CONTROL I

RF synchro:


- Generation of kicker pulses, beam dump signals, Frev, clocks to the experiments and the SPS
- All hardware modules are ready. They have to be tested as far as possible without beam.
- The tests will start mid-January. Expected to last 8 weeks. They have to be completed 3 months before beam.

Beam control:


- Set up the 400 MHz reference generation in the Beam Control crate to drive the Cavity Controllers
- Commission frequency Prgm, synchro loop, radial loop and phase loop without beam
- 2 modules are still under design.
- Tests done from March 2008 till beam start up.



- ⇒ These systems are located in SR4, so accessible even during beam. Most of the commissioning will be done with beam.
- ⇒ The commissioning has to be done by the expert who designed the systems.




Function Gen. Function Gen. LHC LLRF Beam Control A function sets the RF **DUAL** frequency on the injection FREQUENCY -(from P. Baudrenghien) plateau and through the ramp **PRGM Dual Frequency** Program and Rephasor FPGA Injection frequency, injection Function Gen. phase and stable phase will be Radial steering with radial loop adjusted by observing these two **SYNCHRO** DDS1 DDS2 $\Delta\phi_{\mathsf{sync}}$ signals MODULE FIRF Prog 1 F RF Prog 2 Phase Sync Discri Synchro loop Phase switch RF/Fprog phase $\Delta\phi_{ m phase}$ Difference Bunch/RF and Phase phase Low-level Averaging Loops Discri Vt/RF **VCXO** Beam/Vit phase F out 7 TeV Processor Phase phase **BEAM** shifter Phase loop synthesizer CONTROL **CORDIC** CORDIC (+ AGC?) (+ AGC?) 1/h **LOOPS** divider ADC MODULE ADC ADC ADC Radial loop Analog I/Q Analog I/Q Master F RF Master F rev demod demod Master Frf Master Frf The VCXO **BEAM FPGA** generates the RF PHASE **BEAM** Fiber Optic sent to the Cavity ADC **MODULE** POS TX Controllers MODULE Radial PU Front-end To Ring 1 Cavity Controllers (fibers) Delay adjust This synthesizer replaces the lb RF Summing Network frequency program during physics 180 deg hybrid Beam 1 Phase PU Rad. PU Cavities November 8th 2007 D. Jacquet and M. Gruwé 16




TRANSVERSE DAMPERS (ADT)


Principle:

- Designed to damp the transverse oscillations of the beam at injection to preserve beam size
- The system measures the transverse position of the beam (both horizontal and vertical) and applies a correction
- System consists of 4 independent damper systems (2 per beam) with
 - 4 kickers per beam and plane
 - Dedicated pickups (2 per plane and per beam)
 - Electronics on surface (driver amplifiers, PLC controls, fast interlocks)





Overview of one ADT system





ADT (high power part)






ADT Commissioning

Commissioning:

- Controls: Interlocks, power supply controls, application software. Done.
- Power converter tests: interlocks, switch ON. Done.
- Damper power: Done.
 - Damper tetrodes power amplifiers
 - Kickers
 - Drive amplifiers
- Damper Low Level system: feedback loops and the pickups. Ongoing.
 - One of the card is not completed yet.
 - Calibration will be finished as soon as card is ready (one month before beam start up)
 - 10 systems of pick-up have to be calibrated. This requires an access, 2 days per system is needed.
 - Some work can be done with simulated beam, but most of the setting up requires beam.



Conclusions

RF systems commissioning

- The RF power commissioning is ongoing
- Once the lines are ready, the cryo in sector 4-5, then in sector 3-4, have to be ready to start the cavities conditioning.
- OP can be involved in the cavity conditioning, but the other systems require too much expertise.
- The software needed for the hardware commissioning will be provided by the RF group itself.