



# **LHC Beam Instrumentation**

## **Performance, Issues and Plans**

Rhodri Jones on behalf of the  
CERN Beam Instrumentation Group

**CMAC – 14<sup>th</sup> March 2013**

# What Operation Wants!

Jorg Wenninger (BI Day 2012)

We want measurements of all beam parameters that cover the full LHC dynamic range

They should be

- *fast,*
- *accurate (give us 10 x better than what we need and we are happy),*
- *cool and cooled,*
- *bunch by bunch (all in //) and turn by turn,*
- *without gain changes or other operational hazards.*







# What we Managed to Provide

**LHC BLM SYSTEM:  
2012 OPERATION**

# Overall BLM Performance



Fault Down Time System by System




Beam Interlock System First Trigger

- **Very reliable and central system for safe LHC operation.**
  - At 4 TeV now have very well tuned thresholds.
  - Heavily used in CCC and for analysis under all LHC operational conditions.
- **Known issues to be treated during LS1:**
  - Unavailability due to errors from communication link - failures increased dramatically
    - Daily automatic analysis of all links allowed cards to be exchanged before affecting LHC availability
  - Saturation for very fast losses (mainly injection)
  - High voltage breakdowns


# Overall BLM Performance

## • Improvements in 2012

- New data buffer for automatic collimator beam based alignment
  - Delivers 82ms integral from each BLM detector at 12.5Hz
  - Allowed much faster collimator set-up
  - Excellent diagnostic tool
    - time evolution of losses, halo population & diffusion rates
- New UFO Study Data Buffer
  - Capture buffer allowing 80  $\mu$ s integral with 4396 samples/channel
  - Automatic triggering when abnormal losses detected



Dedicated 12.5 Hz data




# LHC BLM SYSTEM: PLANS FOR LS1

# LS1 BLM Actions

- **Dismant**
  - All det
  - 70% of
- **Improve**
  - Exchan
- **Relocati**
  - 816 de

## ARC BLM relocation I

- Proposed option. Move 2nd MQ BLM to the beginning of MB.B



A. LECHNER & M. SAPINSKI

Proposed new BLM location based on signal gain

UFO Location	BLM MB.B	BLM MB.C
MB.A	80	13
MB.B beginning	--	50
MB.B end	--	7

- MQ BLM should be reduced by 50 in order to protect against UFOs at MB.B.
- OTHER OPTION. BLM located in the interconnect (vertically and ~ centered between B1 and B2) would cover all possible UFO locations (to be confirmed).

# LS1 BLM Actions

- **Additional Tunnel Work**

- Exchange of 360 acquisition crate backplanes to improve stability
- Modification of 309 signal distribution boxes
- Modification of 20 high voltage distribution boxes
  - Adding suppressor diodes and resistors
- Modification of ~700 modules for HV level detection
- Connection to WorldFIP
  - Allows additional remote access features

- **Surface Work**

- Replacement of all racks to add temperature regulation
  - Removal and re-installation of complete system
  - Reconnection of all fibre patchcords (~1600)
- Maintenance of ~800 processing modules
- Improvements to the firmware
  - Compatibility with new Linux based CPU
  - Addition of more checks and modifications to buffered data collection



# Post LS1 BLM Thresholds

- **Implement outcome of tunnel installation modification**
  - Simulation of losses & calculation of thresholds for new BLM positions
- **Implement outcome of quench tests**
  - Recalculation of interlock thresholds for BLMs protecting cold elements
    - Fast losses (10 ms, ADT + MKQ + Orb. Bump)
      - Signal 5 times larger than estimated quench level before quenching
    - Steady-state (10 s, ADT + coll. system, protons)
      - Signals reached 3.5 times higher than estimated quench level with no quench
    - Steady-state (20s , ADT + Orb. Bump)
      - Quenched at estimated quench level
  - Extrapolation to 7 TeV requires dedicated analysis + simulations
- **Modifications in Threshold Generation**
  - Implement all functionalities inside the LSA database
    - Migration from C++ stand-alone threshold generation
    - Implementation of generation algorithms in PL/SQL (BE-CO)
    - GUI provided to generate, visualise and compare thresholds
  - Should improve reliability, reproducibility and long term maintainability

CERN

# LHC BPM SYSTEM: 2012 OPERATION

# Overall BPM System Performance

- **System Performance in 2012**

- Channel availability greater than 97%
  - Deployment of automatic analysis tool during LS1
    - for improved fault detection for preventive maintenance
- Orbit Resolution in the order of 10  $\mu\text{m}$ .
  - Automatic configuration of averaging depending on bunch number tested
  - Will be implemented post LS1, pushing resolution below 5  $\mu\text{m}$
- Orbit Stability
  - Tight collimator settings and lower  $\beta^*$  possible with excellent orbit stability
  - Arcs & most of the LSS BPMs
    - Fill to Fill reproducibility of  $\sim 50 \mu\text{m}$  rms.
    - Common regions 1,2,5 & 8,  $\sim 200 \mu\text{m}$  rms.


- **Main Issues**

- Long term stability and reproducibility
  - Dependence on temperature, bunch charge and filling scheme
  - Mitigated for 2012 run but still needs improvement
- Accuracy of IR BPMs
  - In addition to the above also suffer from directivity of stripline pick-ups

# Orbit Feedback System

## System Performance in 2012


- LHC does not work without orbit FB and overall performance 2010-2012 has been remarkable (Jorg Wenninger – BI Day 2012)
- Current correction quality limits (not yet a real problem):
- Arcs + most of the LSS: BPM Fill to Fill reproducibility – 50  $\mu\text{m}$  rms.
- Common regions 1,2,5 & 8,  $\sim 200 \mu\text{m}$  rms (directivity of stripline BPM)



Fill to fill difference is very small and sufficiently good ( $\leftrightarrow$  squeeze in collision)

Orbit correction at IP to bring beams head-on (here B1H correction)

Slow drift over the year  $\rightarrow$  not corrected by OFB.




# Interlock BPMs

- **Purpose**

- Ensure orbit at extraction septum stays within  $\pm 4\text{mm}$  to keep safe extraction trajectory
- A single high intensity, high energy bunch can cause damage to the septum
  - System must be capable of reacting on a bunch by bunch basis

- **Layout**

- 2 redundant BPMs near TCDQ and 2 near preceding Q4
- $90^\circ$  phase advance to minimise chance of an unfortunate orbit bump
- Uses standard LHC BPM analogue electronics BUT specific FPGA firmware
- All hardware detection and trigger of beam abort



## Operational Settings:

- Single bunch instability : 70 readings out of limits over 100 turns
- Fast Full Beam Instability : 250 readings out of limits over 10 turns

# Interlock BPMs

## Issues

- The system suffered from too many false dumps
  - BUT no known case where the interlock did not function when it should have
- As for standard LHC BPMs – system functions in 2 dynamic ranges
  - High sensitivity  $2 \times 10^9$  to  $5 \times 10^{10}$
  - Low sensitivity  $4 \times 10^{10}$  to  $> 2 \times 10^{11}$
- Originally signal attenuated from each pick-up to match arc BPM signal levels
  - Gave issues when single bunches slowly lost intensity & reached low to high sensitivity transition
- Removed attenuation to allow interlock BPMs to reach  $2 \times 10^{10}$  in low sensitivity
  - No more issues for high intensity operation

## Special Machine Conditions

- Tuning interlock BPMs for high intensity operation made them incompatible for several MDs and the p-Pb run
- Difficult to find attenuation to cover low intensity ions & medium intensity protons
- Non linearity systematically dumped the ion fills once a single bunch reached  $\sim 3 \times 10^9$

## Work underway for Post LS1 implementation






- Study possibility to cover entire dynamic range without gain switching – options:
  - Optimisation of current system, reducing spurious reflections
  - Alternative acquisition electronics : e.g. logarithmic amplifiers
- Improve diagnostics for this system which hampered understanding in 2012

# LHC BPM SYSTEM: PLANS FOR LS1

# BPM Temperature Dependence

## • Improvements Foreseen

- Installation of thermalised racks
- Maintains temperature within  $\pm 0.2^\circ\text{C}$
- Prototype successfully tested in 2012



1 bin  $\sim 30\mu\text{m}$




# Collimator & LSS BPM System

- **Diode ORbit & Oscillation System – DOROS**

- New technique developed to provide accurate beam position measurements for collimator BPMs




- Optimised for position resolution, absolute accuracy for centred beams
- Can also provide phase measurement for continuous local beta-beat calculation with very low oscillation amplitudes
- No bunch-by-bunch measurement but could be gated



Diode Orbit Measurement

2 channels shown for one pick-up plane,  
one 19" 1U unit accommodates 8 channels

# Results with DOROS



- Resolution <100nm
- Tested in both the SPS collimator prototype and in parallel to existing BPM system in LHC
- Preparing the cable infrastructure during LS1 for TCT collimators and LSS BPMs

# LHC SYNCHROTRON LIGHT SYSTEMS

## 2012 OPERATION

# BSRT Operation in 2012

## Problems encountered in 2012

### Electro-magnetic coupling - heating

- Mirror support failures, coating blistering → needed to replace both mirrors after August

### Absolute calibration

- Drifting due to mirror coating damage
- Noisy due to numerous folding mirrors

→ Image blurring

### Overall reliability

- auto-steering, auto-gain

## Improvements – Upgrades during 2012

### New mirrors & mirror holder

- From Si to Fused Silica bulk – reduced EM coupling
- Re-design of holder & springs to ensure mirror cannot fall off in case of spring failure

### New optics

- Simplified imaging system – lower PSF corrections

### New FESA server


- Improved reliability
- Fast bunch per bunch scans ( $\sim 12\text{Hz}$ )

# 2012 BSRT Performance

Beam 1, Fill 3333 (MD), 450 GeV

B1 Vertical

Emittance [ $\mu\text{m}$ ]



## After installation of new optics

- Excellent agreement BSRT – WS over a wide emittance range
- Magnification within 10% w.r.t. nominal
- PSF  $\sim 20\%$  smaller than typical values with old optics

$$\sigma = \sqrt{\sigma_m^2 - \sigma_{psf}^2}$$

$\downarrow$  1 mm       $\downarrow$  1.3 mm       $\downarrow$  0.8 mm

- Developing optics for lower wavelengths (lenses, folding mirrors, camera sensor), i.e 300nm or lower, to reduce diffraction

**450 GeV**

**4 TeV**




## Correction Factors

<u>Old Optics</u>	<u>New Optics</u>	<u>Old Optics</u>	<u>New Optics</u>
$\sim 0.9$	0.85	$\sim 1.1$	0.87
$\sim 0.6$	0.35	$\sim 0.7$	0.33
<b>Horizontal Plane</b>		<b>Vertical Plane</b>	

# BSRT Mirror Heating


28-Aug-2012

- Light spot observed to be off-centre
- Dumped beam & retracted mirror
- Mirror later dropped down in out position



# BSRT Heating Issue


Mirror clamps deformed by heating



Mirror coating damaged by heating?




Mirror as it would have been in place



Traces of heating at the ferrite location

# BSRT Heating Issue


- Installed new assembly during 2012/2013 winter technical stop
  - Instrumented with 6 thermocouples in vacuum distributed throughout the mirror support
  - Obtained time for 3 hour high intensity proton fill at injection to obtain data to allow further understanding of heating effects as input for FE modelling





# LHC SYNCHROTRON LIGHT SYSTEMS POST LS1 OPERATION

# BSRT Mirror Assembly Design



## • Modifications clearly required to the current design

- Several options initially being followed
  - Replacement of metallic mirror holder by ceramic parts, e.g. *Macor* (machinable glass ceramic) or *Shapal* (machinable aluminium nitride ceramic)
  - Alternative designs with fixed mirror position
    - "Sheltered Mirror" designs
    - Elliptical cross-section designs
- In parallel study ways to obtain efficient heat transfer from ferrites under vacuum conditions

CERN

# LHC TUNE SYSTEMS: 2012 & POST LS1 OPERATION



# Main BBQ Tune Systems

- **Main Issues**

- Incompatibility of tune measurement with transverse damping
  - Damper operated at high gain suppressing
  - Large octupole currents & chromaticity broadening tune peak
- 50Hz mains harmonic interference at low oscillation amplitudes

- **Solved in 2012 through implementation of gated BBQ system**

- Gating on bunches for which the damper operates at lower gain
- Long, non trivial development resulting in first prototype for summer 2012
- Operational for rest of 2012 with basic functionality



- **Post LS1 Operation**

- Installation of dedicated pick-ups for gated tune
- Software upgraded to allow full gated tune functionality



- **Feedback compatibility with QPS**

- Fast tune changes induce false QPS quench signals
- TE/MPE considers introducing different threshold levels after LS1
- Better tune signal with gating should help reduce spurious tune jumps

# 2012 Schottky System Performance


- *Run with IONS in 2011*

- Good Schottky signals observed on all ion fills
- Reliable single bunch measurements for the tune
- Chromaticity measurements also possible



- *Run with Protons in 2012*

- Signal good on B1H for single & multi bunch measurements at injection & stable beams
- Large coherent signals saturate and destroy the pre-amps in the other systems!
- Still the only system capable of bunch by bunch tune and chromaticity measurements in a non invasive and transverse damper independent way



# Schottky Systems Post LS1

- **Overhaul of all Schottky pick-ups**
  - Reduction of reflections for better return loss on waveguide-to-coaxial transitions
    - New transitions to be manufactured
- **Improve symmetry of opposite electrodes**
- **Replace all internal SiO<sub>2</sub> coaxial cables**
  - Some are leaking argon into vacuum
  - Same issue with collimator BPM cables due to non-adapted material choices and welding procedures
    - Followed up by EN/MME and BE/BI teams directly with manufacturer
- **Overhaul of the RF signal processing**
  - Modify the gating of all front-ends
  - New RF input filter to cope better with amplifier saturation
- **Controls and software**
  - Extend the attenuator & phase shifter control to all systems
  - Adapt the front-end control software to the hardware modifications.
  - Complete replacement of the Java user application software

# OTHER BEAM INSTRUMENTATION SYSTEMS 2012 & POST LS1 OPERATION

# Other Systems I

- **Wire scanners**

- Suffered vacuum leak on bellows after 10,000 scans
  - Redesigning of bellows in collaboration with manufacturers to obtain lifetime of >50,000 scans
- Broke several wires due to control card / software issues
  - Need to be understood & mitigated during LS1

- **Screen Based Beam Size Measurement**

- Suffered from broken RF fingers on dummy chamber
  - Due to metallic gripping resulting from poor production and assembly procedure
  - Re-design complete and all affected systems will be modified
- Matching monitor tested but sensitivity needs to be improved

- **Abort Gap Monitor**

- Depends on light from synchrotron light monitor
- Data published @1Hz with resolution that varies with energy & species
  - Protons - required resolution (0.1 of the quench level) met at all the energies
  - Pb - required resolution only met from 1.5TeV onwards
- The present level of reliability doesn't allow for inclusion in the interlock system

- **Longitudinal Density Monitor**

- Integrating for 5 minutes achieved a resolution of  $10^{-4}$  at flat top
- LDM important during VdM scans for out of bucket beam evaluation
- Efforts in LS1 to fully integrate this into the control system



# Other Systems II

- **Rest Gas Ionisation Monitors**

- MCP failures in early 2012
  - Reasons understood & protection measures now in place
- Difficult cross-calibration
  - No intensity overlap with wire scanners during p-p runs + BSRT B2 mirror problem
- Overall interpretation of results still difficult
  - Evidence of space charge impact on measured profile (especially strong for high-brightness proton beams)

- **Beam Current Monitors**

- Very important for absolute luminosity calibration
  - Pushed LHC Beam Current Transformer performance to its limits
  - Well beyond requirements for normal operation
  - Uncertainty in the absolute DCCT calibration now at the  $< 0.3\%$  level
- Fast BCT monitors
  - Commercial toroids suffer from both position and bunch length dependence
  - Development ongoing to address these issues
  - Implementation of  $dI/dt$  system for machine protection also tested




- **Instability Monitors**

- Ongoing development
  - High sensitivity frequency domain detection system based on bandpass filters and diodes
- Replacement of fast oscilloscopes
  - More adapted acquisition system for performance & reliability

# Studies for HL-LHC


- Investigating use of diamond, silicon and liquid helium chambers as future BLMs at 1.9 K

Installation of 2 diamond and 2 silicon detectors on cold mass of Q7R3






Cryostat at irradiation position

Cold Irradiation in PS T7



# Studies for HL-LHC

- **Beam Gas Vertex Imager for non invasive beam size measurement**
  - Based on experience of LHCb VELO
  - Aims
    - 5 % uncertainty on bunch width in 3 min
    - 5 % uncertainty on beam emittance in 3 min
  - Feasibility study nearly complete
  - Next Steps
    - Approval for installation of prototype after LS1
    - Design of vacuum chamber & RF screen
    - Collaboration with EPFL for detector



# Conclusions

- **OP Perspective (J. Wenninger @ BI Day 2012)**

- The core beam control instruments are doing pretty well, but can profit from quality improvements during LS1
  - We should be careful to preserve the system performance
- This year the focus has shifted heavily towards bunch by bunch data to diagnose instabilities
  - Further bunch by bunch diagnostics should be developed

- **Main Challenges**

- Restarting after LS1 with everything back in working order
  - Most of the BLM system dismantled & re-installed
  - Wire scanners, BSRT, BTVs, BCTs, BGI & Schottky systems removed & consolidated
- Reliable emittance measurements
  - Ideally non-invasive, calibrated and bunch by bunch
  - International workshop to address this planned for April
- Reliable machine protection systems
  - Maintain BLM system at current or improved performance at higher energy
  - New interlock BPM system
  - Addition of  $dI/dt$  system based on beam current measurements