

# LINAC4 and the Upgrade of the LHC Injector Complex



# UPGRADE PLANS FOR THE LHC INJECTOR COMPLEX


- **The LIU project**
- Action plan
- Planning



# LIU Project Definition

**Mandate** (*December 2010*)

“The LHC Injectors Upgrade should plan for delivering reliably to the LHC the beams required for reaching the goals of the HL-LHC. This includes LINAC4, the PS booster, the PS, the SPS, as well as the heavy ion chain.”



Web site: <https://espace.cern.ch/liu-project/default.aspx>

Meetings/workshops etc.: <http://indico.cern.ch/categoryDisplay.py?categId=3208>

EDMS: <https://edms.cern.ch/nav/P:LIU-000363:V0/P:LIU-000363:V0>





# Importance of the Injectors...

- Luminosity in LHC depends directly upon the characteristics of the injected beam:

$$L_{LHC} = \frac{\gamma}{4\pi} \underbrace{\frac{1}{\beta^*} f_{rev} F}_{\text{Collider related}} \underbrace{(n_b N_b)}_{\text{Total current}} \underbrace{\left( \frac{N_b}{\epsilon_n} \right)}_{\text{Brightness}}$$

**Injectors' related**

- More precisely , the critical parameters for the injectors are:

$n_b$  : number of colliding bunches in each LHC ring ( $\sim$  prop. to  $1/\text{distance}$  between bunches)

$N_b$  : number of protons per bunch

$\epsilon_n$  : normalised transverse emittance (assuming round beams)

- Beam transverse brightness ( $N_b/\epsilon_n$ ) is an especially important quantity which governs space charge effects at low energy in the injectors





# Goals § Means

## To increase performance

### Brightness ↗

- ⇒ Increase injection energy in the PSB from 50 to 160 MeV, Linac4 (160 MeV H<sup>+</sup>) to replace Linac2 (50 MeV H<sup>+</sup>)
- ⇒ Increase injection energy in the PS from 1.4 to 2 GeV, increasing the field in the PSB magnets, replacing power supply and changing transfer equipment
- ⇒ Upgrade the PSB , PS and SPS to make them capable to accelerate and manipulate a higher brightness beam (feedbacks, cures against electron clouds, hardware modifications to reduce impedance...)

## To increase reliability and lifetime (until ~2035!) (tightly linked with consolidation)

- ⇒ Upgrade/replace ageing equipment (power supplies, magnets, RF...)
- ⇒ Improve radioprotection measures (shielding, ventilation...)





# UPGRADE PLANS FOR THE LHC INJECTOR COMPLEX

- The LIU project
- **Action plan**
- Planning





Surface building



Equipment hall



New 2.8MW klystron




LEP 1.3MW klystron



# Linac4 architecture

Linac4 is a normal-conducting H- linear accelerator with an energy of 160 MeV, made of:

1. Pre-injector (source, magnetic LEPT, 3 MeV RFQ, chopper line)
2. Three types of accelerating structures, all at 352 MHz.
3. A 70 m transfer line towards the PS Booster (plus a dump line at linac end).



Linac length ~ 80 m

	Energy [MeV]	Length [m]	RF power [MW]	Focusing
RFQ	0.045 – 3	3	0.6	RF focusing
DTL	3 – 50	19	5	112 perm. quads
CCDTL	50 – 102	25	7	21 EM quads
PIMS	102 – 160	22	6	12 EM quads








## Linac4: Achievements in 2012

- RFQ completed and installed in the 3 MeV test stand – RF coupler fabrication started, RF high-power tests January 2013.
- New H<sup>-</sup> source being tested. Plasma production optimized, problems with HV extraction (bad ceramics insulator received from industry, being cleaned/repared – reassembly in progress)
- Prototypes 2.8 MW klystron successfully tested, first unit delivered to CERN by CPI, Thales unit to be delivered before end of year.
- 1<sup>st</sup> DTL tank section (half Tank1) completed, alignment checked. Components for other tanks in production.
- 1<sup>st</sup> batch of 2 CCDTL modules from BINP Novosibirsk received: remaining 5 to be delivered beginning 2013.
- Production of PIMS modules started in Poland.
- Final large orders (magnets) placed, production so far on schedule.



# Linac4: Tunnel




- Waveguide network completely installed
- Cabling and piping completed
- Ion source Faraday cage and support installed








# Linac4 hardware construction (1)






# Linac4 hardware construction (2): PIMS...

- cavity #1, length 1.4 m, weight ~700 kg
- $ZT^2$ : 26.5 M $\Omega$ /m (95% of HFSS calculation)
- cell to cell coupling k: 5.6% to 4.8%
- $E_{S,max} = 1.8$  Kilpatrick (33.2 MV/m @ 352MHz)



PIMS prototype


day	$T_{RF}$	com.	$P_{peak}$	$T_{pulse}$	vacuum	X-ray <sub>axis</sub>	X-ray <sub>ext</sub>	
2010	[h]			[ $\mu$ s]	[mbar]	[mSv/h]	[ $\mu$ Sv/h]	
2.11.	2	setup	1 kW	800	$5 \cdot 10^{-6}$	0	0	
3.11.	6	multipactor	1 .. 10 kW	25	$8 \cdot 10^{-6}$	0	0	
4.11.	6		700 kW	180	$8 \cdot 10^{-6}$	12	14	
5.11.	2	modulator	700 kW	300	$4 \cdot 10^{-6}$	15	20	
8.11.	4	roof, temp. sens.	700 kW	500	$1 \cdot 10^{-6}$	17	30	
9.11.	5	trigger, temp.	~ 500 kW	800	$8 \cdot 10^{-7}$	17	36	
10.11.	3		700 kW	800	$1 \cdot 10^{-6}$	25	44	
sum	28	cavity conditioned to $P_{peak} = 700$ kW, $f_{rep} = 2$ Hz, $T_{pulse} = 800$ $\mu$ s						







# PSB upgrade




All details are available at: <https://espace.cern.ch/liu-project/liu-psb/default.aspx>








# PSB H<sup>-</sup> injection chicane concept



# PSB H<sup>-</sup> injection chicane design





# PS upgrade

J.B. Adams – 25 Nov. 1959 – Design intensity:  $3 \cdot 10^{11}$  p/p

Beam Dynamics
Magnets
RF - LL
RF - HL
RF - TFB (From CONS BC 69710)
EPC
Beam instrumentation
Intercepting device
Vacuum system
Injection
Controls
Electrical system
Cooling and ventilation
Transport
Civil engineering
RP
Machine Interlocks
Alarms
Access doors
Survey

2 GeV injection

Increased intensity / bunch

Increased transverse brightness

Radioprotection








## 200 MHz Travelling Wave Accelerating Structures




One four sections cavity  
(four power couplers and two terminating power loads)



Increased intensity

Increased transverse brightness

- Beam dynamics studies and simulations
- MKDV/H impedance reduction
- Beam instrumentation
- Extraction protection upgrade
- New high bandwidth damper
- Existing damper power upgrade (power + LL)
- Existing damper removal to LSS3
- RF 200 MHz upgrade
- ecloud mitigation: aC coating (in magnets)
- New collimation system
- STI
- New MKE and extraction channel upgrade
- Beam dump upgrade
- TL protection upgrade





# UPGRADE PLANS FOR THE LHC INJECTOR COMPLEX

- The LIU project
- Action plan
- **Planning**










# Linac4 to PSB Connection



- The planning of LHC shutdowns is being revisited.
- One important goal is to implement and commission H- injection in the PSB before proceeding with the other upgrades.

**=> Linac4 must be fully ready by the end of 2016!**



**THANK U**

**FOR YOUR ATTENTION!**




# SPARE SLIDES



# Potential beam characteristics after LS2 with 25 ns

Performance after LIU:  $2.3 \cdot 10^{11}$  p/b in 3.6 mm.mrad at SPS extraction to be compared with

HL-LHC objective (450 GeV):  $2.2 \cdot 10^{11}$  p/b in 2.3 mm.mrad



Batch compression might also bridge the gap (but with 10% less bunches)...

⇒ Limited by space charge in the PS








# Potential beam characteristics after LS2 with 50 ns

Performance after LIU:  $2.7 \cdot 10^{11}$  p/b in 2.7 mm.mrad at SPS extraction

to be compared with

HL-LHC objective (450 GeV):  $3.5 \cdot 10^{11}$  p/b in 2.7 mm.mrad



**⇒ Limited by longitudinal instabilities in the PS and SPS, and by brightness in SPS**

