



EUROPEAN  
SPALLATION  
SOURCE

# The ESS Cryomodule Test Stand

Wolfgang Hees

Leader WP10, Test Stands, ESS

P. Arnold, J. Fydrych, H. Spoelstra, X.L. Wang, J.G. Weisend II


2014-07-10

# Contents

---


- ESS & its linac
- Cryomodules
- Cryomodule testing
- Test stand
- Cryogenic supply
- Outlook

# ESS - An international collaboration to build the world's leading neutron source for science & research



- driven by a superconducting proton linac: 5 MW at 2 GeV
- 146 niobium RF cavities cooled by 2K superfluid helium
- 120 elliptical cavities, grouped by 4 in 30 cryomodules
- 26 spoke cavities, grouped by 2 in 13 cryomodules
- cryoplant supplies single-phase helium via cryogenic distribution line
- 30 elliptical cryomodules are tested on test stand in Lund
- 4.5 K cryoplant with warm sub-atmospheric compression
- test bunker & RF equipment for 2 types of ell.-cavity cryomodules
- spoke cavity cryomodules tested on Uni of Uppsala's test stand

# The ESS elliptical cryomodule



- comes in two variants: medium- $\beta$  (0.67) and high- $\beta$  (0.86)
- both types are interchangeable, so the test stand can accommodate both types without major changes in waveguide arrangement and installations of other services


- acceptance tests and preparation of cryomodules, including coupler conditioning
- main purpose to verify proper functioning of the series production cryomodules
- measuring key parameters of subsystems: heat loads, resonant efficiencies, etc ...
- test bench program:
  - reception of cryomodules at ESS & prep. for test bench
  - installation on test bench & initial testing
  - warm main power coupler conditioning & RF tests
  - cool down & cold main power coupler conditioning
  - cold low level RF tests & cold high power RF tests
  - cryogenic heat load measurements
  - warm up & disconnection from test bench
  - preparation for storage and/or tunnel installation
- RF tests include:
  - measurement of couplers' RF properties including external Q-factor and impedance
  - measurement of the couplers' thermal dynamics
  - measurement of the couplers' static and dynamic heat losses
  - measurement of the cavities' maximum accelerating gradient, X-ray emissions, dynamic RF losses, quality factors, the Lorentz detuning and compensation thereof

**appx. 4 weeks**

# Layout proposal for test stand


bunker:

- magnetite loaded concrete (4 t/m<sup>3</sup>)
- wall t=1 m
- 3 chicanes



- cryoplant is about 100 m away in the coldbox hall
- start in late 2017 with the first medium- $\beta$  cryomodule
- production schedule foresees delivery of 1 CM/month
- windows of 5 m for 1<sup>st</sup> and 3 m for 2<sup>nd</sup> module for starting up of procedures and honing production and testing

# The ESS cryogenic system



Level	Heat load, W	Mass flow, g/s		Pressure, bar		Temperature, K	
		Supply	Return	Supply	Return	Supply	Return
2 K	76	<b>4.0</b>	<b>3.8</b>	$\geq 3$	$\leq 0.027$	<b>4.5</b>	6.0
4.5 K Liqu.	-		<b>0.2</b>	$\geq 3$	<b>1.05</b>	<b>4.5</b>	300
TS	<b>422</b>	tbd	tbd	<b>12.8</b>	<b>12.3</b>	$\geq 33$	$\leq 53$

- the test stand cryoplant also provides liquid helium for neutron instruments and sample environments
- cryomodule testing dominates capacity requirements & plant design
- LN<sub>2</sub> pre-cooling under investigation
- connects to test stand through a vacuum insulated transfer line containing 4 process pipes
- cryoplant sized to provide 76 W at 2 K and 6 l/hr of liquefaction
- cryoplant provides more than the required 7500 liters per month when operated in pure liquefaction mode
- due to the small 2 K load, sub-atmospheric pumping is done by warm vacuum pumps



- operation of ESS will last 40+ years
- test stand will be used for testing replacements and additions
- most of the time, though, it will be available for other activities
- the vision:
  - to make the test stand part of an ESS SRF R&D facility, needed for repair and maintenance, but also serving the wider SRF community to do R&D
  - such a facility is important for ESS, because availability of third party labs can not be guaranteed
  - without on-site repair and maintenance facilities, downtimes can reach significant lengths
- Such an R&D facility is at this point, however, neither planned nor financed !

[europeanspallationsource.se](http://europeanspallationsource.se)