

FROM RESEARCH TO INDUSTRY



TASK 10.3

5 T HTS DIPOLE MAGNET DESIGN AND CONSTRUCTION

Pre-kick off meeting WP 10 | Maria DURANTE

23/04/2013

10.3 SUBTASKS

Subtask 10.3.1 HTS accelerator magnet design

- Explore magnet concept suitable for HTS cable and ribbon based conductors providing magnetic field of accelerator quality in view of the 20 T HE-LHC dipole

Subtask 10.3.2 Bi2212 magnet developments

- Design and manufacture a prototype magnet using Bi2212 cable. This prototype will be intended to determine the highest stress allowable on such a cable and manage the wind and react manufacturing operation

Subtask 10.3.3 YBCO magnet developments

- Design and manufacture an accelerator like prototype magnet using YBCO tape based conductor and having an operating current of at least 5 kA.
- Thin (5-30 μm) HTS tape insulation that is compatible with coil epoxy impregnation will be tested

DELIVERABLES AND MILESTONES (FROM DoW)


■ D10.1 Conceptual study of HTS accelerator magnets (report)	M18	Task 10.3
■ MS64 YBCO magnet design report	M18	Task 10.3
■ MS68 Technical and economical comparison YBCO/Bi2212 magnets	M36	Task 10.3
■ MS62 Organized collaboration with DOE Program Bi-2212	M12	Task 10.1 ?
■ MS63 Cable concept design report	M12	Task 10.2
■ D10.2 Prototype cable lengths and report	M24	Task 10.2
■ MS65 Test Station Kick-off	M26	Task 10.4
■ D10.3 Parameters for choice of SC type	M28	Task 10.1
■ MS66 First Cable length for magnet winding	M32	Task 10.2
■ MS67 Report on HE-LHC Main Dipole design	M36	Task 10.1 ?
■ D10.4 Magnet Cold test	M44	Task 10.4
■ Bi2212 magnet design report	M18 ?	
■ YBCO accelerator like prototype magnet	M38 ?	
■ Bi2212 dipole magnet	M38 ?	

PARTICIPANTS (FROM BUDGET FILES)

Beneficiary short name (all costs in €)	Person-Months	Consumable and prototype direct costs	Travel direct costs
CERN	24	150 000	12 000
CEA	34	150 000	8 000
INPG	19	12 000	4 000
INFN	4		2 000
TUT	10		10 000
DTI	8	20 000	4 000
Total:	99	332 000	40 000

We have to define who, what and when.

And define who is the contact for each institute concerning Task 3.



PARTICIPANTS / SCHEDULE

Nom de la tâche	Durée estimée	Participants
5 T dipole magnet design		
magnet design options study	12 months	<i>cea, cern</i>
conductor definition	12 months	<i>cea, cern, ipng</i>
magnet detailed design	6 months	<i>cea, cern, dti, tut, infn</i>
assembling process design	6 months	<i>cea, cern, dti, infn</i>
CAD detailed design	6 months	<i>cea</i>
tooling design	6 months	<i>Cea, cern, dti</i>
components and tooling procurement		
dipole parts procurement	6 months	<i>cea</i>
tooling procurement	6 months	<i>cea</i>
manufacturing and tests		
Bi-2212 magnet manufacturing	8 months	<i>cea</i>
YBCO accelerator like magnet manufacturing	8 months	<i>cea</i>
stand alone HTS magnet testing	6 months	<i>infn, cea</i>
HTS Insert tests in outsert	6 months	

Commissariat à l'énergie atomique et aux énergies alternatives
Centre de Saclay | 91191 Gif-sur-Yvette Cedex
T. +33 (0)1 69 08 71 27 | F. +33 (0)1 69 08 69 49

DSM
IRFU
SACM

Etablissement public à caractère industriel et commercial | RCS Paris B 775 685 019