
QXF planning

G. Ambrosio, P. Ferracin, G. Sabbi, E. Todesco

3rd Joint HiLumi LHC-LARP Annual Meeting


Daresbury Laboratory, UK

11-15 November, 2013


Introduction

IR layout (by *E. Todesco*)

- IR in the present LHC





- IR in the HiLumi LHC



Introduction

MQXF overview

- Target: **140 T/m** in **150 mm** coil aperture
- To be installed in 2022 (*LS3*)
- **Q1/Q3** (by US LARP collaboration)
 - 2 magnets with **4.0 m** of magnetic length within 1 cold mass
- **Q2** (by CERN)
 - 1 magnet of **6.8 m** within 1 cold mass, including MCBX (1.2 m)
- Baseline: different lengths, same design
 - Identical short model magnets SQXF



Status

- **Conductor and cable**

- HiLumi-LHC/LARP Conductor and Cable Internal Review (16-17 October 2013)
 - Main parameters defined
 - Procurement/schedule verified
 - Fine tuning of cable geometry in progress to improve mechanical stability
- Cable fabrication for first set of short coils starts by the end 2013 / early 2014
- Mandate to Conductor WG for setting the remaining parameters
 - 95% is done
 - Goal: Functional Requirements and Specifications ready by end of this year

QXF Strand & Cable Functional Requirements

Strand

- Strand diameter
 - 0.850 ± 0.003 mm
- Nominal sub-element diameter (according to billet design)
 - < 50 μ m
- Copper to non-copper volume ratio:
 - 1:1 minimum (to be checked with QP)
- Strand twist pitch
 - 17 ± 2 mm
- Strand twist direction
 - right-handed screw
- Minimum I_c for 80% operating point on load line
 - 869 at 12 T (with self-field), 1.9 K
 - 544 A at 15 T (with self-field), 1.9 K
- RRR (after full heat treatment)
 - >150
- n-value @ 15 T and 4.2 K
 - > 30
- Magnetization
 - TBD
- Mechanical Properties
 - Irreversible intrinsic strain ($\epsilon_{irr,0}$) $> 0.2\%$
- Stability
 - $I_s \geq 3 \cdot I_{op}$
 - TBD Criteria for high-field instability at 1.9K


Status

- **Coil**
 - Cross-section and end design defined
 - End spacer optimization in progress, first short coils fabricated
- **Structure**
 - Baseline design completed
 - 2 identical 1.5 m long structures to be procured
 - Aluminium shells procured and detailing design of components in progress
- **SQXF**
 - Coil fabrication starts in early next year. First test in 2015.

Outline

- Overview
- Short model program (SQXF)
- Long model program (prototypes)
- Series production

Overview



- Short model program: 5 CERN-LARP models, 2014-2016
 - Coil fabrication starts in 02/2014
 - First magnet test (SQXF1) in 05/2015
- Long model program: 2 (CERN) + 3 (LARP) models, 2015-2018
 - Coil fabrication starts in 2015: 01 (LARP), 09 (CERN)
 - First magnet test in 08/2016 (LARP) and 07/2017 (CERN)
- Series production: 10 (CERN) + 10 (LARP) cold masses, 2017-2021

Outline

- Overview
- Short model program (SQXF)
- Long model program (prototypes)
- Series production

SQXF plan and schedule

- Definition of cable geometry in 06/2013
- Update of coil design in 07/2013
- Coil parts fabrication/optimization in progress
 - Decision on end parts for first set of coils: 12/2013
 - End spacer turn-around: ~2 months
- Coil tooling
 - Procurement
 - Parallel coil fabrication LARP-CERN
 - CERN: 1 Wind&Curing + 2 React&impreg
 - LARP: 1 Wind&Curing + 2 React&impreg
 - Winding and curing tooling by 11/2013
 - Reaction and impregnation tooling by 02/2014
- Fabrication of full practice coil starts, both at CERN and in the US, in 02/2014
- Fabrication of second set of coils starts in 03/15 (LARP), 05/15 (CERN)
- Possibility of fine tuning cable geometry by 06/2014

SQXF plan and schedule

Coil fabrication

- CERN

- Number of coils

- First set
 - 2 practice coils + 1 mirror coil
 - 5 RRP coils
 - Second set
 - 6 PIT coils
 - 5 RRP coils

- Fabrication steps

- Winding + curing + reaction + impregnation

- Fabrication time

- ~100 days (5 months) per coil
 - 1 coil produced
 - every 2 months in the 1st year
 - every 1.5 months in the 2st year
 - every 1 months in the 3st year

- LARP

- Number of coils

- First set
 - 2 practice coils + 1 mirror coil
 - 5 RRP coils
 - Second set
 - 5 RRP coils

- Fabrication steps

- First set

- FNAL & LBNL: winding + curing
 - BNL & FNAL : reaction + impregnation

- Second set

- LBNL on SQXF
 - FNAL and BNL on LQXF

- Fabrication time

- ~100 days (5 months) per coil
 - 1 coil produced every month

SQXF plan and schedule


Coil fabrication



SQXF plan and schedule


Support structure

- LARP/CERN design
- 2 SQXF structures procured by CERN
- From conceptual design to assembly and qualification
 - Beginning of 2013 to end of 2014



SQXF plan and schedule Tests

- From assembly to disassembly: 5 months
- 1st generation coils
 - First **LARP coil mirror test** in 12/2014 (Dedicated structure)
 - First **CERN coil mirror test** (mirror) in 04/2015 (SQXF structure with practice coils or LARP mirror structure)
 - First magnet test (**SQXF1**) in 05/2015
 - Assembled and tested by LARP with 3 LARP coils and 1 CERN coil
 - Then **SQXF1b** (LARP), **SQXF2** (CERN), **SQXF2b** in series (2015-2016)
 - All the coil fabricated to date will be available for 1 magnet (not shared)
 - Test of LHe containment in **SQXF2b**
- 2nd generation coils
 - LARP RRP: **SQXF3** and **SQXF3b** (2016)
 - CERN PIT: **SQXF4** (2016-2017)
- Test of 2-magnets in 1-cold-mass: **SQXF5** (2017)



Outline

- Overview
- Short model program (SQXF)
- Long model program (prototypes)
- Series production

Long model program

Plan and schedule

CERN

- **Number of coils**
 - 3 practice
 - 1 mirror
 - 11 real (5 RRP + 6 PIT)
 - Coil winding starts **09/2015**
- **Models/tests**
 - 2 models, 3 tests
 - Horiz. “simplified” tests
 - Mirror test in **11/2016**
 - First model test in **07/2017**
 - Last test **10/2018**

LARP

- **Number of coils**
 - 1 practice
 - 1 mirror
 - 16 real
 - Coil winding starts **01/2015**
- **Models/tests**
 - 3 models, 4 tests
 - Vertical tests (workshop in Dec.)
 - Mirror test in **10/2015**
 - First model test in **08/2016**
 - Last test **11/2017**

Outline

- Overview
- Short model program (SQXF)
- Long model program (prototypes)
- **Series production**

Pre-series and series production

(based on “Production Plan” from *M. Anerella*)

CERN (Q2) full length

- 10 cold masses
 - 2 pre-series/spares, 8 series
- 10 magnets
 - 2 pre-series, 8 series
- 45 coils
 - 4.5 per magnet
- 80 days per coil
- 1 coil every 15 days

LARP (Q1/Q3) half length

- 10 cold masses
 - 2 pre-series/spares, 8 series
- 10+10 magnets
 - 4 pre-series, 16 series
- 45+45 coils
 - 4.5 per magnet
- 80 days per coil
- 1 coil every 15 days
- 2 production lines

Pre-series and series production

(based on “Production Plan” from M. Anerella)

- Tooling per production line (both CERN and LARP)
 - 1 oven
 - 1 vacuum impregnation tank
 - 2 winding mandrel assembly
 - Winding while curing outer layer
 - 3 reaction tooling
 - Preparation for reaction
 - Reaction
 - Preparation for impregnation
 - 2 impregnation tooling

Pre-series and series production

(based on “Production Plan” from *M. Anerella*)

CERN (Q2)

- Coil winding starts **09/2017**
- Coil fabric. ends by **02/2021**
- First magnet test in **04/2019**
- Last magnet test in **10/2021**

LARP (Q1/Q3)

- Coil winding starts **03/2017**
- Coil fabric. ends by **08/2020**
- First magnet test in **11/2018**
- Last magnet test in **05/2021**


Pre-series and series production

(based on “Production Plan” from *M. Anerella*)

- This plan foresees LARP series magnets tested and delivered without LHe containment and cryostat
 - Cold mass and cryostat assembly, and testing at CERN of LARP magnet still to be included in the plan
- Alternative scenarios under consideration
 - Cold mass as LARP deliverable
 - Cold mass with cryostat as LARP deliverable
 - No correctors in Q1/Q3
 - Deliverable still to be tested at CERN before installation
- Also to be added: integration work


Pre-series and series production

LARP coil production




Pre-series and series production

Overview of magnet production





Conclusion/comments

- Integrated development of CERN and LARP schedules
 - Useful to verify plans, integration and check consistency
 - CERN 180 team to join asap for prototype and production schedule/plans
- **Short model program** plan reasonably well defined
 - 5 models, fully integrated CERN/LARP, 2014-2016 period
- More work to do on **long prototypes**
 - 2+3 prototypes in the 2015-2018 period
 - Enough model and time? Can we say 5 models in total?
- Much more work on **series production**
 - Still to be defined many *what and where*



Additional slides


Lengths



	Short model	Q1/Q3 (half unit)	Q2
Magnetic length [m]	1.2	4.0	6.8
“Good” field quality [m]	0.5	3.3	6.1
Coil physical length [m]	1.5	4.3	7.1
Cable unit length per coil [m]	150	430	710
Strand per coil [km]	6.5	18	30

CERN procurement plan

Procurement – MQXF Wire



Internal Review, CERN, 16/10/2013

A. Ballarín

CERN specifications

Strand diameter	0.850 ± 0.004 mm
Nominal sub-element diameter (according to billet design)	< 50 μ m
Copper to non-copper volume ratio:	
minimum	1.10
maximum	1.30
Strand twist pitch	19 ± 3 mm
Strand twist direction	right-handed screw
Minimum critical current at 4.222 K	361 A at 15 T (632 A at 12 T)
RRR (after full heat treatment)	> 150
n-value @ 15 T and 4.2 K	> 30



Strand Procurement and Cabling Plan



Month	LARP Strand Delivery kg	Cabling Run and End Use / Coil ID	Coil Winding Start Date	Strand Req. kg	Cable Unit Lengths	T ₀ 108/127 0.85 mm		T ₁ 108/127 0.85 mm		T ₂ 144/16 90.85 mm		T ₃ 144/169 0.85 mm	
						kg	mm	kg	mm	kg	mm	kg	mm
Oct-13		SQXF-PC01		39	1	124	350						
Nov-13		SQXF-PC02	Reduce weight	39	1	124	310						
Dec-13		SQXF-03		39	1	124	271						
Jan-14		SQXF04,05		79	2	124	192						
Feb-14		SQXF06,07	SQXF-PC01	79	2	124	114						
Mar-14	90	SQXF-08	SQXF-PC02	39	1	124	75			90			
Apr-14		SQXF-09	SQXF-C03	39	1	124	165	90		51			
May-14	165						165			396	180		
Jun-14			SQXF-C04				165			396			
Jul-14			SQXF-C05				165			486	90		
Aug-14		LQXF-PC01	SQXF-C06	104	1		61			486			
Sep-14		LQXF-C01	SQXF-C07	104	1		61			382			
Oct-14			SQXF-C08				61			382			
Nov-14		SQXF-C10		39	1		61			343			
Dec-14		SQXF-C11	LQXF-PC01	39	1		61			303			
Jan-15		SQXF-C12	LQXF-C01	39	1		61			264			
Feb-15		SQXF-C13	SQXF-09	39	1		61			225			
Mar-15			SQXF-10				61			225			
Apr-15		LQXF-C02		104	1		61			121			
May-15		LQXF-C03	SQXF-11	104	1		61			267	250		

Conductor Review Oct16-17, 2013

LARP Strand Specs. Procurement, Measurement - A. Ghosh

10



Apr-15		LQXF-C02		104	1		61			121			
May-15		LQXF-C03	SQXF-11	104	1		61			267	250		
Jun-15		LQXF-C04	SQXF-12	104	1		61			163			
Jul-15	200	LQXF-C05	SQXF-13	104	1		61			259			
Aug-15		LQXF-C06	LQXF-C02	104	1		61			155			
Sep-15	200		LQXF-C03				61			355			
Oct-15	150		LQXF-C04				61			505			
Nov-15			LQXF-C05							505			
Dec-15		LQXF-C07	LQXF-C06	104	1					401			
Jan-16		LQXF-C08		104	1					297			
Feb-16		LQXF-C09&C11		208	2					89			
Mar-16	200	LQXF-C10&C12		104	2					185			
Apr-16			LQXF-C07							185			
May-16	150		LQXF-C08							335			
Jun-16		LQXF-C13&C15	LQXF-C09&C11	104	2					231			
Jul-16		LQXF-C14&C16	LQXF-C10&C12	104	2					127			
Aug-16		LQXF-C17		104	1					23			
Sep-16			LQXF-C13&C15							23			
Oct-16			LQXF-C14&C16										
Nov-16			LQXF-C17										

Conductor Review Oct16-17, 2013


LARP Strand Specs. Procurement, Measurement - A. Ghosh

11



Present Specification

LARP-MAG-M-8004 Rev. A



Strand Diameter, mm 0.85

$J_c(12\text{ T})$ at 4.2 K, A/mm² > 2650

I_c , A > 684

$J_c(15\text{ T})$ at 4.2 K, A/mm² > 1400

I_c , A > 381

d_s , μm (nominal) < 60

108/127

Cu-fraction, % > 53

Cu/non-Cu > 1.13

RRR > 150

Piece length > 750 m

Reduced-Sn content to obtain high RRR

d_s sub-element diameter
 J_c Critical Current Density
RRR residual resistivity ratio

Strand needs for the production

Q2

Strand per coil: 30 km

of cold mass: 10 (2 pre-series and 8 series)

of coil per cold mass: 4.5

Total # of coils: 45

Total quantity of strand: 1350 km

Q1/Q3 (half unit)

Strand per coil: 18 km

of cold mass: 20 (4 pre-series and 16 series)

of coil per cold mass: 4.5

Total # of coils: 90

Total quantity of strand: 1620 km

Naming (proposal)

1/3

	Drawing	Cryo-magnet	Cold mass	Magnets
Q1		LQXFA	LMQXFA	MQXF
Q3		(LQXFB)	(LMQXFB)	
Q2a		LQXFC	LMQXFC	MQXFL + MCBXFA/B
Q2b		(LQXFD)	(LMQXFD)	
D1		LBXF	LMBXF	MBXF



I. Bejar Alonso, P. Fessia, H. Prin, S. Chemli


6th HL-PLC



G. Ambrosio and P. Ferracin


13/11/2013

33



LARP

Complete Coil schedule (1/2 production x 2 locations)






Coil Prep schedule (1/2 production x 2 locations)



	Coil Inspection & Insulation	749 days	Mon 10/2/17	Thu 9/17/20
228				
229	1	5 days	Mon 10/2/17	Fri 10/6/17 2
230	2	5 days	Wed 12/6/17	Tue 12/12/17 7
231	3	5 days	Tue 3/20/18	Mon 3/26/18 12
232	4	5 days	Tue 4/10/18	Mon 4/16/18 17
233	5	5 days	Tue 5/1/18	Mon 5/7/18 22
234	6	5 days	Tue 5/22/18	Mon 5/28/18 27
235	7	5 days	Wed 6/13/18	Tue 6/19/18 32
236	8	5 days	Fri 7/6/18	Thu 7/12/18 37
237	9	5 days	Fri 7/27/18	Thu 8/2/18 42
238	10	5 days	Fri 8/17/18	Thu 8/23/18 47
239	11	5 days	Fri 9/7/18	Thu 9/13/18 52
240	12	5 days	Fri 9/28/18	Thu 10/4/18 57
241	13	5 days	Fri 10/19/18	Thu 10/25/18 62
242	14	5 days	Fri 11/9/18	Fri 11/16/18 67
243	15	5 days	Tue 12/4/18	Mon 12/10/18 72
244	16	5 days	Wed 12/26/18	Wed 1/2/19 77
245	17	5 days	Fri 1/18/19	Thu 1/24/19 82
246	18	5 days	Fri 2/8/19	Thu 2/14/19 87
247	19	5 days	Mon 3/4/19	Fri 3/8/19 92
248	20	5 days	Mon 3/25/19	Fri 3/29/19 97
249	21	5 days	Mon 4/15/19	Fri 4/19/19 102
250	22	5 days	Mon 5/6/19	Fri 5/10/19 107
251	23	5 days	Mon 5/27/19	Mon 6/3/19 112
252	24	5 days	Tue 6/18/19	Mon 6/24/19 117
253	25	5 days	Thu 7/11/19	Wed 7/17/19 122
254	26	5 days	Thu 8/1/19	Wed 8/7/19 127
255	27	5 days	Thu 8/22/19	Wed 8/28/19 132
256	28	5 days	Thu 9/12/19	Wed 9/18/19 137
257	29	5 days	Thu 10/3/19	Wed 10/9/19 142
258	30	5 days	Thu 10/24/19	Wed 10/30/19 147
259	31	5 days	Fri 11/15/19	Thu 11/21/19 152
260	32	5 days	Fri 12/6/19	Thu 12/12/19 157
261	33	5 days	Mon 12/30/19	Mon 1/6/20 162
262	34	5 days	Wed 1/22/20	Tue 1/28/20 167
263	35	5 days	Wed 2/12/20	Tue 2/18/20 172
264	36	5 days	Thu 3/5/20	Wed 3/11/20 177
265	37	5 days	Thu 3/26/20	Wed 4/1/20 182
266	38	5 days	Thu 4/16/20	Wed 4/22/20 187
267	39	5 days	Thu 5/7/20	Wed 5/13/20 192
268	40	5 days	Thu 5/28/20	Wed 6/3/20 197
269	41	5 days	Thu 6/18/20	Wed 6/24/20 202
270	42	5 days	Thu 7/9/20	Wed 7/15/20 207
271	43	5 days	Thu 7/30/20	Wed 8/5/20 212
272	44	5 days	Thu 8/20/20	Wed 8/26/20 217
273	45	5 days	Fri 9/11/20	Thu 9/17/20 222

- Cmm inspection
- Install midplane ground insulation
- Part time use of 3rd coil winder






Yoke / Shell Subassembly (1/2 production shown x 2 parallel lines)



- Parallel effort to production
- Early start due to (slightly) longer task duration
- Assembly (2 x 2 Techs), Strain Gauge Installation (1 Tech) performed in parallel
→ All subassemblies available for production, including shipping time

Need date

[-] Shell & Yoke Assembly	633 days	Mon 4/2/18	Mon 9/28/20		
[-] Quad #1	75 days	Mon 4/2/18	Wed 7/18/18	10/3/18	
Shell & yoke Assembly	62 days	Mon 4/2/18	Wed 6/27/18		
strain gauge instl / cabling / QA	13 days	Thu 6/28/18	Wed 7/18/18	277	
[-] Quad #2	75 days	Thu 6/28/18	Fri 10/12/18	3/11/19	
Shell & yoke Assembly	62 days	Thu 6/28/18	Tue 9/25/18	277	
strain gauge instl / cabling / QA	13 days	Wed 9/26/18	Fri 10/12/18	280	
[+] Quad #3	75 days	Wed 9/26/18	Mon 1/14/19		
[+] Quad #4	75 days	Wed 12/26/18	Fri 4/12/19		
[+] Quad #5	75 days	Wed 3/27/19	Fri 7/12/19		
[+] Quad #6	75 days	Mon 6/24/19	Tue 10/8/19		
[+] Quad #7	75 days	Fri 9/20/19	Tue 1/7/20		
[+] Quad #8	75 days	Wed 12/18/19	Mon 4/6/20		
[+] Quad #9	75 days	Thu 3/19/20	Wed 7/1/20		
[+] Quad #10	75 days	Mon 6/15/20	Mon 9/28/20	1/7/21	





Quadrupole Assembly & Test (1/2 production x 2 locations)



307	Quad Assembly and Test	841 days	Tue 5/8/18	Mon 8/30/21	
308	Quad #1	318 days	Tue 5/8/18	Mon 8/12/19	
309	Assembly	159 days	Tue 5/8/18	Fri 12/21/18	
310	Coil Pack Assembly	98 days	Tue 5/8/18	Tue 9/25/18	233
311	QA	5 days	Wed 9/26/18	Tue 10/2/18	310
312	Coil Structure Assembly	49 days	Wed 10/3/18	Wed 12/12/18	311
313	QA	7 days	Thu 12/13/18	Fri 12/21/18	312
314	Cold Test	159 days	Mon 12/24/18	Mon 8/12/19	
315	He Vessel, Cryostat Assy	15 days	Mon 12/24/18	Tue 1/15/19	313
316	Leak check Testing	9 days	Thu 1/17/19	Tue 1/29/19	315
317	Setup	40 days	Wed 1/30/19	Wed 3/27/19	316
318	Test: 30 calendar days	22 days	Thu 3/28/19	Fri 4/26/19	317
319	Disconnect	15 days	Mon 4/29/19	Fri 5/17/19	318
320	Vessel, Cryostat Disassy	20 days	Mon 5/20/19	Mon 6/17/19	319
321	Ship to CERN	38 days	Tue 6/18/19	Mon 8/12/19	320
322	Quad #2	197 days	Wed 12/19/18	Mon 9/30/19	
323	Assembly	88 days	Wed 12/19/18	Thu 4/25/19	
324	Coil Pack Assembly	53 days	Wed 12/19/18	Thu 3/7/19	241,325SS-4
325	QA	5 days	Mon 3/4/19	Fri 3/8/19	326SS-5 day
326	Coil Structure Assembly	27 days	Mon 3/11/19	Tue 4/16/19	327SS-27 da
327	QA	7 days	Wed 4/17/19	Thu 4/25/19	329SS-7 day
328	Cold Test	109 days	Fri 4/26/19	Mon 9/30/19	
329	He Vessel, Cryostat Assy	10 days	Fri 4/26/19	Thu 5/9/19	330SS-10 da
330	Leak check Testing	6 days	Fri 5/10/19	Fri 5/17/19	331SS-6 day
331	Setup	20 days	Mon 5/20/19	Mon 6/17/19	319
332	Test: 20 calendar days	15 days	Tue 6/18/19	Wed 7/10/19	331
333	Disconnect	10 days	Thu 7/11/19	Wed 7/24/19	332
334	Vessel, Cryostat Disassy	10 days	Thu 7/25/19	Wed 8/7/19	333
335	Ship to CERN	38 days	Thu 8/8/19	Mon 9/30/19	334
336	Quad #3	204 days	Mon 3/11/19	Thu 12/26/19	
337	Assembly	92 days	Mon 3/11/19	Fri 7/19/19	
338	Coil Pack Assembly	53 days	Mon 3/11/19	Wed 5/22/19	325,245
339	QA	5 days	Thu 5/23/19	Wed 5/29/19	338
340	Coil Structure Assembly	27 days	Thu 5/30/19	Wed 7/10/19	339
341	QA	7 days	Thu 7/11/19	Fri 7/19/19	340
342	Cold Test	109 days	Thu 7/25/19	Thu 12/26/19	
343	He Vessel, Cryostat Assy	10 days	Thu 7/25/19	Wed 8/7/19	341,333
344	Leak check Testing	6 days	Thu 8/8/19	Thu 8/15/19	343
345	Setup	20 days	Fri 8/16/19	Thu 9/12/19	344
346	Test: 20 calendar days	15 days	Fri 9/13/19	Thu 10/3/19	345
347	Disconnect	10 days	Fri 10/4/19	Thu 10/17/19	346
348	Vessel, Cryostat Disassy	10 days	Fri 10/18/19	Thu 10/31/19	347
349	Ship to CERN	38 days	Fri 11/1/19	Thu 12/26/19	348

Coil 5 done

1st assy with 2x duration

1st test with 1.5x duration



Test time based on FNAL
(BNL test time TBD)

Coil 15 done

Coil Pack (2 techs) in parallel
w/ Structure (2 techs)

Test setup in parallel w/
He vessel , cryostat assy
(2nd set of vessels req'd)
(2 testing techs,
4 assy/disassy techs)

Coil Pack



Coil Structure

NOT Optimized yet



Complete Production Schedule (1/2 production x 2 locations)



1	† Wind/Cure/React/Impregnate	883 days	Wed 3/15/17	Thu 9/10/20	
227	† Coil Inspection & Insulation	749 days	Mon 10/2/17	Thu 9/17/20	
273	† Shell & Yoke Assembly	633 days	Mon 4/2/18	Mon 9/28/20	
304	▣ Quad Assembly and Test	841 days	Tue 5/8/18	Mon 8/30/21	
305	† Quad #1	318 days	Tue 5/8/18	Mon 8/12/19	
319	† Quad #2	197 days	Wed 12/19/18	Mon 9/30/19	
333	† Quad #3	204 days	Mon 3/11/19	Thu 12/26/19	
347	† Quad #4	207 days	Thu 5/30/19	Wed 3/25/20	
361	† Quad #5	210 days	Fri 8/23/19	Thu 6/18/20	
375	† Quad #6	213 days	Thu 11/14/19	Mon 9/14/20	
389	† Quad #7	216 days	Fri 2/7/20	Fri 12/11/20	
403	† Quad #8	219 days	Thu 4/30/20	Wed 3/10/21	
417	† Quad #9	222 days	Tue 7/21/20	Fri 6/4/21	
431	† Quad #10	225 days	Mon 10/12/20	Mon 8/30/21	



April 2022 CERN need date (30 months float)

December 2022 CERN need date (18 months float)

SQXF plan and schedule

