

# LHC Injectors Upgrade





## LHC Injectors Upgrade

# PICs in the injectors – what are we talking about?

K. Hanke

thanks to S. Gilardoni, B. Goddard, B. Mikulec  
and the LIU working group members



# Scope and Assumptions

- PIC definition
- PIC items per project
- risk *of not* doing the consolidation
- consequences *of* doing the consolidation
- cost
- time lines

assumptions for this talk:

- Linac4 and the modifications to the PSB injection region are not covered in this presentation
- ions are not considered (dedicated session)



# PICs Definition

## **CONSOLIDATION:**

Partial or complete replacement of a system to be performed in order to maintain the present level of performance/availability (from RLIUP glossary)

example: PSB multipole power converters

## **UPGRADE:**

Replacement or addition of a system to improve the performance, which would otherwise not be necessary

example: H- injection, PS injection for 2 GeV


## **PERFORMANCE IMPROVING CONSOLIDATION:**

Replacement or upgrade of a system justified by consolidation but with the goal of improving performance

example: change an ageing PSB power supply by a new one which is more reliable and which can also go up to 2 GeV



# PICs in the Upgrade Scheme





# LIU-PSB: List of PICs and Borderline Cases

PIC	comments
<b>Magnets</b>	<ul style="list-style-type: none"><li>○ a number of BI quadrupoles pure consolidation items</li><li>○ partial replacement of transfer line magnets → consolidation + upgrade</li><li>○ modifications of main magnets: upgrade</li></ul>
<b>LL RF</b>	<ul style="list-style-type: none"><li>○ new digital LL RF, new TFB</li></ul>
<b>HL RF</b>	<ul style="list-style-type: none"><li>○ replacement of present C02 and C04 by Finemet</li></ul>
<b>Power Converters (rings, extraction, transfer)</b>	<ul style="list-style-type: none"><li>○ replace MPS (borderline case)</li><li>○ replace power converters in extraction and transfer which cannot operate at 2 GeV</li></ul>
<b>Beam Instrumentation</b>	<ul style="list-style-type: none"><li>○ new wire scanners</li><li>○ new orbit</li><li>○ new BLM system (partly consolidation, but additional BLMs for upgrade)</li></ul>
<b>Main Dump</b>	<ul style="list-style-type: none"><li>○ new PSB dump (completed LS1)</li></ul>
<b>Extraction &amp; Transfer</b>	<ul style="list-style-type: none"><li>○ new extraction elements</li><li>○ new recombination and transfer line elements (borderline cases)</li></ul>
<b>Cooling &amp; Ventilation</b>	<ul style="list-style-type: none"><li>○ complete renovation of the system, cooling for new MPS, dump, etc.</li></ul>
<b>Transport &amp; Handling</b>	<ul style="list-style-type: none"><li>○ renovate handling equipment to be operational for upgrade work</li><li>○ studies and work for removal of old dump and other equipment</li></ul>

# LIU-PSB: Risks

PIC	if not done	if done
<b>Magnets</b>	<ul style="list-style-type: none"> <li>○ some magnets are urgent consolidation items, risk of failure, unsatisfactory spare situation (BT.BHZ10)</li> </ul>	<ul style="list-style-type: none"> <li>○ delicate transport &amp; handling</li> </ul>
<b>LL RF</b>	<ul style="list-style-type: none"> <li>○ old system obsolete and inappropriate for Linac4 and new HL RF</li> </ul>	<ul style="list-style-type: none"> <li>○ re-commissioning needed</li> </ul>
<b>HL RF</b>	<ul style="list-style-type: none"> <li>○ old system obsolete and will not work with Linac4 intensities and 2 GeV</li> </ul>	<ul style="list-style-type: none"> <li>○ system cannot be fully tested before decision (space)</li> <li>○ technical issues, impedance</li> </ul>
<b>Power Converters (rings, extraction, transfer)</b>	<ul style="list-style-type: none"> <li>○ ageing equipment</li> <li>○ MPS would need consolidation if it were to continue (MPS and SCV)</li> <li>○ transfer line power converters consolidation items</li> </ul>	<ul style="list-style-type: none"> <li>○ commissioning of new MPS required</li> <li>○ LS2 duration</li> </ul>
<b>Beam Instrumentation</b>	<ul style="list-style-type: none"> <li>○ insufficient machine protection</li> <li>○ insufficient emittance diagnostics</li> </ul>	<ul style="list-style-type: none"> <li>○ new systems need to be commissioned</li> </ul>
<b>Main Dump</b>	<ul style="list-style-type: none"> <li>○ old dump inappropriate</li> </ul>	<ul style="list-style-type: none"> <li>○ none identified</li> </ul>
<b>Extraction &amp; Transfer</b>	<ul style="list-style-type: none"> <li>○ reliability and spare situation issue with some equipment</li> </ul>	<ul style="list-style-type: none"> <li>○ issue with rise time of recombination kickers</li> </ul>
<b>Cooling &amp; Ventilation</b>	<ul style="list-style-type: none"> <li>○ present system obsolete (was CONS item); to be renovated taking into account new requirements; closely related to RP issues</li> </ul>	<ul style="list-style-type: none"> <li>○ potential time driver for LS2</li> </ul>
<b>Transport &amp; Handling</b>	<ul style="list-style-type: none"> <li>○ equipment not ready, delays</li> </ul>	<ul style="list-style-type: none"> <li>○ some critical issues under study</li> </ul>



# LIU-PSB: Cost

PIC	total cost [kCHF]	consolidation /performance [%]
Magnets	2696	10 90
LL RF	1566	100
HL RF	11732	100
Power Converters (rings, extraction, transfer) <sup>1</sup>	18451	35 65
Beam Instrumentation <sup>2</sup>	2954	100
Main Dump (compl. LS1)	460	74 26
Extraction & Transfer	3515	15 85
Cooling & Ventilation	6994	65 35
Transport & Handling	644 t.b.c.	60 40



**49012**

**51 / 49**

1)

- MPS consolidation foreseen before LIU: **3 MCHF**
- total cost for the 2 GeV MPS including building: **15 MCHF** → large part “performance”
- power converters transfer line: total **4 MCHF**, of which **3.3 MCHF** pure consolidation

2) budgeted in LIU, but is a MUST in all possible scenarios





# From the Feasibility Study (EDMS 1082646)

## 20.2.17 BUDGET ESTIMATE SUMMARY

	all units kCHF		
	all beams at 2 GeV (baseline)	only LHC beams at 2 GeV	from con- solidation budget
Beam Dynamics	50	50	0
Magnets	3445	3595	-210
Magnetic Measurements	111	111	0
RF	14320	14320	-14320
Beam Intercepting Devices	700	700	-700
Power Converters	20850	21100	-6630
Vacuum system	100	100	0
Beam Instrumentation	67	67	-10
Commissioning and Operation	50	50	0
Extraction, Transfer, PS Injection	5763	5763	-550
Controls	116	116	0
Electrical Systems	1700	1700	0
Cooling and Ventilation	5500	5500	-4500
Radiological Protection	0	0	0
Transport and Handling	680	680	-400
Survey	50	50	0
<b>Total</b>	<b>53502</b>	<b>53902</b>	<b>27320</b>
covered by consolidation	27320		
after correction for consolidation	<b>26182</b>	<b>26582</b>	

total

upgrade part

consolidation part



# LIU-PSB: Time Lines

PIC	total time [m]	split (y/n)	minimum single block [m]	earliest start date
Magnets	4-5	y	3	partly before LS2
LL RF	7	n	7	LS2 dig .compl. LS1
HL RF	10.5	n	10.5	LS2
Power Converters (rings, extraction, transfer)	MPS: 2×1+3 TL: 12	y n	12	LS2
Beam Instrumentation	9	y	3.5	LS1
Main Dump		n		LS1 (done)
Extraction & Transfer	7	n	7	LS2
Cooling & Ventilation	7 excluding other activities + 12	n	7 + 12	
Transport & Handling		y		after LS1





# LIU-PS: List of PICs and Borderline Cases

PIC	comments
Beam Instrumentation	<ul style="list-style-type: none"><li>○ new wire scanners</li><li>○ new BLMs</li></ul>
Magnets	<ul style="list-style-type: none"><li>○ new vertical correctors</li><li>○ new normal &amp; skew quadrupoles</li></ul>
Transverse Damper	<ul style="list-style-type: none"><li>○ new power converter</li><li>○ second kicker</li></ul>
Longitudinal Damper	<ul style="list-style-type: none"><li>○ Finemet cavity to damp longitudinal and coupled-bunch instabilities</li></ul>
Radiation Shielding	<ul style="list-style-type: none"><li>○ increase shielding on top of extr. septum and route Goward</li></ul>
Power Converters	<ul style="list-style-type: none"><li>○ low energy quadrupoles</li><li>○ orbit correctors</li><li>○ skew quadrupoles/sextupoles</li><li>○ 40/80 MHz cavity power amplifier</li></ul>
Beam dumps	<ul style="list-style-type: none"><li>○ new beam dumps</li></ul>
HL RF	<ul style="list-style-type: none"><li>○ renovation of 10 MHz system</li></ul>
LL RF	<ul style="list-style-type: none"><li>○ upgrade feedback amplifiers</li><li>○ new 1-turn delay feedbacks for 10,40 and 80 MHz systems</li><li>○ new digital beam control</li></ul>





# LIU-PS: Risks

PIC	if not done	if done
<b>Beam Instrumentation</b>	<ul style="list-style-type: none"><li>○ limited emittance diagnostics</li><li>○ old BLM system obsolete</li></ul>	<ul style="list-style-type: none"><li>○ need to recommission</li></ul>
<b>Magnets</b>	<ul style="list-style-type: none"><li>○ skew quadrupoles: low reliability due to large thermal heating. Head-tail instability today cured by linear coupling not available</li></ul>	<ul style="list-style-type: none"><li>○ need to recommission</li></ul>
<b>Transverse Damper</b>	<ul style="list-style-type: none"><li>○ limited DC power and bandwidth</li></ul>	<ul style="list-style-type: none"><li>○ need to recommission</li></ul>
<b>Longitudinal Damper</b>	<ul style="list-style-type: none"><li>○ limited bunch intensity incompatible with HL-LHC parameters</li></ul>	<ul style="list-style-type: none"><li>○ none identified</li></ul>
<b>Radiation Shielding</b>	<ul style="list-style-type: none"><li>○ RP issues</li></ul>	<ul style="list-style-type: none"><li>○ none</li></ul>
<b>Power Converters</b>	<ul style="list-style-type: none"><li>○ increased number of failures due to large RMS current and old thermal protections.</li></ul>	<ul style="list-style-type: none"><li>○ need to recommission</li></ul>
<b>Beam Dumps</b>	<ul style="list-style-type: none"><li>○ present mechanics prone to vacuum leaks.</li><li>○ precision on triggering.</li></ul>	<ul style="list-style-type: none"><li>○ need to recommission</li></ul>
<b>HL RF</b>	<ul style="list-style-type: none"><li>○ limited longitudinal beam stability, degradation of beam quality</li></ul>	<ul style="list-style-type: none"><li>○ need to recommission</li></ul>
<b>LL RF</b>	<ul style="list-style-type: none"><li>○ transient beam loading issues at high intensity</li><li>○ degraded beam quality &amp; stability, bunch-to-bunch spread</li><li>○ drift, break-down, insufficient spares</li></ul>	<ul style="list-style-type: none"><li>○ need to recommission</li></ul>



# LIU-PS: Cost

PIC	total cost [kCHF]	consolidation /performance [%]
Beam Instrumentation <sup>1</sup>	1062	34 66
Magnets	1000	48 52
Transverse Damper	350	50 50
Longitudinal Damper <sup>2</sup>	1500	100
Radiation Shielding	3150	100
Power Converters	3065	42 58
Beam Dumps	850	30 70
HL RF	4200	10 90
LL RF	900	63 37

**16077**

**42 / 58**

- 1) part of it is only required for upgrade (IPM and fast BLMs)
- 2) considered a MUST in all scenarios



# LIU-PS: Time Lines

PIC	total time [m]	split (y/n)	minimum single block [m]	earliest start date
Beam Instrumentation	5	y	1	LS2
Magnets	12	y		LS2
Transverse Damper	not critical	n		ongoing
Longitudinal Damper				done LS1
Radiation Shielding				done LS1
Power Converters	3	n	3	end 2015
Beam Dumps	1	y	0.5	LS2
HL RF	3	n		LS2
LL RF	parallel	y		LS2





# LIU-SPS: List of PICs and Borderline Cases (1)

PIC	comments
<b>Machine Interlocks (WIC)</b>	<ul style="list-style-type: none"><li>○ replace obsolete electromechanical relays with PLC solution compatible with other SPS TL and CERN systems</li><li>○ better reliability and maintenance, standard supervision and diagnostics</li></ul>
<b>800 MHz Upgrade</b>	<ul style="list-style-type: none"><li>○ replacement of analogue control with digital</li><li>○ new 1-turn feedback and feed-forward (essential for beam control) in low level</li><li>○ consolidation of existing power system and doubling available power (needed to match 200 MHz upgrade)</li></ul>
<b>LSS1 Vacuum Sectorisation</b>	<ul style="list-style-type: none"><li>○ addition of sector valves around TIDVG and MKP/D, to reduce personnel dose, protect sensitive equipment and reduce pump-down times</li></ul>
<b>Scraper Improvement</b>	<ul style="list-style-type: none"><li>○ construction of additional spares and improvements to local shielding</li></ul>
<b>Beam Instrumentation</b>	<ul style="list-style-type: none"><li>○ replacement of obsolete MOPOS electronics, plus new fibre backbone</li><li>○ replacement of obsolete BLM electronics, using MOPOS fibres</li><li>○ replacement of wire scanners with new devices</li><li>○ improvement of BGI, BSRT, IMM and Head-Tail monitors</li></ul>
<b>Transverse Damper Improvement</b>	<ul style="list-style-type: none"><li>○ improvement of low-level control</li><li>○ addition of dedicated pickups</li><li>○ consolidation of damper cables</li></ul>



## LIU-SPS: List of PICs and Borderline Cases (2)

PIC	comments
<b>Arc Vacuum Sectorisation</b>	<ul style="list-style-type: none"><li>○ reduce length of arc sectors by factor 2, to reduce pumping times</li><li>○ improved protection against loss of ecloud scrubbing</li></ul>
<b>New TIDVG Core</b>	<ul style="list-style-type: none"><li>○ replace present TIDVG core with improved version</li><li>○ robust against present and future LHC beams</li></ul>
<b>Other Kicker Impedance Reduction</b>	<ul style="list-style-type: none"><li>○ addition of transition pieces in MKD kickers</li><li>○ serigraphy of MKQ kickers</li></ul>
<b>ZS Improvements</b>	<ul style="list-style-type: none"><li>○ improvement of pumping</li><li>○ impedance reduction</li><li>○ improvement of ion trap connections</li><li>○ short-circuiting of anodes</li></ul>
<b>200 MHz RF Consolidation</b>	<ul style="list-style-type: none"><li>○ consolidation of drivers, cavity controllers, HV power supplies, CV and power couplers</li><li>○ low-level improvement</li></ul>





# LIU-SPS: Risks (1)

PIC	if not done	if done
<b>Machine Interlocks (WIC)</b>	<ul style="list-style-type: none"><li>○ possible reliability issue, extra maintenance costs, extra resources for keeping obsolete system operational</li></ul>	<ul style="list-style-type: none"><li>○ none identified</li></ul>
<b>800 MHz Upgrade</b>	<ul style="list-style-type: none"><li>○ beam instabilities at higher intensity</li><li>○ insufficient 800 MHz voltage</li><li>○ extra cost, resources and reliability risk to keep obsolete low-level running</li></ul>	<ul style="list-style-type: none"><li>○ readiness for SPS operation end 2014</li></ul>
<b>LSS1 Vacuum Sectorisation</b>	<ul style="list-style-type: none"><li>○ increased risk of venting and damage to sensitive or very radioactive equipment</li><li>○ increased radiation dose to personnel</li></ul>	<ul style="list-style-type: none"><li>○ none identified</li></ul>
<b>Scraper Improvement</b>	<ul style="list-style-type: none"><li>○ insufficient spares</li><li>○ reduced LHC performance (unable to clean transverse tails in SPS)</li></ul>	<ul style="list-style-type: none"><li>○ none identified</li></ul>
<b>Beam Instrumentation</b>	<ul style="list-style-type: none"><li>○ extra cost, resources and reliability risk to keep obsolete systems running</li><li>○ no reliable transverse beam size measurement</li><li>○ insufficient resolution and no bunch-by-bunch capability for LHC beams</li></ul>	<ul style="list-style-type: none"><li>○ none identified for MOPOS and BLM (deployment in parallel with existing system)</li><li>○ HOM heating for new WS</li></ul>
<b>Transverse Damper Improvement</b>	<ul style="list-style-type: none"><li>○ extra cost, resources and reliability risk to keep obsolete systems running</li><li>○ not able to properly damp Pb ion beams</li></ul>	<ul style="list-style-type: none"><li>○ none identified</li></ul>



## LIU-SPS: Risks (2)

PIC	if not done	if done
<b>Arc Vacuum Sectorisation</b>	<ul style="list-style-type: none"><li>○ longer scrubbing times for ecloud</li></ul>	<ul style="list-style-type: none"><li>○ none identified</li></ul>
<b>New TIDVG Core</b>	<ul style="list-style-type: none"><li>○ damage to TIDVG for repeated dumping of intense/bright LHC beams</li><li>○ long (months) recovery to condition with beam</li></ul>	<ul style="list-style-type: none"><li>○ long beam conditioning time of newly installed dump</li></ul>
<b>Other Kicker Impedance Reduction</b>	<ul style="list-style-type: none"><li>○ intensity limitation with high duty cycle beams due to other kickers</li><li>○ limitation of scrubbing beam time</li></ul>	<ul style="list-style-type: none"><li>○ none identified</li></ul>
<b>ZS Improvements</b>	<ul style="list-style-type: none"><li>○ ZS sparking</li><li>○ limitations on other beams</li><li>○ longer switch to LHC cycle</li></ul>	<ul style="list-style-type: none"><li>○ none identified</li></ul>
<b>200 MHz RF Consolidation</b>	<ul style="list-style-type: none"><li>○ extra cost, resources and reliability risk to keep obsolete systems running</li><li>○ insufficiently performing beam control</li></ul>	<ul style="list-style-type: none"><li>○ none identified</li></ul>



# LIU-SPS: Cost

PIC	total cost [kCHF]	consolidation /performance
Machine Interlocks (WIC)	600	100
800 MHz Upgrade		50 50
LSS1 Vacuum Sectorisation	800	25 75
Scraper Improvement	200	100
Beam Instrumentation	5600	25 75
Transverse Damper Improvement	1300	50 50
Arc Vacuum Sectorisation	2500	25 75
New TIDVG Core	2900	50 50
Other Kicker Impedance Reduction	4100	25 75
ZS Improvements	1000	50 50
200 MHz RF Consolidation	3700	25 75

22700

48 / 52



# LIU-SPS: Time Lines

PIC	total time [m]	split (y/n)	minimum single block [m]	earliest start date
Machine Interlocks (WIC)	6	n/a	n/a	done LS1
800 MHz Upgrade	12	n/a	n/a	done LS1
LSS1 Vacuum Sectorisation	6	n/a	n/a	done LS1
Scraper Improvement	0			
Beam Instrumentation	24	y	3	LS1
Transverse Damper Improvement	9	y	6	LS1
Arc Vacuum Sectorisation	6	y	3	2015/16
New TIDVG Core	3	n	3	LS2
Other Kicker Impedance Reduction	3	y	2	2015/16
ZS Improvements	3	y	2	2015/16
200 MHz RF Consolidation	6	y	3	2016/17





# Summary & Conclusions (1)

## time drivers and smallest increment

**LIU-PSB:** smallest increment **12 m**

→ LIU time drivers CV, RF, cabling (combined)

**LIU-PS:** smallest increment **3 m**

can be done during intermediate shutdowns

not all details known, but not considered critical

**LIU-SPS:** smallest increment **6 m**

can be done during intermediate shutdowns

all time estimates depend strongly on available resources (manpower)

## cost of PICs [kCHF]

**LIU-PSB:** 50'000 (essentially LIU-PSB budget<sup>1</sup> without the Linac4 part)

**LIU-PS:** 16'000 (80% of total budget 20'000<sup>2</sup>)

**LIU-SPS:** 23'000 (30% of total budget 77'000)

1: total budget 60.8 MCHF

2: baseline 20 MCHF, with all options 32 MCHF



## Summary & Conclusions (2)

- classification of what is a PIC is often ambiguous (many borderline cases)
- accounting of what is the “PI” and what is the “C” in a PIC is often ambiguous - however it is interesting to notice that a 50/50 split seems to be the average across all machines
- for LIU-PSB PICs cover almost the entire budget, for the PS 80% and for the SPS 30%
- several items (e.g. beam instrumentation) need to be done in all possible scenarios in order not to compromise performance over the coming years
- PICs are important and must be fully implemented in the injectors regardless of which upgrade scenario is chosen



## LHC Injectors Upgrade

**THANK YOU FOR YOUR ATTENTION!**

