



Specification of the Stray Field Issue and the MICE Hall Model

P J Smith 23rd September 2013







Introduction: The MICE Magnets and Defining the Problem.

Specification

MICE Hall Model

Vector Field Reports on the Model

Tour of the Model

Comments

Shield Wall Model

Substation Model

How much does the picture change at Step VI?

Conclusions



The MICE Magnets



The MICE superconducting magnets were designed without return yokes (circa 2000 to ~2004). About two years ago Mike Courthold and Vicky Bayliss (RAL) started to build and run some simulations of the cooling channel that indicated that there may be a problem with the stray fields produced by the MICE magnets; the predicted air fields from the MICE magnets were of sufficient magnitude to be of concern.

There was clear indication that there was the possibility of some risk to the reliable functioning of equipment primarily within and possibly beyond the MICE hall.

What are the reasons for these magnet not having return yokes?...some speculation as no-one is really holding their hand up and they were designed before I was involved.

At this stage the reason is irrelevant. It's a problem that we have and it's a problem that we urgently need to solve!





Defining the Problem



Since then a significant amount of work done has to been to try and ascertain:

- What is the extent of the problem?
- What areas of the experimental hall are particularly affected?
- What items are particularly affected?

• Are there areas of the experimental hall that are not so badly affected by stray field and is it ok to put equipment in those areas?

• Where equipment can't be moved, what is the effect of the field on that equipment and if necessary can it be mitigated?

Can the field be mitigated with a retrofitted return yoke?

•In trying to fix this problem what specification do we need to work to?



Specification



1) We need to find a solution that permits the MICE magnets to be utilised to their full operating currents, in both flip and solenoid mode for Step IV of the experiment.

2) The solution must be practical, insomuch that it must not place unreasonable constraints upon the ability to operate the experiment both in terms of physical access to the various components of the experiment and the amount of time it takes to run the experiment.

3) All equipment belonging to MICE and ISIS must function normally. Not only does this include equipment that is specific to the experiment itself but also covers the infrastructure that supports the experiment and the surrounding buildings.

4) All health and safety requirements with respect to personnel safety in magnetic fields must be adhered to.





In order to further understand the issues with the stray field of the MICE magnets it was deemed prudent to build a magnetic model of the MICE Hall to give us further insight into the likely effect of the stray field throughout and beyond the volume of the MICE Hall. This model should be capable of:

1) Producing field maps for a variety of magnet configurations that would permit a better understanding of potential issues arising within the hall from not having a return yoke on the cooling channel magnets. This in turn would guide the necessary mitigation work for the baseline design.

2) To allow members of the collaboration to have access to estimates of the likely field levels in the vicinity of their equipment.





The MICE hall represents a significant volume of approximately 40m x 12m x 12m and contains a significant amount of ferrous material. There is no symmetry to exploit. There is also much interest in how the fields penetrate beyond the confines of the MICE hall, particularly on the South Side. The total volume of the model has turned out to be approximately 120m x 80m x 80 m.

Building an FEA model on this scale requires a careful balance between detail and mesh size. This means that certain ferrous objects have not been modelled and in some cases some detail in the objects has been omitted to make the problem tractable.

The models contains:

- The bulk ferrous components contained within the MICE hall
- Many reference structures that are not magnetic.

The model does not contain:

- Some ferrous components that were going to be difficult to mesh due to their fiddly geometry (where the mass is significant an approximation has been included)
- Racks, instrumentation, other fine detailed structures.
 23rd Sept 2013





The MICE Hall model with the relative compass directions – these are used frequently to reference structures. The buildings on the south side of the Hall model have been omitted as have a few of the structures on the North side to aid viewing.









A few of the items are labelled for reference. A complete description of the components included in the model are described in the report. Most of the results presented are taken from hall models 91-96. These models represent the latest iteration of the Hall models and are available online. 10



VF Reports



We approached Vector Fields and asked them to validate the Hall model. We also asked for some advice on specific issues relating to using the hall model as a basis for sub-modelling.

These reports have now been published and are available on the modelling website at:

http://www.hep.shef.ac.uk/research/mice/opera_models/

Vector field produced two reports, the first deals with the hall model itself whilst the second deals with issues surrounding sub-modelling and how that would integrate with the hall model.

A lot of conclusions were drawn in these reports, and these have been discussed in detail in the review documentation – I don't have time to cover all of what was discussed in this presentation but I will briefly look at one or two areas they looked at from the first report.



VF Reports



Comparison of fields in free space

By comparing of a couple of line integrals and a patch on a model with all the elements set to air with Biot Savart Calculations it was determined that the error on those compared areas was less than or equal to 0.21%. This is indicative of the error introduced by the finite mesh.

Adding ferromagnetic components to the model

It is probable that the MICE Hall model already contains enough of the significant components for the fields in free space to be accurate within 1 or 2% - remembering of course that all fields may be at least 0.2 % of the all 'free space' value in error anyway. From Cobham's knowledge of the MICE Experimental Hall, there do not appear to be any major components that have been omitted that will further significantly affect results



VF Reports



Investigation of material property variations

In this item the magnetisation values of BH curves of the steel was reduced by 10% and the effect on the three patches within the hall volume was calculated. The observed changes were usually well below 5%. The reduction in the magnetisation of the shielding walls means that they are not performing quite as well but as they are generally far from saturation in model 91 the effect is quite small.

Investigation of mesh quality

The hall model has been run using quadratic elements throughout as this is the safest and most accurate method of calculating the fields....To investigate whether the use of quadratic elements was necessary two models were run, one with mixed elements and one with all linear elements. The integrated fields on the patches were compared with the results from the quadratic model.

The results showed that on the patches examined the benefit of using quadratic elements was marginal yet the solve time improvement was significant.

Field Throughout the Hall Volume

The University Of Sheffield.



Model 91 – Step IV Solenoid 240 MeV/c – y=0 (beam height) - 5 gauss scale. This gives some indication of where the 5 gauss boundary lies in this model.



Model 91 – Step IV **Flip** mode 240 MeV/c – y=0 (beam height) - 5 gauss scale. This gives some indication of where the 5 gauss boundary lies in this model.

By flipping between this and the previous slide it is clear that solenoid mode produces more fringe field. 23rd Sept 2013



Model 91 – Step IV Solenoid 240 MeV/c – y=0 (beam height) - 5 gauss scale. One can immediately see that the field through this volume doesn't look to worrying but we'll take a closer look at some specific volumes shortly.







Model 91 – Step IV Solenoid 240 MeV/c – 5 gauss scale North Wall (external)





mm

A/m

A/mm²

267x1079

-7953.0

Cartesian

20960.0

y=-5375.0 to z=-33005.0 to

Α

w

Ν

(nodal/inte)

x=6094.0



Model 91 – Step IV Solenoid 240 MeV/c – 5 gauss scale South Wall (external)







Model 91 – Step IV Solenoid 240 MeV/c – MAX SCALE 0.4 gauss West Wall (external)







Model 91 – Step IV Solenoid 240 MeV/c –5 Gauss Scale Roof (external)







Model 91 – Step IV Solenoid 240 MeV/c –10 Gauss Scale Roof (external)







Model 91 – Step IV Solenoid 240 MeV/c –5 Gauss Scale ISIS control Rooms North Side (MICE South Wall Side)

59x301

5050.0

Cartesian

19350.0

y=2080.0 to z=4280.0 to





mm

A/m

A/mm²

А

W

Ν



Model 91 – Step IV Solenoid 240 MeV/c –5 Gauss Scale **ISIS control Rooms East**

23rd Sept 2013

161x59

2080.0

y=5050.0 to

Cartesian

z=4280.0







Model 91 – Step IV Solenoid 240 MeV/c –5 Gauss Scale ISIS control Rooms Floor







Model 91 – Step IV Solenoid 240 MeV/c –10 Gauss Scale **ISIS control Rooms Ceiling**

23rd Sept 2013

19350.0







Model 91 – Step IV Solenoid 240 MeV/c –5 Gauss Scale MLCR North Wall





mm

A/m

A/mm²

60x69

360.0

Cartesian

9125.0

y=-2630.0 to z=5670.0 to

А

w

Ν



Model 91 – Step IV Solenoid 240 MeV/c –1 Gauss Scale **MLCR South Wall**







Model 91 – Step IV Solenoid 240 MeV/c –5 Gauss Scale MLCR East Wall







Model 91 – Step IV Solenoid 240 MeV/c –5 Gauss Scale MLCR West Wall



Comments



So we have a lot of plots like this. Additionally work has been done to go through a list of components that may be affected by the stray field, and with some exceptions and a few caveats, most of this doesn't look too troubling for step IV. You will hear more about in the presentation from Craig MacWaters.

ISIS have provided us with a list of their equipment that may be at risk. We are in a position to give an indication of predicted air fields in these regions. However the presence and effect of small quantities of ferromagnetic materials in these areas that are not included in the model may alter the field at a localised level—this represents an uncertainty.

If the baseline solution was to be adopted we would need to ascertain what these plots implied for the ISIS control room and equipment.



Comments



So why not recommend the baseline solution? Well I think the answer is RISK. A lot of effort has been put into the model to ensure that technically it is as accurate as it possibly can be. However:

- 1. The model has not been benchmarked. By benchmarked this is defined as running the hall model on a second code or having experimental measurements to back up and verify the output. We are confident that the model is representative but it is hard to prove. The shielding or moving of a significant number of items in the baseline solution is dependent upon the accuracy of the model and so any error in the model output could be compounded. This represents the largest risk.
- 2. The hall model still represents an approximation. Approximations have been made with objects and difficult to mesh (steel) objects are not included. Whilst we understand that this is unlikely to have a large impact upon the model output it still represents an uncertainty.
- 3. The hall model makes assumptions about the magnetic properties of the steel within the hall. Some simple tests have demonstrated that the hall model output does not appear to be hugely dependent upon the assumed BH curves, but that testing was not comprehensive. 31

Shield Wall Model





ICE



The North and South Shield Walls are modelled as a dual skinned homogenous sheets of tenten steel. In reality they are built of a plate structure bolted to a steel framework with significant gaps between the plates. These gaps are of concern as they may reduce the effectiveness of the shield wall.

To try and understand the effect of these gaps a model was built that modelled a more realistic section of a shield wall. I'm not going to include a lot of details here about the model because of time but this material is available on the magnetics website.



Shield Wall Model



The 'realistic' models are large, complex, they are not 100% representative but are a much better approximation to a real shield wall. This is to some extent still work in progress, I now have some models for the North Shield Wall but these are more difficult to compare with model 91 due to the proximity of the magnetic Linac Shield Wall to the NSW.

The shield wall model is ~50% smaller than the real wall (But it can't be made any bigger due to computer memory constraints)

The plot on the next page shows the predicted field 250mm behind the shield wall in one of these models compared with the predicted field 250mm behind the South Shield Wall in model 91. The gaps between the plates in both the horizontal and vertical direction is 7mm.

It is clear that there is not a 'good' magnetic connection between the plates and the Ibeams in the MICE hall; this has been modelled by a plate to I-beam gap. Models have been run with a 0 mm gap (a good connection) and a 1 mm gap (a bad connection).

The amount of field leakage is sensitive to the presumed gap between the I-beams and the steel plates. I think it would take a measurement to resolve this; something that I don't believe we can do easily.

Comparison Plots of Field Behind Modelled Shield Wall at x=3861 mm (3977 mm) y=0mm



Green line – predicted field 250 mm behind South Shield Wall in model 91 Blue line – predicted field behind the shield wall model with a 1 mm plate gap between plates and I beams (which is a presumed worse case)

Note: Due to an small error in the reference location in these models there is a small discrepancy in the distance of the shield wall from the beam-line centre between these models (3861 mm in shield wall model vs 3977 mm in model 91). This represents a difference of ~3% in radial difference from the beamline centre.



Sub Station Model



The MICE hall contains a large sub-station that provides power to much of the MICE experiment. This is a new substation and contains a significant amount of electronics 'embedded' into the front panels of the equipment.

The sub-station is constructed from about 5300 kg of iron, it is partially shielded by the north shield wall but much of the substation has no shielding from the MICE stray fields whatsoever.



There are two concerns:

What stray field does the substation see?

Does the presence of the iron increase the field that the instrumentation embedded in the panels experiences?



Sub Station Model



We added a shell of the substation (5300kg steel) to model 91 to ascertain whether this would have an effect on the field in the location of the substation. Very minor changes to the field distribution are predicted. The magnitude of the field in the region of the sub-station doesn't look worrying. This exercise needs repeating for step VI.

I also ran some sub-models to ascertain the likely effect of placing apertures in the skin of the substation to see what the field would be at the location of the surface mounted instrumentation. The results were encouraging, the instrumentation shouldn't see much more than background field, although there is a slight dependency upon the field direction.



Integral = 1.894551E+07

opera





The transformer section is slightly smaller in the model than in reality (aids meshing)

In the sub-model the skin is 2mm thick giving total mass of ~1000kg















External field of 5 gauss applied to the sub-model

Field perpendicular to sub-station (South to North)







500 gauss

25 gauss

17/Aug/2013 12:36:03

10 gauss



How much does the picture change at Step VI?



The primary focus has been on Step IV, as this represents an important milestone for the MICE experiment. However, these models have also been run for Step VI, so how do they compare?

There has been much less analysis done at Step VI on the hall model but it is clear that the situation gets worse as the cooling channel is extended.

Generally the stray field is pushed West, and the East Stray field doesn't change too much. This result isn't too surprising as the cooling channel is extended in the westward direction.

The 5 gauss line is generally contained within the MICE hall but there are a couple of hotspots. The field external to the MICE hall does increase but other plots - not shown here - indicate that the increase is perhaps not as much as was initially anticipated. The field in the MLCR and the ISIS control room increases.

The sub station is clearly going to vulnerable in Step VI, although of course situation is likely to be different with a return yoke!







Integral = 3.110028E+07

opera



Conclusions



- We have successfully developed a tool that allows us to predict the stray field produced from the MICE magnets in the MICE hall and the surrounding buildings. The results from these models, in addition to an extensive image library, have been made publicly available.
- A lot of work has been put into developing the model to ensure within the limitation of producing a tractable model that it accurately represents the stray field within the MICE hall.
- The model has been instrumental in isolating likely problem areas and making initial predictions of the stray field in many areas both within and surrounding the MICE Hall.
- The complexity of the model has prevented us from benchmarking the model. As the model is instrumental in predicting the field in the region of a significant number of critical items this uncertainty represents a risk.
- Although not shown in this presentation an early yoke design for Step IV has been implemented in the model. The results have not yet been correlated with Holger's work but it is hoped that with further work this could be used to continue to support the field prediction effort.