





# Overview of strategy:

## Mitigation of stray magnetic field

### History

# V. Bayliss; CM33, Jun12:



# Strategy adopted:

- Requirement:
  - **Develop mitigation strategy that:**
    - Reduces stray field to acceptable level for all sensitive equipment;
    - Reduces remaining risk that stray field will impair operation of equipment;
    - Preserves as far as possible the Step IV schedule
      - Data taking after ISIS long shutdown; Mar15
- Parallel approach adopted:
  - **Baseline:**
    - Remove items (e.g. compressors and racks) from regions of high magnetic field where possible;
    - Develop local shielding options for items (e.g. tracker cryostats) that can not be moved to remote locations;
  - **Mitigation of risk that shielding of one or more items to acceptable level is not possible:**
    - Develop partial return yoke

## Parallelism a strength:

UK personnel developed baseline;

US personnel developed partial return yoke


- At CM33 it was not clear that a partial return yoke could be developed that satisfied:
  - The mitigation requirements;
  - The constraints of the MICE Hall;
  - Preserved the schedule at least to Step IV
- The study of the baseline and partial return yoke is now sufficiently mature to allow the original strategy to be reviewed


## Mitigation of stray magnetic field

**Steps taken:**



# Compressor relocation:

- Compressors located to meet  $\leq 30\text{m}$  high-pressure hose lengths
- Build necessary structure to support compressors & services
- Additional requirements
  - Personnel access
  - Compressor access (for installation & swap)
  - Equipment delivery & assembly space (especially MICE devices)






- Document in preparation for transmission to Technical Board
- Strong pressure now to move from design to execution



# Equipment delivery and assembly area:










**Mitigation of stray magnetic field**

**Partial return yoke**

# PRY concept and performance:



## Partial return yoke:

- Contains field in the vicinity of the MICE magnetic channel:
  - 5 G line contained within the MICE Hall
    - No issues in South Side Buildings
- Require to perform full simulation of yoke in the MICE Hall Model
  - Expect acceptable fields at (e.g.):
    - RF amplifiers;
    - Tracker electronics
  - Require to check (e.g.):
    - Field on roof and at LH2 gas panel

**Mitigation of stray magnetic field**

**Conclusions and recommendations**

# Magnetic Shielding Group conclusions:

- **Baseline:**
  - Results indicate that can shield at Step IV
    - **Technical risk:**
      - One or more critical items will not be shielded such that performs to specification
  - PRY required for Step V/VI because coupling coil likely to yield unacceptably large fields at the position of the:
    - RF amplifiers (electron tubes);
    - Electricity substation;
    - South Side Buildings (including the ISIS control rooms)
- **PRY:**
  - Results indicate that integration in the Hall at Step IV can be accommodated with modest modifications to existing infrastructure;
    - Significant modifications are required for Steps V/VI
      - Mitigation:
        - » Time to plan and execute alongside substantial engineering projects
  - Initial analysis of schedule indicates delay to implementation of Step IV is modest
  - While PRY will extend time required to exchange absorbers;
    - Initial analysis indicates that the exchange is manageable

# Mag. Mitigation Group's recommendations:

- Initial analysis of implementation schedule:

	Finish Date	Delayed finish due to Risk
StepIV base line	2/1/15	29/9/15
SS before PRY	30/1/15	27/10/15

- Assuming either:
  - Full resource leveling does not change projected end dates substantially and/or
  - Additional resources can be raised to allow the projected end-date to be preserved
- Mitigation Group's recommendations:
  - Install the partial return yoke at Step IV
  - Seek implementation such that a "Step IV fit-up" and a "field-off shakedown" run can be performed before the long shutdown