

LHC Injectors Upgrade





LHC Injectors Upgrade



SPS Orbit Upgrade

J.L. GONZALEZ



Outline

- SPS Multi Orbit POSition System (MOPOS)
 - SPS Beams & Beam Position Monitors (BPM)
 - Specifications for Trajectory and Closed Orbit Measurements
- System Architecture
- First Measurements with Beam
- Development Status
- Budget
- Summary and Conclusions



Specifications: SPS Beams

Beam Type	Bunch spacing [ns]	Bunch number	Bunch charge [10^{10}]	Bunch length [4σ , ns]
FT / CNGS	5	400-4000	0.1-2	1-4
LHC25NS	24.96	$N_{bat} \times 72$	1-50	1-4
LHC50NS	49.92	$N_{bat} \times 36$	1-50	1-4
LHC75NS	74.88	$N_{bat} \times 24$	1-50	1-4
LHC single bunch	524.4-2022.6	1-16	0.2-50	1-4
LHC ion / Pb82+	100	$N_{bat} \times 4$	0.01-2	1-4

N_{bat} : number of batches (1..4 for proton beams and up to 13 for ion beams)

Bandwidth: 40 MHz & 200 MHz

Charge Dynamic Range: >70 dB



SPS Beam Position Monitors

Monitor Type	Physical Beam Aperture (mm)	Quantity	Mechanical Section	Comments
BPH	44V x 154H	103	rectangular	Electrostatic shoe-box
BPV	83 x 83	94	square	Electrostatic shoe-box
BPA	269	4	circular	Resonant cavity [LSS2]
BPD	269	2	circular	BPA emulation [LSS1]
BPCN	76	7	circular	Stripline directional couplers [2 plane BPMs]
BPCE	206	6	circular	

Total = 216 BPMs: 6 x 36 slots

BPA/BPD: will be replaced with BPCE (mainly used for extraction)

- Current MOPOS channels (shoe-box single-plane BPMs): 240 [6 x 40 slots]
- **No request yet for 2-plane BPMs [≥ 432 channels]**



Specifications: Acquisition Modes

- **Trajectory acquisitions (multiple gated batches)**
 - Automatic: **50 first turns** (every batch, with one measurement per batch)
 - On request: **10k turns** (for a selected batch)
- **Closed Orbit acquisitions (single gated batch)**
 - Averaged over 40 turns [$40 \times 23 \mu\text{s} = 920 \mu\text{s}$]: **up to 100 s** acquisitions @ 1 kHz \rightarrow **100k** data points per channel
 - Required: all the data or a subset (every 10 ms for example)
- **Intensity information**
 - Used to detect beam presence

Specifications: Resolution & Accuracy

- Resolution over ± 15 mm BPM-Aperture

	Large intensity beams ($\geq 2 \cdot 10^{10}$ p/bunch)	Low intensity beams (ex. LHC pilot: $2 \cdot 10^9$ p/bunch)
ORBIT (AVG 42 turns ~ 1 ms)	100 μm	400 μm
TRAJECTORY (turn-by-turn)	400 μm	1000 μm

- Required Accuracy: < 0.5 mm RMS
Including mechanical alignment, electrical offsets...
Difficult to guarantee with such old BPMs




System Architecture

- **MOPOS Front-End**
 - 216 modules in the tunnel
 - Exposed **up to 100 Gy/y**
 - Optical transmission

- **MOPOS Read-Out**

- In BA1 ... BA6
- 6 VME-Crates
- 9 VFC*/Crate

* VME FMC Carrier



U Front-End: Measurement Principle

- Logarithmic derivation of normalized position

$$x = \frac{A - B}{A + B} \quad \Leftrightarrow \quad \frac{A}{B} = \frac{1 + x}{1 - x}$$


$$\ln \frac{1 + x}{1 - x} = 2 \left(x + \frac{x^3}{3} + \frac{x^5}{5} + \dots \right)$$

$$\log_a X = \frac{\ln X}{\ln a} \quad \Rightarrow \quad \log \left(\frac{A}{B} \right) \cong \frac{2x}{\ln 10}$$

$$x = K (\log A - \log B)$$
$$K = \frac{\ln 10}{2}$$




Front-End: Measurement Principle






Front-End: Block Diagram





MOPOS: Simplified Block Diagram





Read-Out Board


- VME FMC Carrier (VFC)

General Purpose BI Board

2 FPGAs : Xilinx Spartan-6 150T

- FMC Board

2 SFP Cages for Commercial Optical Transceivers




BST
160Mb/s

MOPOS FMC Board




Front-End Prototype

- SPS Tests with beam: Jan./Feb. 2013





First Beam Measurements: Single Bunch Proton Injection (LHCFAST2)





First Beam Measurements: Ion Injection, 2 bunches/batch @ 200ns


H BPM

Pb⁸²⁺


10¹⁰ charges/bunch

Low Signal

→ 40MH_HS



Batches 1 to 10



Injection of Batch 11



Sensitivity & Resolution

		Sensitivity [$\mu\text{m}/\text{ADC-bin}$]							Noise (Worst Case)	
Bump [mm]		- 5	- 2.5	- 1	+ 1	+ 2.5	+ 5	AVG	Trajectory (turn-by-turn)	Orbit (1 ms)
Single Bunch	40MH_HS H	1.8	1.7	1.8	2.0	1.7	1.8	1.8	150 ADC-bin 375 μm Required Resolution: 400 μm	34 ADC-bin 80 μm Required Resolution: 100 μm
	40MH_HS V	2.3	2.5	2.6	2.6	2.4	2.4	2.5		
Multi-Bunch	40MH_LS H	1.9	1.9	1.5	1.7	2.1	1.8	1.8		
	40MH_LS V	2.3	2.4	2.6	2.6	2.2	2.3	2.4		
	200MH H	1.8	1.7	1.4	1.6	1.9	1.7	1.7		
	200MH V	2.2	2.3	2.6	2.4	2.1	2.1	2.2		

H-Measurements: Stripline BPM

V-Measurements: Shoe-Box BPM



Development Status

- **Front-End**
 - Final version of analogue board: under test
 - Digital board: still under development
 - **Radiation Resistant Components to be selected and tested (ADC, FPGA)**
- **Read-Out Board**
 - Currently using VFC_V2
 - VFC_HPC is under development
- **Production for the Test of a Sextant**
 - Front-End Chassis: about 40 modules
 - VFC_V2: about 20 modules



Installation Status

- **Mini-Racks in the Tunnel**
 - 6U-Model: about 200 units installed
 - 16U-Model: 12 units installed
- **Radiation Resistant Optical Fibres**
 - Total Quantity: ordered
 - Patch Cords: partially ordered
- **Cable Installation**
 - Completion during LS1
- **Fibre Installation**
 - BA6, TS6+ & TS6-: completed
 - BA1 & TS1+: completed
 - BA4, BA5, TS5+ & TS5-: installation on-going
 - **BA2, BA3, TS1-, TS2+/-, TS3+/-, TS4+/-: after LS1**




Installation and Commissioning Plan

- Installation in parallel with current MOPOS system in Sextant 6 foreseen in 2014 to allow:
 - Radiation resistance testing of the Front-End
 - Software development
- Fibre installation will be completed **during long technical stops or in LS2**
- Full system installation: as soon as the final version of the Front-End and the VFC are produced and **fibres installed**.



Project Schedule



* Depending on the progress of the fibre installation, the front-end chassis can be placed in surface buildings



Budget Status

Code 64724	2010... 2012	2013
Development & Mini-Racks	300 k	
Rad-Hard Fibre		650 k
Fibre Installation		630 k
Cable Installation		60 k



Budgetary Requirements: 2014...

Description	Code 64724
Front-End Chassis Production (300)	450 k
VFC-HPC Development & Production (75)	200 k
Rad-Hard Components (500)	200 k
Commercial SFPs (300)	60 k
FSU (2014...2016)	240 k
Other (cables, fibre patches...)	100 k
Total:	1250 k

- Electronics cost in line with 1.5M estimate
- Fibre installation, still requires additional **1500 k**



Cost Breakdown

Code 64724	MOPOS Electronics	MOPOS Optical Fibres	
2014	350	550	350
2015	300	200	
2016	300	200	
2017	300	200	
2018		400	600
2019		-	600
	1250	1550	1550




Summary and Conclusions

- The **MOPOS upgrade** is required to **replace** the obsolete electronics and **improve** the **measurements**
- The **first prototype tested** in the CERN-SPS with proton and lead-ion beams has shown that it is able to:
 - **resolve** a **multi-batch** structure
 - **reconstruct** the **injection oscillations**
- The system **resolution** was estimated to:
 - 375 μm in trajectory mode
 - 80 μm in orbit mode
- These values **agree** with the **specifications**



Summary and Conclusions

- The system is now being optimized to **improve the sensitivity** for **low charge** beams
- **Several** commercial components have been already **tested under radiation**. Further tests are planned in 2014 to validate the ADC and the FPGA for the Front-End Digital Board
- The **current MOPOS** electronics and the **upgrade system** will run **in parallel** for one SPS sextant in **2014**



LHC Injectors Upgrade

THANK YOU FOR YOUR ATTENTION!






Spare Slides




Front-End: Analogue Board






Front-End: Log Conformance Error






Front-End: Digital Board





First Beam Measurements: Proton Injection

4 batches – 36 bunches @ 50ns



H BPM
1.35 10^{11} p/bunch
High Signal
→ 40MH LS
→ 200MH

Injection of Batch 4




First Beam Measurements: Local Bumps

Displayed Function: MDV42107/IREF, MDV42307/IREF, MDVA41932/IREF


Measurement of beam position

- For each BPM
 - ✓ Horizontal
 - ✓ Vertical
- 6 local bumps:
 - ✓ ± 1.0 mm
 - ✓ ± 2.5 mm
 - ✓ ± 5.0 mm
- For each bump
 - Before
 - Bump Centre
 - After





Local Bump Measurements





MOPOS Acquisition: Test-Modes

Mode	Type	# SPS turns	# ADC Slots	Mean Values	Timing
FIFO	Debug	Up to 3 ($\sim 70 \mu\text{s}$)	All frames	-	Async
Capture	Operational / Debug	220 ($\sim 5 \text{ ms}$) 64000 ($\sim 1.5 \text{ s}$)	All slots 8	-	Sync
Injection Trajectory	Operational	Up to 54 ($\sim 1.2 \text{ ms}$)	Up to 235	13 batches (width selectable)	Sync
Orbit Diagnostic	Debug	Up to 255 ($\sim 5.8 \text{ ms}$)	All slots *	One for each slot	Sync
Global Orbit	Operational	Up to 255 ($\sim 5.8 \text{ ms}$) Default 40 ($\sim 1 \text{ ms}$)	Up to 235	One for each turn (selected slots)	Sync
Continuous Filter	Operational	Permanence	All slots *	One value for each BPM plane	Async

* This parameter is fixed and cannot be changed via software