

# LHC Injectors Upgrade





## LHC Injectors Upgrade

**Linac4 up to PSB injection systems**

Jocelyn TAN, BE-BI

On behalf of my BI colleagues



# Outline

- Linac2 to PSB transfer lines
  - Fast BCTs
  - BPMs
- **H<sup>-</sup> INJECTION SYSTEM IN THE PSB**
  - BLMs
  - H<sup>0</sup>/H<sup>-</sup> measurement at injection dump
  - BTV screens at stripping foil
  - SEM-Turn by turn profiles for injection matching
- New requests
- Conclusion




# Fast BCTs - Consolidation

- **Acquisition chain**
  - Upgraded to TRIC
  - Acquisition moved to BOR: All monitors downstream LT.BHZ20:
  - Planning: completed for LS1
- **FBCT Proposed consolidation**
  - Motivation: LT, LTB, LBE and LBS monitors are 35-40 years old
  - Budget: 280 kCHF for 7 BCTs
  - Planning: completed for Linac4 connection
  - WP responsible: BI-PI

# Fast BCTs

- BI.BCT10: Dose rate  $10\mu\text{S/h}$
- BI.BCT20: Dose rate  **$200\mu\text{S/h}$**
- Present number of windings  $N=10$
- For ultra short Linac4 pulses  $\Rightarrow N=20$
- No spares
- **Plan A:**
  - **LS1:** Dismantle the BCTs for new windings
  - One hour per monitor
  - **Collective dose:  $\sim 1000\mu\text{S}$**
- **Plan B:**
  - New WP request
  - WP responsible: BI-PI
  - 2015 Build four new monitors (mechanics)
  - 2016 Ready for Linac4 connection to PSB
  - **Collective dose:  $\sim 200\mu\text{S}$**
  - **Estimated cost 160 kCHF, on LIU budget**



BI.BCT20: Four rings  
Dose rate  **$200\mu\text{S/h}$**

Courtesy: F. Lenardon



# New BPMs in the Linac to Booster Transfer lines: 20 BPMs



- Motivation
  - Upgrade the LT, LTB and BI trajectory system with the Linac4 standards
- Specifications
  - Measure beam position with resolution /accuracy of 0.1/0.3 mm
  - Relative beam intensity between two BPMs (1% wrt peak current)
  - Beam phase wrt to RF reference ( $0.5^\circ$ )
  - Energy via TOF between two BPMs (1 ‰)



# Status of Development

- **Commissioning**
  - Sept.2012 - end of run
  - 1BPM tested with Linac2 beams
- **MSWG** endorsed the new system on 15/03/2013
- **Cabling campaign:** completed
- **Planning LS1**
  - Analogue board: teething issues pending
  - Monitor production: on schedule
  - Nov. 2013-Jan.2014: Machine installation
- **Concerns**
  - Helicoflex seal – not specific to this device
  - All devices must pass new outgasing test
  - **TE-VSC has limited manpower**
- **This system has top priority for post-LS1 start-up**






# Outline

- Linac2 to PSB transfer lines
  - Fast BCTs
  - BPMs
- **H<sup>-</sup> INJECTION SYSTEM IN THE PSB**
  - BLMs
  - H<sup>0</sup>/H<sup>-</sup> measurement at injection dump
  - BTV screens at stripping foil
  - SEM-Turn by turn profiles for injection matching
- New requests
- Conclusion





# Beam Loss Monitoring in the H<sup>-</sup> system



## ● Specifications

- Monitor foil degradation
- Machine protection : H0/H- dumps designed for 1bad pulse only:  $2.5 \times 10^{13}$  charges, 500 J
- Beam Interlock System : Integration and High reliability
- Resolution time :  $2 \mu\text{s}$
- Low loss threshold : PPM with FESA
- High loss threshold : non-PPM, fully HW-based
- PPM: enable/disable


## ● Proposed technology: Little Ionization Chambers (LIC)

- Electronics: Ready
- BLM support design and integration: Following the new vacuum sectorization, the final design from TE-ABT is needed

## ● Budget: 100 kCHF



# Beam Loss Observation in the H<sup>-</sup> system



## ● Specifications


- Monitor fast losses and foil degradation
- Optimize stripping efficiency over the injection duration (100 $\mu$ s)
- Resolution time : 100 ns
- Min/Max loss:  $2 \times 10^{10}$  /  $2.5 \times 10^{13}$
- PPM acquisition
- Read out under discussion: OASIS, or CIVIDEC, or VFC (BI standard carrier)

● Proposed technology: Diamond detector

● Budget : 150 kCHF




# H<sup>0</sup>/H<sup>-</sup> current monitor



H<sup>0</sup>/H<sup>-</sup> current monitor needed in front of the dump in the BSW4 magnet

- to monitor the efficiency of the stripping foil (detect degradation and failure)
- to allow efficient setting up of the injection
- to protect the dump by providing an interlock signal in case of 10% detected beam load



CONCEPT: plates intercepting the H<sup>0</sup> and H<sup>-</sup> ions and acting as a Faraday cup for the stripped electrons (stripping & collection)

# Specifications

---

LINAC4 Project Document No.

**L4-T-EP-0003 rev 1.0**

---

CERN Div./Group or Supplier/Contractor Document No.

**TE/ABT**

---

EDMS Document No.

**1069244**

---

- Robust and simple (lifetime  $\approx$  20 years, no maintenance)
- Radiation dose of 0.1-1.0 MGy per year
- Vacuum level  $10^{-9}$  mbar without beam ( $10^{-8}$  mbar with beam)
- Withstand the BSW4 pulsed magnetic field of 0.4T and at the same time do not perturb the field by more than  $\approx$  0.1 %
- Placed as close to the dump as possible (to minimize uncontrolled losses)
- Sensitive areas maximized to cover as much as beam halo as possible
- Withstand the heat load in normal operation condition and a full Linac4 pulse load ( $2.5 \times 10^{13}$  H- ions), in case of failure of the stripping foil, on a one-off basis, several times per year
- Dynamic range:  $5 \times 10^7$  –  $5 \times 10^{12}$  ions (for H- and H0 alike)
- Absolute accuracy  $\pm$  20 %, relative accuracy  $\pm$  10 %
- Time resolution: integral over the full injection time (however better time resolution would be potential advantage for operational diagnostics)



# Proposed Technology

Titanium plates 1 mm thick:

- best compromise between the “high” conductivity needed for the current read-out and the “low” conductivity required by the presence of the magnetic field
- 1mm thickness suited to stop all the stripped electrons and tolerated in the presence of the vertical B-field (to avoid current loop in the horizontal plane)
- Acceptable thermal load (150 mW with 2% beam load)
- Low activation (low-Z material)

*Comparison study with other materials:*

Material	Conductivity (1/Ωm) (for signal read-out)	Thermal load (ΔT) for a full Linac4 pulse	Melting point	Neutron yield (w.r.t. n° of protons)	Signal Q (e/H <sup>-</sup> ) with NO external fields*	Signal Q (e/H <sup>0</sup> ) with NO external fields*	Compatibility with BS4 field
Graphite	6.1 × 10 <sup>4</sup>	67 K	3773 K	0.41 %	- 1.83	- 0.90	YES
Aluminum	3.77 × 10 <sup>7</sup>	50 K	933 K	0.57 %	- 1.63	- 0.80	NO
Titanium	2.34 × 10 <sup>6</sup>	80 K	1933 K	0.99 %	- 1.42	- 0.70	YES
Copper	5.96 × 10 <sup>7</sup>	98 K	1356 K	1.0 %	- 1.22	- 0.60	NO
Tungsten	1.89 × 10 <sup>7</sup>	229 K	3683 K	6.4 %	- 0.68	- 0.33	NO

- Fully acceptable
- Acceptable (not ideal)
- Not acceptable

\* taking into account losses due to electron backscattering and secondary emission





# Development and commissioning

- Still on-going developments
  - Mechanical integration in the BSW4 magnet (plates support and cabling)
  - Not much flexibility for integration
  - Read-out electronics
  - Interlock circuitry: based on SEM interlock system
  - Feasibility study to add beam horizontal position information (NOT included in the specifications but potential advantage for operation diagnostics)
- Budget: 57 kCHF
- 2014 : Finalize the integration design by Q2
- 2015 : Finalize electronics and interlock by Q4



# BTV screen at injection foil

- Foil inspection
- Measure injected beam position and size to steer the beam onto the foil after 1 turn
- Position / size accuracy : 0.2mm / 10%





# Development and commissioning

- **Collaboration** TE-ABT between and BE-BI
  - Mechanism integration
  - Interlock logic between screen and foil: to be defined
- Vidicon tube based camera
- **Prototype**: 80% to completion
- **Budget**: 120 kCHF
- **2014**: Vacuum test of the prototype / validation
- **2015**: Production of 4 BTVs + 2 spares





# Planning for BTVs and H0/H- meas, and BLMs (LICs + Diamond)

- **End 2015:** Half-injection sector test
  - These instruments should be ready
  - Need clarification / installation planning
  - Need temporary installation (cables + controls)
- **End 2016:** Linac4 connection
  - Ready **if their cable campain is granted**




# SEM grids for matching and emittance measurements at injection

- Specifications: based on 3 slides from C. Carli (26<sup>th</sup> October 2011)
  - injection of half a PSB turn (i.e.  $0.5 \mu\text{s}$ ,  $2 \times 10^{11}$  protons) to well separate turn-by-turn profiles
  - acquisition of – **say up to 20** – consecutive profiles
  - to avoid burning the wires : Implement an **interlock on the pre-chopper** to shorten the Linac4 pulse.
  - a pair of monitors (H+V) in one ring is sufficient
  - **PPM In/Out (like the sieve) : NOT OK**
  - *Permanent implementation for MDs and operation: **VERY DEMANDING***

- Mechanical specifications: compact monitor

- grid size : 20mm
- 48 graphite wires ( $\varnothing = 33 \mu\text{m}$ )
- Thick frame for stopping scattered protons



$\epsilon_{\text{rms}}$  of incoming beam  $0.5 \mu\text{m}$   
beam size w/  $\beta$  mismatch x2 1.1 -2.2 mm rms  
PSB straight sections  $\beta_{\text{T}} = 5 \text{ m}$

# Status

## ● Status

- new monitor to be built,
- WP responsible: section BI-PM
- Few free straight sections: possible in 4L1
- Simulations: **5mV Max. over 50  $\Omega$  on a wire**
- Study possibility to transport this weak signal through special coaxial lines (25m long) to the amplifiers.

## ● Budget : 135 KCHF

## ● Planning

- 2015 Start electronics development
- **A few cables to be pulled**
- **End 2016: Ready for Linac4 connection if signal/noise ratio is good enough**




# Outline

- Linac2 to PSB transfer lines
  - Fast BCTs
  - BPMs
- H<sup>-</sup> INJECTION SYSTEM IN THE PSB
  - BLMs
  - H<sup>0</sup>/H<sup>-</sup> measurement at injection dump
  - BTV screens at stripping foil
  - SEM-Turn by turn profiles for injection matching
- New requests
- Conclusion



# BI.SMV position plates



- Recent request, **no specification, no WP**
- Based on existing system: ensure the sliced beams are centered in their respective apertures.
- Metal plates, thickness to be defined for stopping electrons
- No interlock
- Direct signals on OASIS
- WP responsible: BI-PM, in collaboration with TE-ABT
- **Planning:** Septum design nearly completed  $\Rightarrow$  **BI should propose a design ASAP**




# Schottky signals for energy spread measurements at injection

- Motivation:
  - Limited resolution from the Feshenko monitor in the LBS line
  - For BCMS beams: the PS needs very well defined energy spread
  - Compensate for longitudinal painting
- A schottky monitor in the PSB for  $\Delta E/E$  at injection, using existing pick-ups.
- Recent request
- No specification, no WP, no planning
- WP responsible: BI-PI



# Conclusion

- New baseline for Linac4 to PSB connection: **End 2016**
- **Commissioning in Half-injection sector test: OK** if clear planning and temporary installation (**cables** + controls)
- Time and budget wise, **the LIU-PSB WPs presented here can make it**, provided the requested **cables** be pulled
- Some concerns:
  - **BI.BCT20**: high dose rate, no spare (CONS)
  - **SEMs**: S/N ratio, development in 2015
  - **New WP requests**: find resources



# LHC Injectors Upgrade

**THANK YOU FOR YOUR ATTENTION!**

