



# Linac4 H<sub>2</sub> injection system

P. Carrié, F. Fayet, R. Guida, S. Izquierdo Rosas, J. Rochez, A. Wasem, M. Wilhelmsson

J. Lettry, R. Scrivens, E. Mahner

Roberto Guida PH-DT-DI

Linac4 Ion Source Review November 14th, 2013



### Outlook

- Introduction
- H2 supply systems: description
- Software Controls and User Interface
- Performances
- Budget analysis
- Conclusions



# Linac4 H<sub>2</sub> supply system

- Detector Technologies
- Two identical systems: 3 MeV Test Stand and Bldg400:
- Each system contains H<sub>2</sub> gas supply for Ion Source and LEBT
- H<sub>2</sub> supply at 3 MeV Test Stand operational since August 2012
- H<sub>2</sub> supply at Linac4 Bldg400 operational since August 2013





### The team involved

PH-DT Detector Technologies


#### 

Linac4.....Jacques, Richard, Edgar, Michael



Ion Source H<sub>2</sub> supply


Detector Technologies







CERN





### Software controls

- Remote monitoring and control
- Application running on PLC with remote interface in PVSS
- Local touch screen is available
- Alarms propagated via email/sms
- Prepared following the standard used for gas systems at LHC experiments

#### **Operational States**

**Stop** – (maintenance, modifications)–all the actuators in their fail-safe positions.  $H_2$  has been evacuated from the system.

**Stand-by** – (allows interventions on other systems) –The gas system is stopped with all the actuators in their fail-safe positions,  $H_2$  has not been evacuated.

**Evacuate** – (improve gas purity at  $H_2$  filling) –  $H_2$  is evacuated from the gas system until a certain pressure threshold is reached.

**Run** – (normal gas system operational state): The gas system is running and all the parameters are stable and within the defined limits for this operational state.




**Detector Technologies** 

#### Software controls - Interface

Controls and Interface








### Software controls - Interface

- PH-DT Detector Technologies
- On-line values and immediate access to one year data
- Values published on DIP for other users (i.e. Linac4 control system)






#### Software controls - Interface

PH-DT Detector Technologies

Controls and Interface





# **Controls and Performances**

#### **Safety and Alarms:**

- Detection of abnormal consumption:
  - At supply level  $\rightarrow$  pressure drop in H<sub>2</sub> cylinder
  - At P regulation level  $\rightarrow$  H<sub>2</sub> flow monitoring
- Several alarms implemented for system stop, unstable regulation, failure of components, measurements out of range, ...


#### **Performances:**

- Stable operation (the system at the 3 MeV Test Stand is operational since one year)
- Gas density regulation is better than 0.5 mbar at 25 °C
- System tested with Pressure set-point for operation from 100 mbara to 1800 mbara
- About 15 minutes for achieving set-point with standard regulation from vacuum to 1300 mbara (room for improvement)



### Performances – gas density regulation

Detector Technologies





## Budget analysis

PH-DT Detector Technologies

			Price (CHF)	Team
Budget for construction		Ion source	20 k	PH-DT-DI/gas team
		LEBT	12 k	PH-DT-DI/gas team
		Pipes/connectors	4 k	PH-DT-DI/gas team
		Pressure regulators	5 k	EN-MEF-SI
		manpower (mechanical and electrical)	7 k (165 hours)	PH-DT-DI/gas team
		Functional analysis	-	PH-DT-DI/gas team
		PLC and I/O modules	4 k	EN-ICE-PLC
		Software PLC and PVSS	-	EN-ICE-PLC

#### About 55 kCHF (including manpower) per rack



### Conclusions

- Two H<sub>2</sub> (or other gases) supply racks have been built for 3 MeV Test Stand and final Linac4 system at Bldg400
- Each rack contains fully independent H<sub>2</sub> supplies for Ion Source and LEBT
- Fundamental to study/record the stability of the 4 systems over the coming months/year
- Construction based on experience from gas systems for the LHC experiments which demonstrated extremely high availability (>99.9% power cuts excluded) over the last years
- Spare parts, maintenance, manpower, ... needed for operation to be reviewed in few months
- Each system has already an on-site redundancy to cope with unexpected failures

Conclusions