

CLIC-ILC Cost & Schedule Agenda – 8feb08

John Carwardine = secretary & rapporteur

this file: <http://www-ilcpcb.fnal.gov/CLIC-ILC/Cost & Schedule Sub-Group 8feb08.ppt>

10:15-10:20 – Reminder of ILC Confidentiality Protocol (PeterG)

10:20-10:55 – ILC Presentation (Peter Garbincius)

RDR Estimate – instructions, format, basis, status, evolution into TDR est.

examples: Klystrons & Modulators, Beam Delivery System, Schedules

ILC Project Management Plans including Primavera

discussion of needs and desires

10:55-11:30 – CLIC Presentation (Hans Braun)

status and discussion of needs & desires

11:30-11:45 – Integrating parametric studies, risk analyses, and inflation
in the cost estimate (John Carwardine)

11:45-12:15 - Common CLIC-ILC Cost & Schedule Activities (All)

Goals – what we need to work on

Plan on how to work together

What can we expect to deliver over what timescale? (pre-) Sendai

logistically, we could not arrange a joint parallel session between

Civil Engineering & Conventional Facilities and Cost & Schedule working groups

maybe this can be done by WEBEX...

ILC-GDE Cost Disclosure Rules

<http://www-ilcdcb.fnal.gov/cost-confidentiality-official-njw.pdf>

This meeting will involve discussion of actual cost estimating numbers and data

“review” access has been granted by the GDE Executive Committee to cost data

- questions are allowed, but

- no hard copy or e-file

you must agree (or have previously agreed) not to discuss outside of context of this meeting, publish, or post on public web-site any cost estimating information

Agreed for CLIC-ILC meeting: P. Garbincius, J. Carwardine, T. Shidara,

S. Weisz, H. Braun, K. Foraz – *is anyone else participating?*

ILC Cost & Schedule Status

Peter H. Garbincius

ILC-GDE and Fermilab

CLIC-ILC Collaboration Meeting

CERN, February 8, 2008

RDR Estimate – instructions, format, basis, evolution

Examples: BDS (incl CF&S) and Klystrons & Modulators

Project Management Plans – including Primavera

ILC needs

Public References:

<http://www.linearcollider.org/cms/?pid=1000437> download Vol 3 - Accelerators

http://ilcdoc.linearcollider.org/record/6321/files/ILC_RDR_Volume_3-Accelerator.pdf

http://www-ilcdcb.fnal.gov/RDR_costing_guidelines.pdf

http://www-ilcdcb.fnal.gov/RDR_Cost_Estimating_Instructions_23may06.pdf

http://www-ilcdcb.fnal.gov/CLIC-ILC/no-cost_roll-up_1june07.xls

http://www-ilcdcb.fnal.gov/CLIC-ILC/no-cost_BDS_KOM_11oct07.pdf

http://www-ilcdcb.fnal.gov/CLIC-ILC/no-Cost_HLRF_KOM_Oct_1-3-07_SLAC.pdf

ILC Beam Delivery System Estimate

- Confidential BDS estimate

[BDS_WBS_v1.9_19dec06.xls](#) – on PHG desktop


- Skim through my summary presentation at EDR Kick-Off Meeting for BDS in October 2007

[http://www-ilcdcb.fnal.gov/CLIC-ILC/no-cost BDS KOM 11oct07.pdf](http://www-ilcdcb.fnal.gov/CLIC-ILC/no-cost_BDS_KOM_11oct07.pdf)

this includes examples of next lower level spreadsheets from Global & Technical Systems

- XXX

Continuing Evolution & Value Engineering for BDS



| Possible savings due to changes in design or assumptions | | |
|--|----------------|---|
| Savings may not be feasible, and may not be additive, and require more studies | | |
| 14/14 baseline cost | 883844 | |
| cost of 20/2 alt (single 5m wall, deassigned shafts & bypass) | 100.00% | consequence |
| assign e+ bypass back to BDS from e+ | 1.86% | TPC does not change |
| assign shafts 2 & 3 back to BDS from linac | 3.63% | TPC does not change |
| use two 9x18m muon walls instead of one 5m wall | 2.26% | can collimate 1e-3 instead of 2e-5 |
| move cost of spare FDs to operation cost | -1.87% | risk that spare FDs will not be produced and will not be available if needed |
| decrease size of collider hall from 32*72*40m to 32*54*35m & assume surface detector assembly | -5.53% | cannot assemble detector underground and commission the BDS. Do not accept it for separated halls as independence of commissioning is required. |
| do not install PS for 1TeV at the start | -2.83% | harder 1TeV upgrade |
| do not install full cooling capacity for 1TeV | -6.03% | harder 1TeV upgrade |
| Reduce number of bends | -0.65% | E upgrade more difficult |
| Decrease vacuum chamber aperture | -0.57% | more losses and background |
| Reduce number of movers | -0.11% | more complex tuning |
| Shorten extraction lines by 100m and rely on sweeping | -0.79% | MPS issues in beam dumps |
| Shorten the separate low E+ tunnel | -1.01% | cannot access part of beamlines of IR which is OFF |
| Combine two IR halls, by increasing sum of crossing angles to ~28mrad, on surface detector assembly, decreased collider hall size to 38*32*35m | -5.84% | In this case one can simultaneously commission beamline and make final assembly at other IP, then move detector to the commissioned IP. Self shielded detector would add benefits. Transition from push-pull may be smooth. This saving already included in 14/14 with smaller hall |
| Change construction of tapered tunnel (which is 2*1400m): make taper starting only when beamlines separated by 3m, thus reduce tapered tunnel to 2*1000m and replace the rest 2*400m with usual TBM tunnel | -1.51% | Difficult access around beamlines in BSY region |
| Replace full power tune-up dump with low power (see sub table for evaluation) | -2.97% | MPS and operation issues, full power dump may be needed elsewhere |
| Total acceptable savings for baseline | -17.33% | |
| Total savings applicable to 14/14 case | -12.33% | |
| Combine tune-up dump with one of main dumps, total: | 2.37% | MPS & operation issues, and accessibility of collider hall |
| less cooling capacity at point 2&3 | -2.67% | |
| less beam dump halls & hardware | -2.28% | |
| increased cost of main dumps | 1.81% | |
| magnets in additional transport line | 1.44% | |
| vacuum system of additional transport line | 4.07% | |
| Replace full power tune-up dump with low power, total: | -2.97% | MPS & operation issues, high power dump may be needed elsewhere |
| less cooling capacity at point 2&3 | -2.52% | |
| less cost of tuneup dumps | -0.45% | |
| Remove service tunnel, total: | 1.46% | issues with access, T stability in tunnel, cabling, laser rooms, etc |
| remove service tunnel | -5.83% | |
| move shafts 2&3 by 1000m closer to IP and incur higher cost of crgo tranfer line (8k/m) | 1.81% | use this as less cost impact |
| or: build a BDS dedicated shaft 1750m from IP | 3.63% | do not sum this one as higher cost impact |
| build partial service tunnels near IR along extraction and near BSY, total 2*600m, excavation, not TBM | 3.54% | |
| build 20 alcoves with volume 300CY, excavation | 0.25% | |
| increased overhead of power supplies | 1.13% | |
| increased cost of cables | 0.57% | |
| Savings may not be feasible, and may not be additive, and require more studies | | |
| | actual | with savings added |
| Cost of 20/2 alt | 1.000 | 0.827 |
| Cost of 14/14 small hall | 1.368 | 1.245 |

ILC High Level RF Power Estimates

Ray Larsen (SLAC) & Shigeki Fukuda (KEK)

Team Leaders

- Skim through RayL's summary presentation at EDR Kick-Off Meeting for HLRF in October 2007


http://www-ilcdcb.fnal.gov/CLIC-ILC/no-cost_HLRF_KOM_Oct_1-3-07_SLAC.pdf

- view Confidential HLRF estimate spreadsheets

HLRF WBS SUM 121906 R26 rsl-mn.xls – on PHG desktop

ILC Schedules – need a lot of work!

- Top-down goal of 7 year construction period
 - Do as much design, contractor selection, industrialization, etc. as possible beforehand
 - Does not include commissioning of accelerators
- Is this even possible technically, logistically, or financially?
- (non-integrated) schedule examples (RDR III-6.3):
 - Martin Gastal – CF&S – shafts, tunnels, and caverns
 - Bob Kephart – Cryomodule industrialized production
 - Ewan Paterson – Funding profile
- How do we manage and control all of this?
 - Multiple TBM operations, concurrent installation?
 - Multiple world-wide vendors of high-tech components



**A Sample Cryomodule Production Schedule
for One Region**





FIGURE 6.3-3. A possible model schedule for cryomodule production shows 1/3 of the required ILC cryomodules produced in one of three regions. R&D and pre-series devices lead to 5 years of series production (yellow). The position and magnitude of the peak of series production will vary with changes to the available construction and test infrastructure.

% of Total Value per Year



ILC Project Management Plans

- a multi-B€, complex, international, project
 - Expect to quickly outgrow MS Project
 - Need integrated cost & schedule, enterprise level Project Management tools,
stable, well supported, preferably commercial
 - Options considered:
 - Primavera – most users world-wide, international support, used by most US National Labs and Projects
 - OpenPlan – also used in US, e.g. Fermilab projects
 - CERN EVM & PPT – Bill Willis & PHG investigated in Jan06
 - could not get promise of continuing CERN support
- Goal: implement PM discipline during TDR phase
- Purchased Primavera P6 (web-based) licenses

P6 Functionality by Level

| concurrent Level 4 – Complete Solution | | Remaining Level Functionality | | |
|---|--|-------------------------------|--|--------------|
| Level 4 Components | Key Functionality | Level 3 | Level 2 | Level 1 |
| Client (planning and scheduling) | <ul style="list-style-type: none"> Includes Planning and Scheduling (client): • Multi-project support • Security and administration • Master program integration • Resource leveling • Advanced baseline management • Report creation | Not included | Not included | Not included |
| Web Project, Resource, Portfolios | <ul style="list-style-type: none"> • 100% Web • Planning and scheduling one project at a time • Intuitive, interactive PM • High-level resource planning • Analyze capacity vs demand • Portfolio performance | Included | Partial -No resources -No portfolios - Can only view task and update project status | Not included |
| Advanced Portfolio & Capacity Planning | <ul style="list-style-type: none"> • Strategic planning and optimization of: <ul style="list-style-type: none"> - portfolios - capacity • Calculated KPIs | Included | Not included | Not included |
| Dashboards | <ul style="list-style-type: none"> • Standard and configurable views • Unlimited number | Included | Included | Not included |
| Collaboration | <ul style="list-style-type: none"> • Personal and project workspaces • Communication center • Discussion threads, doc mgt, workflow | Included | Included | Not included |
| Timesheet | <ul style="list-style-type: none"> • Capture and track time • ADA Section 508 compliant | Included | Included | Included |
| API | <ul style="list-style-type: none"> • Open API for easy integration | Included | Included | Included |

5 L4 Planner Scheduler, 5 L3 Engineer (myPrimavera), 1 L2 TM-Collaborator, 1 L1 Team Member 12

Need to implement:

- Hardware – evaluated Primavera-endorsed, off-site, commercial host - reduce in-house costs contract held up by ILC budget situation in US
- Project Management Support Team
 - Goal is 3 experts centralized at PM office at Fermilab plus local help for the PMs at KEK and DESY
 - Shouldn't rely on sci/eng to invent it themselves
 - Couldn't secure experienced PM people from US Labs
 - Completed call for tender for consulting firms to get ILC PM Office and tools started contract held up by ILC budget situation in the US
 - Obvious place where ILC can use PM assistance!

What help does ILC Project Management Team Need?

- Can/should we reopen question of EVM & PPT?
- Experienced Scheduling Expert(s)
- Project Management Team members
 - Either experienced in Primavera or able to learn
- Develop the plan to implement PM tools both for TDR and for the actual construction project
- Evolving the ILC Estimate for completeness and to facilitate (parametric) studies – DataBase?
- What else?

What does ILC need for Project Management Support and when?

Short term – immediately:

Plan, Plan, Plan, Plan!

improvements to RDR
estimate – DataBase?

implement Primavera

start managing a sample
of TD Work Packages
including Earned Value

Through the TD period:

improved estimates:

requirements, instructions,
templates, etc.

Evolve from Bill of Materials to
activity-based WBS

Integrated Cost/Schedule/EV
Value Engineering and
other cost reductions

Use TD experience to show we
can manage ILC

CLIC-ILC Cost & Schedule Agenda – 8feb08

John Carwardine = secretary & rapporteur

10:15-10:20 – Reminder of ILC Confidentiality Protocol (PeterG)

10:20-10:55 – ILC Presentation (Peter Garbincius)

RDR Estimate – instructions, format, basis, status, evolution into TDR est.

examples: Klystrons & Modulators, Beam Delivery System, Schedules

ILC Project Management Plans

discussion of needs and desires



10:55-11:30 – CLIC Presentation (Hans Braun)

status and discussion of needs & desires

11:30-11:45 – Integrating parametric studies, risk analyses, and inflation in the cost estimate (JohnC)

11:45-12:15 - Common CLIC-ILC Cost & Schedule Activities (All)

Goals – what we need to work on

Plan on how to work together

What can we expect to deliver over what timescale? (pre-) Sendai?