



*HEPTech Academia - Industry Matching Event on  
Technology of Controls for Accelerators and Detectors*

# **CLIC Two-beam Module controls issues**

*Dec 2<sup>nd</sup>, 2013*


G. Riddone

- CLIC introduction and timeline
- Main requirements
- Main issues
- Solutions under study
- Conclusions and next steps

# CLIC in few words

- Linear collider  $e^+/e^-$  with center-of-mass collision energy up to 3TeV
- Total length up to 48 km; main linac  $\sim 90\%$
- Based on two-beam acceleration
  - Drive beam (RF decelerating structures – PETS – which transfer the RF power to the main beam via a complex RF network)
  - Main beam (RF structures which accelerates the beam – 100 MV/m)
- Main linac houses the 2-m long two beam modules (TBM)
- For the control of the TBMs, we have to develop a compact acquisition and control module (ACM)

# CLIC Layout at 3 TeV




Main LINAC → two-beam modules

Main Beam Generation Complex

# CLIC project time-line

## 2012-16 Development Phase

Develop a Project Plan for a staged implementation in agreement with LHC findings; further technical developments with industry, performance studies for accelerator parts and systems, as well as for detectors.




## 2016-17 Decisions

On the basis of LHC data and Project Plans (for CLIC and other potential projects), take decisions about next project(s) at the Energy Frontier.

## 2017-22 Preparation Phase

Finalise implementation parameters, Drive Beam Facility and other system verifications, site authorisation and preparation for industrial procurement.

Prepare detailed Technical Proposals for the detector-systems.




## 2022-23 Construction Start

Ready for full construction and main tunnel excavation.

## 2023-2030 Construction Phase

Stage 1 construction of a 500 GeV CLIC, in parallel with detector construction.

Preparation for implementation of further stages.




## 2030 Commissioning

From 2030, becoming ready for data-taking as the LHC programme reaches completion.

\* S. Stapnes, CLIC Workshop 2013, CERN

# Two-beam module layout



**CLIC at 500 GeV (4232 modules)**

26920 Accelerating structures

13460 PETS

~ 70000 RF components

**CLIC at 3 TeV (21460 modules)**


142760 Accelerating structures

71380 PETS

~ 400000 RF components




# First TBM prototype



Collaboration with NTUA  
and other Greek  
institutes (PATRAS,  
Democritos,...)


# RF system – RF structures




Accelerating structure (AS) – disks with 4 manifolds and all needed technical systems



RF network:  
waveguides and  
several RF  
components



PETS – octants housed in a tank and coupler







# RF structures - Requirements

Requirements are dictated by beam physics and RF

→ ultra high precision machining and positioning to allow the beam to pass through (beam emittance few nm in V)



# Acquisition and Control Module

- For the TBMs, we have to develop a compact acquisition and control module (ACM)
- ACM: a device providing timing, data acquisition and control to the different systems (Alignment, Stabilization, Power, Vacuum, Cooling, ...), communicates with Front End Computers (FECs) installed in alcoves.

# Inventory of signals

Ch type	S-rate [S/s]	Resolution [bits]	# ch
V. Fast ADC	2 G	8	0
Fast ADC	200 M	14	28
Slow ADC	1 k	16	105
Slow DAC	1 k	18	8
Raw DIO	1 k		146
Serial I/O			14
Total per TBM			301


**Including spare: about 500 signals per modules,  
In addition: to increase reliability, critical signals for machine operation (~50)  
could be duplicated in adjacent ACMs**

# ACM constraints and requirements

- CLIC have to concentrate all (or most of) data acquisition and setting through a single point (ACM) → generic solution suitable to all technical systems
- Due to sector dimensions digitalization shall be done in place.
  - Sector length 878m
  - Considering central counting room the distance between TBM and counting room can be over 400m
- Common timing
- High reliability and easy maintainability
- Modular and compact design
- Power consumption < 50 W
- Cost (large series production)





# Possible layout




# Tunnel integration

- Radioactive zone: TIDs, from 100 to 1000 Gy
- Tunnel integration; several options under study




# Signals Timing Diagram



**Total bandwidth per ACM (@50 Hz): < 5Mb/s**

# Common timing

- Data acquisition and digitalization is done at ACM level.
- Acquired data are then pushed to the control system.
- The control system needs to synchronize and correlate all this data.
- It is necessary to synchronize all the nodes and propagating a common timing to all the ACMs:



**Total bandwidth per ACM (@50 Hz): < 5Mb/s**

Sampling clock  
synchronization: ##### ns



# Radiation constraints

- Radiation issue is a key point to design the control infrastructure
  - high-level of radiation (100Gy .. 1kGy/y) **although proper estimation is still needed** (energy, spectrum, fluence)
- Radiation effects on electronics:
  - TID (Total Ionizing Dose), destructive. Electronics needs to be periodically replaced.
  - SE{L/GR/B} (Single Event {latchup/gate rupture/burnout}): if not destructive, can be addressed at design level via TMR (triple modular redundancy).

# Alternative solution for ACM development

- Industrialized solution
- Development based on NI-PXI systems
  - Miniaturise 15 boards into 1 small box
  - NI has long experience with custom design

# NI system overview



Controller

Synchro  
IEEE-1588

Fast ADC

DIO

DIO + Slow ADC + DAC

Serial

# FPGA controller

- Fiber-Optic MXI-Express x4 link, PXIe-PCIe8375
- 838 MB/s sustained transfer rate
- Remote control of PXIe crate





# Conclusions and next steps

- Up to 20000 TBM, 500 signals each
- Modular system adapted to all module components
- Challenging development taking into account several requirements
- Prototypes to be procured and tested under accelerator conditions



# Thanks for your attention

**Acknowledgements to D. Gudkov, F. Locci, A.  
Rijllart, A. Samoshkin for their great  
contribution for the preparation of this  
presentation**