



# FIO

# Fabric Infrastructure and Operations

CERN IT  
Department

## Tier0 Status

Tony Cass

(With thanks to Miguel Coelho dos Santos & Alex Iribarren)

LCG-LHCC Mini Review, 1<sup>st</sup> July 2008

- Resource Ramp-up
- CASTOR Performance and Metrics
- Power Issues and Progress

- **Resource Ramp-up**
- CASTOR Performance and Metrics
- Power Issues and Progress

- **Resource Ramp-up**
  - Tier0 purchasing affected by two issues
    - Elonex bankruptcy
    - Disk server problems under heavy load
- CASTOR Performance and Metrics
- Power Issues and Progress

- **Elonex Bankruptcy**
  - One disk server order rapidly switched to alternative suppliers.
  - Second disk server order plus CPU order switched to alternative suppliers after FC in March.
- **Disk server load issues**
  - Problems brought to light by improvements to hardware burn-in procedure.
    - Load to provoke issues significantly exceeds normal load on disk servers.
    - Previous generation servers also show the problems with extremely high load.
    - New capacity now released to deployment (and many servers have run well for some time with no issues.

- CPU
  - 100% of pledge delivered in early May, i.e. with one month delay
- Disk
  - 52% of pledge delivered to experiments in early May.
  - Balance of pledge is at CERN and will be deployed progressively in coming weeks.
  - Delay, but minimal impact on CCRC exercise
- Tape
  - 100% of pledge available well before April
- 2009 Procurements
  - On schedule: tenders for September FC adjudication opened; tenders for December adjudication to be sent out shortly.

- Resource Ramp-up
- **CASTOR Performance and Metrics**
- Power Issues and Progress




- Resource Ramp-up
- **CASTOR Performance and Metrics**
  - CASTOR Service
  - SRM Interface
  - CASTOR metrics
- Power Issues and Progress




- CASTOR ran well throughout the May CCRC Overall through end-user: load seemed low...

- In general incidents (<10) were detected rapidly, resolved quickly and only affected a single CASTOR instance.



Three problems with the garbage collection mechanism for CM contributed to large peaks of internal traffic...


- The exception was a problem on the CASTOR CASTOR public service which impacted ATLAS as the SRM interface was shared; this configuration was due to hardware (non-)availability; the planned dedicated SRM interfaces are being deployed.



It showed the I/O capacity of the CMS setup (peaks of 9GB/s (in+out))

- Desired operational improvements (notably tape request prioritisation) are being deployed with promising initial results.

- When it works it works well
- A large volume of data was transferred
- The average rate was high



- Reliability is still an issue
- ~10 incidents with impact ranging from service degradation to complete unavailability

- May 5 - **redundant SRM back-ends lock each other in database** [ALL VOs]
  - May 13<sup>th</sup> - **lack of space on SRM DB** [LHCb]
  - May 13<sup>th</sup> - **DB "extreme locking" / DB deadlocks** [ALL VOs]
  - May 9<sup>th</sup>, May 14<sup>th</sup>, May 19<sup>th</sup> - **SRM 'stuck' / no threads to handle requests** [ATLAS]
  - May 21<sup>st</sup>, May 24<sup>th</sup> - **slow stager backend causes SRM stuck / DB overload** [ All VOs]
  - May 30<sup>th</sup> - **get Timeouts due to slowness on Castor backend** [ATLAS, LHCb]
  - 3 times in May - **problematic use of soft pinning caused GC problems** [CMS]
  - June 6<sup>th</sup> - **patch update crashed backend servers** [ATLAS, ALICE, CMS]
- 
- To be improved:
    - Better resiliency to problems
    - More service decoupling
    - Some bugs need to be fixed
    - Better testing needs to be done


- Separate out LHC VOs from shared instance **Done**
- Migrate all SRM databases to Oracle RAC **Done**  
(done for ATLAS)
- Upgrade to SRM 2.7 and deploy on SLC4\*  
**In (very early) test**
  - Redundant backends
  - Uses CASTOR 2.1.7 API which allows deployment of redundant stager daemons
  - Deploy fixes for identified bugs
- Configure SRM DLF to send logs to appropriate stager DLF\* **In test**
  - Improve our debugging response time
- Continue improving service monitoring

\* Required for "time to turl" metric; could be delivered in ~1 month.

- Metric implementation continues as collaboration between developers and operations teams.
- Improved instrumentation rolled out during CCRC in May
  - so few measurements for LHCb or ALICE
  - no upload to Lemon; excel plots only
- New Lemon sensor for CASTOR will be deployed in the near future to deliver automatic generation of metric plots
  - (this version centralises all daemon monitoring, so needs the 2.1.7-10 CASTOR release.)
- The following slides show a selection of metric plots which cover performance and issues during the May CCRC.




## Typical Drive Performance




Date	Alice	Atlas	CMS	LHCb
CCRC May '08	322 MB	1291 MB	872 MB	1327 MB
March '08	143 MB	230 MB	1490 MB	865 MB
CCRC Feb '08	340 MB	320 MB	1470 MB	550 MB
Jan '08	200 MB	250 MB	2000 MB	200 MB


## CASTORATLAS Number of migrated files per day



## CASTORCMS Number of migrated files per day










T0ATLAS is working well. Already mentioned issue on default pool...

- Repeated (read) tape mounts per VO




High value of repeat mounts for reading...

CASTORATLAS Get/Put latency




CASTORCMS Get/Put latency



- Resource Ramp-up
- CASTOR Performance and Metrics
- **Power Issues and Progress**

- Resource Ramp-up
- CASTOR Performance and Metrics
- **Power Issues and Progress**
  - B513 status
  - New Computer Centre Planning
  - Covering the Gap

## CPU Server Power Consumption





- In-house design and construction of new centre not possible (TS effort focussed on Linac4).
- No desire to tender for turn-key design and construction
  - Lowest cost bidder wins...
- Four phase process developed:
  1. Request (many) conceptual designs
  2. Commission 3-4 companies submitting conceptual designs to develop an outline design
  3. In-house, turn a selected outline design into plans and documents enabling
  4. Single tender for overall construction.
- “Call for proposals” for the conceptual designs sent out (deadline July 18<sup>th</sup>); process could lead to negotiation of construction contract end 2009.
  - Estimate subsequent detailed design phase of ~6 months and construction phase of ~18 months
  - New centre available for equipment installation in Jan 2012



- B513 OK until end 2010 +  
New Centre from Jan 2012 ==>
  - Need to cover 2011 installations
  - Plus 1H2012 installations in case of construction delays.
- Tier1 centres asked for possible spare capacity in this window.
  - Oslo could be a possibility: Completing 2MW facility end-2009, but only need 1MW initially.
    - Discussions on modalities (hardware requirements, operation model, ...) to start soon.
- Reviewing co-Lo options within ~1hr of CERN.
  - No spare capacity at present,
  - Options possible on 2011 timeframe, but still at ~2kW/m<sup>2</sup>, so likely very expensive.

