



CLIC Workshop 2014

Monolithic transformer-based Klystron Modulator for the CLIC Drive Beam

Francisco Cabaleiro

LEEPCI – Laval University (Canada)

CERN – European Organization for Nuclear Research




Outline

- Introduction
- Objectives
- R&D Status
 - Methodology
 - Topology Selection
 - Power & Droop Compensators
 - Monolithic Pulse Transformer
- Schedule

Introduction

•Pulse Requirements

Nominal pulse voltage	V_{kn}	150 - 180 KV
Nominal pulse current	I_{kn}	160 - 195 A
Rise & Fall Times	t_{rise}, t_{fall}	3 μ s
Settling time	t_{set}	5 μ s
Pulse Length	t_{flat}	140 μ s
Repetition Rate	REPR	50 Hz
Voltage overshoot	V_{ovs}	1 %
Flat-top stability	FTS	0.85 %
Pulse to pulse repeatability	PPR	10 ppm
Pulse efficiency	η_{pulse}	95 %
PFS electrical efficiency	η_{pfs}	98 %
Modulator global efficiency	η_{mod_global}	90 %





~1300 modulators of 29MW

Total peak power: ~40 GW

Average power consumption: ~300 MW

Objectives

- Optimal Design of a Klystron Modulator for CLIC-DB, based on a monolithic transformer based topology, capable of:
 - Respecting the challenging pulse and efficiency specifications.
 - Operating at constant power consumption




R&D Status

- Influence of several modulator parameters on active bouncer requirements


Examples:

- HV charger bandwidth
- Transformer droop
- Main capacitor bank size




R&D Status

- Influence of several modulator parameters on active bouncer requirements
 - Need for an integrated system approach
 - Constrained nonlinear optimization




R&D Status

- Methodology



R&D Status

- Topology Selection



R&D Status

- Power & Droop Compensators:
 - 300 kW prototype (1kV, 300A).




***Validation & Correction of Mathematical Models
and Control Strategies***



R&D Status

- Monolithic Pulse Transformer




R&D Status

- Monolithic Pulse Transformer
 - HV Tests: Determination of expert coefficients



MIDEL & Silicon
Oil tests



PEEK test



Insulation system test

Schedule

- 2014:

	February - July	August	September - December
Theoretical Studies			
Prototype Testing			
Compensator Final Design			
Transformer Final Design			
Specification & Purchasing of Components			

- Beginning of full scale construction: December 2014
- Full Power Testing & Validation: 2015



www.cern.ch