

# Status and plans for Two-Beam Test Stand and Two-Beam module in CTF3


Wilfrid Farabolini




# Contents

- Test of the 2 accelerating structures installed in TBTS
  - Energy gain performances
  - Beam kick experiment
  - BD statistics
  - Wake Field Monitors
  - Beam shape change after ACS
- Diagnostics tests
  - Electro Optical System for Bunch Length Measurement
  - Cavity BPMs
  - Diamond detector
  - Cherenkov crystals for spectrometer
  - Coherence length of Optical Diffraction Radiation
- Installation of CLIC module
- Tests planned with the CLIC module

# 2 Accelerating Structures in the TBTS




TD24 structure




ACS tank



TBTS








One PETS for 2 structures



Probe beam Energy with and w/o RF power after phase “optimization”


# Improvement of RF lines calibration



L. Timeo  
S. Rey  
N. Vitoratou


Injection after the 50 dB coupler of a RF calibration signal (1 kW – 11994.2 + 2 MHz)

# Beam kick




On YAG screen  
without BD


With BD



Time resolved position on  
cavity BPM




Kicks to the beam measured on screen CA.MTV0790




A. Palaia PhD Thesis

Anisotropy not explained but still not enough statistics

# 2 models for a “single” phenomena



Magnetic deflection by a BD arc of 200 A approx.





Asymmetric blowout of the BD inhomogeneous plasma [\*].

[\*] Refraction of  $e^-$  beam due to plasma lensing at a plasma-vacuum interface, A.A. Sahai, T.C. Katsouleas, June 16, 2013





Experiment to discriminate these 2 phenomena (large statistics needed)

- Use a delayed (several  $\mu\text{s}$ ) probe beam after the BD
- Send the PB at zero crossing

# BD statistics studies




- No hot cell in whatever ACS,
- BD rather evenly distributed in the 2 structures,
- No new data in 2013 since not enough power after conditioning (85 MV/m).




See B. Wooley and A. Degiovanni presentations (Tues. 04)

But huge quantity of data generated and analyzed from the X-Box1

# Wake Field Monitors study



## WFM signals from a PB pulse



WFM signals without  
12 GHz RF power


WFM signals with RF power

F. Peauger - IRFU


- Two types of WFM installed on the structures : (HOMs: 18 GHz and 24 GHz).
- Resolution already better than 20  $\mu\text{m}$ .
- Robustness with nominal 12 GHz RF power (42 MW) still to be investigated



# Re-alignment of the 2 structures



First successful results: realignment of the ACSs tank according to the position delivered by the WFM.  
Using corrector is now no longer required to transport the beam through TBTS line.



# New acquisition electronics



Present log detector PCBs and crate




Next PCB (8 channels log detector)


A. Andersson  
A. Khan  
S. Rey

- Based on a novel “log detector” chip still operational at 24 GHz
- New design shared with X-Box2 data acquisition system
- WFM tests to be resumed in February with RF nominal power


# Octupolar modes evidences




Large beam ( $\Phi > 5$  mm) shadowed by the structure, non accelerated (left) and accelerated (right)



For very weak RF power (few MWs, uncertain phase)



At zero-crossing (rising RF power side), 25 MW




At zero-crossing (falling RF power side), 25 MW

Effect of the disks symmetry (HOM damping waveguides) already foreseen but not significant for a well centered small size beam (green beamlets on the simulation).

*“Multipoles of the accelerating field and the beam distortion in TBTS”, Alexej Grudiev, 29/05/2013 CLIC RF Structure Development Meeting*

# Beam shape and coupling







**Figure :** Image of the probe beam for a non-accelerated (a) and accelerated case (b). A change of the beam position as well as of the size and the x-y-correlation is visible.

Question: How does the RF influence the beam transversely?


***“Measurement of transverse coupling in the TBTS, Christopher Borgmann, 22. October 2013, CLIC/CTF3 Exp. Verification meeting”***

# Electro Optical Sampling



EO Spectral Decoding


Rui Pan (PhD student), Electro-Optical Bunch Profile Measurement at CTF3 IPAC'13 MOPME077.




See S. Mazzone talk "Beam instrumentation developments at CTF3", This WS, Tues 17:30

A laser pulse (top trace) is visible 420ns after the trigger signal (RF), bottom trace. Evidence for a depolarisation induced by the E-O crystal


# Short bunches no longer achieved



Streak Camera



CTF3 logbook 3 July 2009





Particles tracking model

- Despite the phase shifter for setting the first LIL structure in velocity bunching, bunch length is always longer than 15 ps FWHM
- Before phase shifter installation, 3.3 ps bunch length was measured with the deflecting cavity.
- To be solved urgently (particles tracking model, RF pulse compression phase...)

# Cavity BPMs

- BPM required to measure orbit with 50 nm and 50 ns resolutions.
- 15 GHz stainless steel prototype cavity BPM installed in CALIFES.
- Two cavities: Position (dipole) and reference (monopole).
- Beam tests last spring.
- No motor control to vary beam position, used corrector magnets.





*F. Cullinan , J. Towner*

See S. Mazzone talk  
“Beam instrumentation  
developments at CTF3”,  
This WS, Tues 17:30

# Other diagnostic tests in preparation



**Diamond  
detector**



*F. Burkart, O. Stein (TE-MPE-PE)  
E. Nebot Del Busto (BE-BI-BL)*



Very low and well  
calibrated bunch charge  
requested ( $10^5 e^-$ )

**Cherenkov  
crystals for  
spectrometer**



See S. Mazzone talk  
“Beam instrumentation  
developments at CTF3”,  
This WS, Tues 17:30


**Coherence  
length of  
ODR light**





# CALIFES beam time use in 2013

Califes Beam Time (days)




- Cavity BPM : 22 days
- EOS : 18 days
- WFM : 5 days
- CALIFES development : 7 days
- TBTS acceleration: : 3 days

**Beam interrupted from June 2013**


# Installation of the CLIC module



The CLIC module in the lab




The RF network



The CLIC module on the beam lines (longer than the TBTS)

G. Riddone, D. Gudkov (BE-RF-PM)

# Preparation work has started in CLEX



A shelter on the car park to host the new equipments



A trench cut for the cables



External wall drilled according to RP requirements




TBM TO@CLEX Cabling Summary

System	Racks for electronics		Cable Type	Quantity	Ø (mm)	Starting (S) and End (E) Points				A
	Shielded bunker	CITP3 gallery				TB04	Shielded bunker	Outside Shelter		
Pre-alignment	Sensor conditioning crates (375, 30 x 200mm)	2 x 43 U (2 racks)	Shielded bunker	40	4	S	Shielded bunker	Outside Shelter	640	
			Shielded bunker	8	4	S	Shielded bunker	Outside Shelter	650	
			Shielded bunker	17	17	S	Shielded bunker	Outside Shelter	660	
			Shielded bunker	6	277	S	Shielded bunker	Outside Shelter	670	
RF			Shielded bunker	2	2	S	Shielded bunker	Outside Shelter	714.4	
			Shielded bunker	2	2	S	Shielded bunker	Outside Shelter	720	
			Shielded bunker	2	2	S	Shielded bunker	Outside Shelter	726	
			Shielded bunker	2	2	S	Shielded bunker	Outside Shelter	732	
BT	Track		Shielded bunker	2	16	S	Shielded bunker	Outside Shelter	200	
			Shielded bunker	2	16	S	Shielded bunker	Outside Shelter	210	
			Shielded bunker	2	16	S	Shielded bunker	Outside Shelter	220	
			Shielded bunker	2	16	S	Shielded bunker	Outside Shelter	230	
Vacuum	6 rows		Shielded bunker	2	17	S	Shielded bunker	Outside Shelter	85.30	
			Shielded bunker	2	17	S	Shielded bunker	Outside Shelter	86.44	
			Shielded bunker	2	17	S	Shielded bunker	Outside Shelter	87.58	
Magnet			Shielded bunker	1	1	S	Shielded bunker	Outside Shelter	0	
			Shielded bunker	1	1	S	Shielded bunker	Outside Shelter	0	
			Shielded bunker	1	1	S	Shielded bunker	Outside Shelter	0	
			Shielded bunker	1	1	S	Shielded bunker	Outside Shelter	0	
Cooling	2 x 43 U (2 racks)		Shielded bunker	30	30	S	Shielded bunker	Outside Shelter	220	
			Shielded bunker	1	1	S	Shielded bunker	Outside Shelter	220	
			Shielded bunker	1	1	S	Shielded bunker	Outside Shelter	220	
			Shielded bunker	1	1	S	Shielded bunker	Outside Shelter	220	
			Shielded bunker	1	1	S	Shielded bunker	Outside Shelter	220	
			Shielded bunker	1	1	S	Shielded bunker	Outside Shelter	220	
			Shielded bunker	1	1	S	Shielded bunker	Outside Shelter	220	
			Shielded bunker	1	1	S	Shielded bunker	Outside Shelter	220	

14640 mm<sup>2</sup>

Cable list established


# Beam dynamic study with the CLIC module



- 2 additional quads required between the PETS tank and the CLIC module
- Powering, sensitivity to errors and uncertainties studied

See J. Esberg talk “Two-beam module layout and optics”, This WS, Wed 11:30

# Schedule of the installation

Redrawing the line to accommodate the CLIC module	✓	
Cables and crate reservations -> new premises	✓	
Study of the new beam optics	✓	
Drawing and manufacturing of all the elements	✓	
Civil Engineering works	✓	
Shelter installation and equipment on the car park		
Remove the TBTS tanks		2 <sup>nd</sup> June
Storage inside CLEX of all reusable equipments		
Remove the girders and the feet		
Remove the cables trails and pipes		
Replace the PETS tank		
Install the CLIC module and the new girders with their equipments		
Vacuum chambers connections and leak tests		
Re-cabling of all the equipments and tests		
Connection to the shelter and tests		15 <sup>th</sup> Sept.

# Test planned with the CLIC module

- Module program:

*R. Corsini*


- Basic RF behaviour (system conditioning, breakdown cross talks...).
- Basic two-beam acceleration (energy gain, set-up with beam and phasing...).
- Active alignment and stabilization, in presence of radiation and EM noise.
- Alignment and fiducialization - WF monitors vs. BPMs.
- Phase drifts studies (thermal effects, losses...)

# Conclusion

- Despite a CALIFES beam interruption since June, the year 2013 has been pretty busy
  - Growing interest from the beam diagnostics community
  - Consolidation of the existing systems
  - Preparation of the CLIC module installation
- The first half of 2014 will be dedicated to complete the essential experiments with the TBTS (WFM, Nominal accelerating gradient...) and to deliver beam for testing the diagnostics already installed.
- The second half will see the challenging CLIC module installation and commissioning.

# Specific pre-alignment tests foreseen on the CLEX

- Alignment of the girders (when there is no beam)
  - Control of the metrological data (impact of the transport test)
  - Alignment of the girders (with respect to the existing beam)
  - Absolute measurement (comparison between cWPS sensors and AT401 tracker)
- Test of the Degree of freedoms
  - Actuators displacement (5 D.O.F on 1 mm range)
  - Test of the Articulation Point (transfer of 2 D.O.F)
- Validation of equipment performance in radiation and high EMC noise
- Pre-alignment versus beam alignment
  - Follow up of the data
  - Comparison between sensors alignment and beam data



**H. Mainaud Durand**