



www.cern.ch

LHC status & prospects

Dr. Frédéric Bordry

Large Hadron Collider Physics (LHCP) conference

New York - 2nd June 2014

LHCP 2014

The Second Annual Conference
on Large Hadron Collider Physics



Outline


- **LHC recall and Run 1**
- **LS1 status**
- **Run 2 (from LS1 to LS2)** \Rightarrow ***13-14 TeV***
- **LS2 and Run 3** \Rightarrow **300 fb⁻¹**
- **High Luminosity LHC project**
- **LHC Roadmap up 2035** \Rightarrow **3'000 fb⁻¹**
- **Post-LHC machine**

LHC (Large Hadron Collider)

14 TeV proton-proton accelerator-collider built in the LEP tunnel

Lead-Lead (Lead-proton) collisions


- 1983 : First studies for the LHC project
- 1988 : First magnet model (feasibility)
- 1994 : Approval by the CERN Council
- 1996-1999 : Series production industrialisation
- 1998 : Declaration of Public Utility & Start of civil engineering
- 1998-2000 : Placement of the main production contracts
- 2004 : Start of the LHC installation
- 2005-2007 : Magnets Installation in the tunnel
- 2006-2008 : Hardware commissioning
- 2008-2009 : Beam commissioning and repair
- 2010-2035 : Physics exploitation**



June 1994
first full scale prototype dipole

June 2007 First sector cold

ECFA-CERN workshop



1994 project approved by council (1-in-2)



April 2008
 Last dipole down



25 years

Main contracts signed



Decision for Nb-Ti

9T -10 m prototype



2002 String 2



November 2006
 1232 delivered




September 10, 2008
 First beams around

2010-2012 (Run 1): LHC integrated luminosity

CMS Integrated Luminosity, pp

Data included from 2010-03-30 11:21 to 2012-12-16 20:49 UTC



2010: **0.04 fb⁻¹**
 7 TeV CoM
 Commissioning


2011: **6.1 fb⁻¹**
 7 TeV CoM
 ... exploring limits

2012: **23.3 fb⁻¹**
 8 TeV CoM
 ... production

7 TeV and 8 TeV in 2012
Up to 1380 bunches
with $1.5 \cdot 10^{11}$ protons


Long Shutdown 1

LS1 starts as the shutdown to repair the magnet interconnects to allow nominal current in the dipole and lattice quadrupole circuits of the LHC.




wn which, in addition, maintenance, consolidation, s the whole accelerator experimental facilities.

All this in the shadow interconnects.




LS 1 from 16th Feb. 2013 to Dec. 2014



LHC Injectors start-up

LHC-injectors ... getting ready for beams

- PSB & PS : hardware tests started in April
- Cold check-out phases well advanced
- SPS: powering tests will start by end of June



The main 2013-14 LHC consolidations

Opening: 100%

1695 Openings and final reclosures of the interconnections

100 % done

Complete reconstruction of 3000 of these splices

100 % done

Consolidation of the 10170 13kA splices, installing 27 000 shunts

100 % done

Installation of 5000 consolidated electrical insulation systems



100 % done

300 000 electrical resistance measurements

100 % done

10170 orbital welding of stainless steel lines

Closure: 95%



80 % done
18 000 electrical
Quality Assurance tests

80 % done
10170 leak tightness tests

3 quadrupole magnets
to be replaced

15 dipole magnets to be
replaced

100 % done
Installation of 612
pressure relief devices
to bring the total to
1344

90 % done
Consolidation of the
13 kA circuits in the 16
main electrical feed-
boxes

Done

Done




SHUNTS

FINISH

SMACC PROJECT
30/04/2014

Superconducting Magnets And Circuits Consolidation Dashboards




The other activities



Vacuum



UPS-RE82



18 kV & 3.3 kV circuit breakers

Before

After




Cryo plant

LBDS Kickers
 Cavities Vacuum P7-enclosure
 Survey Tests Thermoswitch
 Cooling-stations UPS RF
 Water-Cooled-Cables **Maintenance**
 Cooling-towers Access
 Collimators Consolidation Cryogenic AUG
 Cabling Optical-fibbers Helium Shielding
 Instrumentation Upgrade
 Dump




P7 enclosure



Pumping station




Helium spill test



ACS transport



LS 1: LHC status



13 TeV operation



LS1 status

LHC injectors getting ready for beams

LHC: all signals are green for beam on January 2015

Yogi Berra




LHC schedule: Run2 and LS2

LS2 starting in 2018 (July) => 18 months + 3 months BC



30 fb⁻¹



(Extended) Year End Technical Stop: (E)YETS


Run 2:
Start with 13 TeV
and later decision towards 14 TeV
according to magnet training



Expectations after Long Shutdown 1 (2015)

- Collisions at least at **13 TeV** c.m.
- **25 ns** bunch spacing
Using new injector beam production scheme (BCMS), resulting in brighter beams.

Batch Compression and Merging and splitting (BCMS)



Courtesy of the LIU-PS project team

- $\beta^* \leq 0.5\text{m}$ (was 0.6 m in 2012)
- Other conditions:
 - Similar turn around time
 - Similar machine availability
- Expected maximum luminosity: **$1.6 \times 10^{34} \text{ cm}^{-2} \text{ s}^{-1} \pm 20\%$**
 - Limited by inner triplet heat load limit, due to collisions debris

	Number of bunches	Intensity per bunch	Transverse emittance	Peak luminosity	Pile up	Int. yearly luminosity
25 ns BCMS	2508	1.15×10^{11}	1.9 μm	$1.6 \times 10^{34} \text{ cm}^{-2} \text{ s}^{-1}$	~43	~42 fb^{-1}

Potential performance

	Number of bunches	Ib LHC [1e11]	Collimat or scenario	Emit LHC (SPS) [um]	Peak Lumi [cm ⁻² s ⁻¹]	~Pile-up	Int. Lumi [fb ⁻¹]
25 ns	2760	1.15	S1	3.5 (2.8)	9.2e33	21	24
25 ns low emit	2508	1.15	S4	1.9 (1.4)	1.6e34	43	42
50 ns	1380	1.6	S1	2.3 (1.7)	1.7e34 levelling 0.9e34	76 levelling 40	~45*
50 ns low emit	1260	1.6	S4	1.6 (1.2)	2.2e34	108	...

- 13 TeV
- 1.1 ns bunch length
- 150 days proton physics, HF = 0.2

All numbers approximate

* different operational model – **caveat - unproven**

LS2 : (mid 2018-2019), LHC Injector Upgrades (LIU)


LINAC4 – PS Booster:

- H⁻ injection and increase of PSB injection energy from 50 MeV to 160 MeV, to increase PSB space charge threshold
- New RF cavity system, new main power converters
- Increase of extraction energy from 1.4 GeV to 2 GeV



PS:

- Increase of injection energy from 1.4 GeV to 2 GeV to increase PS space charge threshold
- Transverse resonance compensation
- New RF Longitudinal feedback system
- New RF beam manipulation scheme to increase beam brightness



SPS


- Electron Cloud mitigation – strong feedback system, or coating of the vacuum system
- Impedance reduction, improved feedbacks
- Large-scale modification to the main RF system

These are only the main modifications and this list is far from exhaustive


Project leadership: R. Garoby and M. Meddahi

LHC schedule: LS3 ? and Run 3

LS2 starting in 2018 (July) => 18 months + 3 months BC
 LS3 LHC: starting in 2023 => 30 months + 3 months BC
 Injectors: in 2024 => 13 months + 3 months BC



(Extended) Year End Technical Stop: (E)YETS



LS3 : HL-LHC installation




- c) *Europe's top priority should be the **exploitation of the full potential of the LHC**, including the high-luminosity upgrade of the machine and detectors with a view to collecting **ten times more data than in the initial design, by around 2030**. This upgrade programme will also provide further exciting opportunities for the study of flavour physics and the quark-gluon plasma.*

HL-LHC from a study to a PROJECT

$300 \text{ fb}^{-1} \rightarrow 3000 \text{ fb}^{-1}$

**including LHC injectors upgrade LIU
(Linac 4, Booster 2GeV, PS and SPS upgrade)**

“...exploitation of the full potential of the high-luminosity upgrade of the LHC
=> High Lum



Kick-off meeting: 11th Nov. 2013
(Daresbury)

<http://cern.ch/hilumilhc>





LHC status & prospects
Frédéric Bordry
Large Hadron Collider Physics (LHCP) conference – New York

HiLumi LHC-LARP

Daresbury Laboratory, UK
3rd Joint Annual Meeting
11-15 November 2013

High
Luminosity
LHC Project
Kick-off
Monday 11 Nov.
Special Event



Organizing Committee:

- L. Rossi – CERN, Project Coordinator
- O. Brüning – CERN, Deputy Project Coordinator
- J. Doublet/C. Noels – CERN, Projects Support
- R. Appleby – CERN, Chairperson
- D. Angal-Kalinin – STFC
- S. Boogert – JAI
- G. Burt – CERN
- A. Dexter – CERN
- K. Hock – CERN
- L. Kennedy/S. Waller – STFC
- A. Wolski – CERN

The HiLumi LHC Design Study project

is organizing its 3rd Annual Meeting in collaboration with LARP. The meeting will review the progress in design and R&D of the FP7 HiLumi work packages, as well as other work packages. The main scope will be to provide a solid ground for the preparation of the High Luminosity LHC Conceptual Design Report, a key deliverable of the Design Study, due in the first part of 2014.

To mark the recent approval of the High Luminosity LHC project by the CERN Council as first priority for CERN and Europe, a special event called the HL-LHC Project Kick-off will be organized on the afternoon of Monday 11th November, with the participation of directors of the major stakeholders of the project.


The HiLumi LHC Design Study is included in the High Luminosity LHC project and is partly funded by the European Commission within the Framework Programme 7 Capacities Specific Programme, Grant Agreement 284404.

For more details and free registration:

<http://cern.ch/hilumilhc>



The HL-LHC Project



- New IR-quads Nb_3Sn (inner triplets)
- New 11 T Nb_3Sn (short) dipoles
- Collimation upgrade
- Cryogenics upgrade
- Crab Cavities
- Cold powering
- Machine protection
- ...

Major intervention on more than 1.2 km of the LHC
Project leadership: L. Rossi and O. Brüning

Squeezing the beams: High Field SC Magnets


Quads for the inner triplet

Decision 2012 for low- β quads

Aperture \varnothing 150 mm – 140 T/m

($B_{\text{peak}} \approx 12.3$ T)

(LHC: 8 T, 70 mm)




More focus strength,

β^* as low as 15 cm (55 cm in LHC)

thanks to ATS (Achromatic Telescopic Squeeze) optics



In some scheme even β^ down to 7.5 cm are considered*



- Dipoles 11 T for LS2
- Dipoles for beam recombination/separation capable of 6-8 T with 150-180 mm aperture (LHC: 1.8 T, 70 mm)

LQS of LARP

Courtesy: G. Ambrosio FNAL
and G. Sabbi, LBNL



**3.3 m coils
90 mm aperture**

**LQS01a: 202 T/m at 1.9 K
LQS01b: 222 T/m at 4.6 K
227 T/m at 1.9 K**

**Target:
200 T/m gradient at 1.9 K**


**LQS02: 198 T/m at 4.6 K 150 A/s
208 T/m at 1.9 K 150 A/s
limited by one coil**

**LQS03: 208 T/m at 4.6 K
210 T/m at 1.9 K
1st quench: 86% s.s. limit**



LS2 : collimators and 11T Dipole

- LS2 2017-18: Point-~~X~~,7 & IR-2
- LS3 2020+: IR1,5 as part of HL-LHC




LS2: 12 coldmass + 2 spares = 14 CM
 LS3: 8 coldmass + 2 spares = 10 CM
 Total 24 CM



LS2: 24 coldmass + 4 spares = 28 CM
 LS3: 16 coldmass + 4 spares = 20 CM
 Total 48 CM

Nb₃Sn 11T Dipole R&D

Single aperture model




Twin aperture model




Crab Cavities, Increase “Head on”

Aim: reduce the effect of the crossing angle




New crossing strategy under study to soften the pile-up density: some new schemas have interesting potential as “crab-kissing”, to be discussed with all experiments



$\alpha_{||1} = \alpha_{||} : (y-z)$ normalized angle for B1



$\alpha_{||2} = \alpha_{||} : (y-z)$ normalized angle for B2




- 3 proto types available
- Cavity tests are on-going
- Test with beam in SPS foreseen in 2015-2016
- Beam test in LHC foreseen in 2017




Setting up International collaboration

Baseline layout of HL-LHC IR region




with national laboratories **but also involving industrial firms**

Luminosity Levelling, a key to success



- High peak luminosity
- Minimize pile-up in experiments and provide “constant” luminosity

- Obtain about 3 - 4 $\text{fb}^{-1}/\text{day}$ (40% stable beams)
- About 250 to 300 $\text{fb}^{-1}/\text{year}$



Baseline parameters of HL for reaching 250 -300 fb⁻¹/year

25 ns is the option

However:

50 ns should be kept as alive and possible because we DO NOT have enough experience on the actual limit (*e-clouds, I_{beam}*)

Continuous global optimisation with LIU

	25 ns	50 ns
# Bunches	2808	1404
p/bunch [10 ¹¹]	2.0 (1.01 A)	3.3 (0.83 A)
ϵ_L [eV.s]	2.5	2.5
σ_z [cm]	7.5	7.5
$\sigma_{\delta p/p}$ [10 ⁻³]	0.1	0.1
$\gamma\epsilon_{x,y}$ [μm]	2.5	3.0
β^* [cm] (baseline)	15	15
X-angle [μrad]	590 (12.5 σ)	590 (11.4 σ)
Loss factor	0.30	0.33
Peak lumi [10 ³⁴]	6.0	7.4
Virtual lumi [10 ³⁴]	20.0	22.7
T _{leveling} [h] @ 5E34	7.8	6.8
#Pile up @5E34	123	247


LHC roadmap: schedule beyond LS1

LS2 starting in 2018 (July) => 18 months + 3 months BC


LS3 LHC: starting in 2023 => 30 months + 3 months BC

Injectors: in 2024 => 13 months + 3 months BC


(Extended) Year End Technical Stop: (E)YETS



30 fb⁻¹




PHASE 1



300 fb⁻¹

PHASE 2




3'000 fb⁻¹



“to propose an ambitious **post-LHC accelerator project at CERN** by the time of the next Strategy update”

CERN should undertake design studies for accelerator projects in a global context, with emphasis on proton-proton and electron-positron high-energy frontier machines. These design studies should be coupled to a vigorous accelerator R&D programme, including **high-field magnets** and **high-gradient accelerating structures**, in collaboration with national institutes, laboratories and universities worldwide.

HFM - FCC





HGA - CLIC




Malta Workshop: HE-LHC @ 33 TeV c.o.m.


14-16 October 2010



Material	N. turns	Coil fraction	Peak field	J _{overall} (A/mm ²)
Nb-Ti	41	27%	8	380
Nb ₃ Sn	55	37%	12	500



Dipole Field for Hadron Collider



Magnet design (20 T): very challenging but not impossible.

300 mm inter-beam
Multiple powering in the same magnet (and more sectioning for energy)

Work for 4 years to assess HTS for 2X20T to open the way to 16.5 T/beam .

Otherwise limit field to 15.5 T for 2x13 TeV

Higher INJ energy is desirable (2xSPS)

beam screen at 60 K.
ramping time.


handling 2x10³⁴ appears reasonable.
handling for INJ & beam dump:
ice more room for LHC kickers.

"High Energy LHC"

**HE-LHC :33 TeV
with 20T magnets**

First studies on a new 80 km tunnel in the Geneva area


- **42 TeV with 8.3 T using present LHC dipoles**
- **80 TeV with 16 T based on Nb₃Sn dipoles**
- **100 TeV with 20 T based on HTS dipoles**



80-100 km tunnel infrastructure in Geneva area – design driven by pp-collider requirements (FCC-hh) with possibility of e⁺-e⁻ (FCC-ee) and p-e (FCC-he)

**FCC (Future Circular Colliders)
CDR and cost review
for the next ESU (2018-2019)
(including injectors)**

**16 T ⇒ 100 TeV in 100 km
20 T ⇒ 100 TeV in 80 km**



Future Circular Collider Study Kick-off Meeting

12-15 February 2014,
University of Geneva,
Switzerland

LOCAL ORGANIZING COMMITTEE

University of Geneva

C. Blanchard, A. Blondel,
C. Doglioni, G. Iacobucci,
M. Koratzinos


CERN

M. Benedikt, E. Delucinge,
J. Gutleber, D. Hudson,
C. Potter, F. Zimmermann

SCIENTIFIC ORGANIZING COMMITTEE

FCC Coordination Group

A. Ball, M. Benedikt, A. Blondel,
F. Bordry, L. Bottura, O. Brüning,
P. Collier, J. Ellis, F. Gianotti,
B. Goddard, P. Janot, E. Jensen,
J. M. Jimenez, M. Klein, P. Lebrun,
M. Mangano, D. Schulte,
F. Sonnemann, L. Tavian,
J. Wenninger, F. Zimmermann



<http://indico.cern.ch/e/fcc-kickoff>



LHC status & prospects
Frédéric Bordry
Large Hadron Collider Physics (LHCP) conference –



340 International Participants

Kick-off Meeting of the Future Circular Colliders Design Study

12 - 15 February 2014, University of Geneva / Switzerland



HL-LHC (3000 fb^{-1})

LHC 13-14 TeV (300 fb^{-1})

LHC 7-8 TeV (30 fb^{-1})



www.cern.ch