

WP8 – Improvement and equipment of irradiation beam lines

Giovanni Mazzitelli &
LNF, INFN, Italy

Michael Moll
CERN, PH, Switzerland

Contents:

- **WP8 – Task overview**
- **WP8 – Status of tasks**
- **Summary**
- **Annex: Table on status of milestones and deliverables**

- WP8 – tasks and task leaders

8.1. Coordination and Communication	Co-leader: <u>Giovanni Mazzitelli</u> (INFN LNF) <u>Michael Moll</u> (CERN)	(gm) (mm)
8.2. Test beams infrastructure at CERN and Frascati		
8.2.1. <i>CERN</i>	Leader: <u>Ilias Efthymiopoulos</u> (CERN)	(gm)
8.2.2. <i>Frascati</i>	Leader: <u>Giovanni Mazitelli</u> (INFN-LNF)	(gm)
8.3. Upgrade of PS proton and neutron irradiation facilities at CERN	Leader: <u>Michael Moll</u> (CERN)	(mm)
8.3.1. <i>Improvement of irradiation facilities and evaluation of upgrade proposals</i>		
8.3.2. <i>Common infrastructure for the facilities</i>		
8.4. Qualification of components and common database	Leader: <u>Simon Canfer</u> (STFC)	(mm)
8.4.1. <i>Review existing data and experience from LHC, define test program</i>		
8.4.2. <i>Define test procedures and conduct tests on selected components</i>		
8.4.3. <i>Set-up and publish a WEB database compiling the information above</i>		
8.5. General infrastructure for test beam and irradiation lines		
8.5.1. <i>Commission and operate beam tracking telescope</i>	Leader: <u>Hanno Perry, Igor Rubinsky</u> (DESY)	(gm)
8.5.2. <i>TASD and MIND</i>	Leader: <u>Paul Soler</u> (STFC)	(gm)
8.5.3. <i>GIF++ user infrastructure</i>	Leader: <u>Davide Boscherini</u> (INFN Bologna)	(mm)
8.6. Coordination of combined beam tests and common DAQ		
8.6.1. <i>Common test beam experiments at CERN and DESY</i>	Leader: <u>Ties Behnke</u> (DESY)	(mm)
8.6.2. <i>Common DAQ</i>	Leader: <u>David Cussans</u> (Uni Bristol)	(WP9)


Test beams infrastructure at CERN and Frascati

Task 8.2

8.2.1 CERN


8.2.2 Frascati

- Design of a low-energy (1-9 GeV/c) muon, pion and electron beam in the H8 beamline, for neutrino detector R&D
 - Design of the **optics** for the very low energy muon, pion and electron beam.
 - **Maximize** the ratio at the experiment for the **muon** beam.
 - **Maximize** the **acceptance** of the beamline.
 - **Minimize** the **background** (muon beam halo + decay) at the experiment.
 - Adapt to the **layout constraints** in the building; use of the large MORPURGO magnet.




Four-bends layout

- ▶ similar to the one used for the ATLAS&CMS calorimeters in the past
- ▶ compatible with detectors installed inside the large Morpurgo magnet
- ▶ suffers from large background from the direct secondary beam





Three-bends layout

- ▶ reduces the background from the direct secondary beam – essential for ν -detectors ?
- ▶ less straightforward to install detectors inside the Morpurgo magnet




- Selecting the “tertiary” muons by setting the first and second half of the VLE spectrometer at cascading energies.




- **Status and future work**

- ✓ specifications for the beamline are fixed (see milestone report)
- ✓ Target FLUKA simulation
- ✓ beamline design for the 2 chosen layouts
- ✓ beamline simulation with FLUKA
- ✓ produce table with expected experiment
- ✓ produce final report by end



the





- **Status of Milestones & Deliverables**

- ✓ MS27 [m12] “Specification of beamline” **done**
- ✓ D8.3 [m26] “Design of beamline finished” **delayed**
 - expected in June 2013 (3 months delay)
 - reason for delay: late hiring of student performing the calculations for the study

• Upgrade of the Beam Test Facility:

- equip the BTF with a **remote trolley**
- equip the BTF with a **GEM** tracking chambers (res<100 μm)
- use the **LYSO** calorimeter to measure the beam energy spread
- improve multi purpose **DAQ**






disposable area	600x600 mm
min height	915 mm
max height	1250 mm
horiz. excursion	1000 mm
max load	200 Kg
accuracy	< 1 mm ²





AIDA-NOTE-2012-003


- ✓ Up to now, the DAQ system is fully operative with a standalone software now working at 25Hz bunch rate in !CHAOS MEMCACHED live data storage
- ✓ A MEDIPIX detector (Timepix) has been tested to increase transverse beam detection quality and qualify the BTF calorimeters over a wide range of multiplicity.
- ✓ Preliminary study for the porting of the BTF DAQ and the main subsystem of the BTF device in !CHAOS environments has been started.



- ✓ The prototype of the TPC GEM tracker has been replaced by a fully operative system completed of all service elements (gas system, electronics, etc).





spatial resolution of about 80 μm



Measurement @BTF of positron beam splitting through a crystal

- ➔ All the functionality of the GEM system (CANBUS via KVASER in HVGEM) runs temporary on virtualized environment and we are still developing of CANBUS over Ethernet software.
- ➔ Some preliminary test to study the relation among HVGEM currents and particle multiplicity has been started to obtain an independent beam current monitor over a wide range.

- ✓ **Analysis** of the data collected during the test beam has been performed. A reasonable **agreement between data and Monte Carlo** has been obtained.



▶ **Beam spread at 500MeV fixed at 1%**

▶ Only one point at this energy, BS can't be extracted

▶ **Measured beam spread:**

▶ 4.8% at 100MeV

▶ 2.7% at 200MeV

▶ 2.1% at 300MeV


▶ 1.4% at 400MeV

▶ **LYSO matrix resolution**

$$\frac{\sigma_E}{E} = \frac{1.1\%}{\sqrt{E(\text{GeV})}} \oplus \frac{0.4\%}{E(\text{GeV})} \oplus 1.2\%$$

- ✓ 9 LYSO crystals have been readout with 36 (4 per crystal) and tested at the BTF line with energy range from from 100 up to 500 MeV

- ✓ also in this configuration, with a **constant term of about 2%**





- **Status and future work**

- ✓ **remote trolley** done (see AIDA-NOTE-2012-003)
- ✓ **GEM tracker** with a resolution less than 100 μm **is completed**: the prototype of the TPC GEM tracker has been replaced by a fully operative system completed of all service elements
- ✓ **LYSO calorimeter beam energy spread measurements is completed**: LYSO resolution data normalized by energy beam spread are fitting optimally the Monte Carlo data; UV optimized SiPM has been tested showing a reduction of SNR reproducing a $\sim 2\%$ of energy resolution for the beam line as previously measured.
- ➔ multi purpose **DAQ system is in progress**: neutron detectors, environmental detectors, and beam diagnostic detectors has been implemented; GEM tracker system in under integration in the BTF controls.


- **Status of Milestones & Deliverables**

- ✓ D8.8 [m48] “All equipment ready” is on schedule

Upgrade of PS proton and neutron irradiation facilities at CERN

Task 8.3

- 8.3.1. Improvement of existing irradiation facilities
and evaluation of upgrade proposals
- 8.3.2. Common infrastructure for the facilities




• Proton irradiations

- Since 1992 (until 2012)
- Direct exposure to 24 GeV/c protons (IRRAD1, IRRAD3, IRRAD5)
- Low intensity radiation field of backscattered particles (SEU and Dosimeter testing) (IRRAD6)


• Neutron (mixed field) irradiations


- Mixed field produced in cavity after carbon (50cm) iron (30cm) lead (5cm) 'target' (IRRAD2)

- **2008-2010: Working Group on Irradiation Facilities at CERN**
 - See: <http://www.cern.ch/irradiation-facilities/>
- **2011: Beginning of AIDA project**
 - AIDA objective: Design study of the facilities plus new infrastructure for old/new facility
- **2012: CERN management agrees on facilities upgrade**
 - AIDA was very helpful in achieving the green light for the project
- **November 2012: First technical meeting & END of DIRAC experiment**
 - CERN-EN is charged and funded to design and construct the irradiation beam line in the framework of the EA renovation plan during LS1
 - R2E project (LHC machine): Mixed-field facility & infrastructure design
 - **CERN-PH & AIDA: Proton facility & infrastructure design**
- **2013: Dismantling (DIRAC & old IRRAD facilities); start of construction**
- **2014: Construction and commissioning of new facilities**
 - First irradiation experiments toward end of the year
 - R2E project: Cern High-energy Accelerator Mixed-field facility (**CHARM**)
 - CERN-PH & AIDA: proton **IRRAD**iation facility (IRRAD)
- **END of 2014: First irradiations for users**



Building 157









AIDA Proton Beam Parameters

□ Beam Dimensions


- Several optic variants possible on T8
- Beam spot from $5 \times 5 \text{ mm}^2$ to $20 \times 20 \text{ mm}^2$ (FWHM)
- Standard size: $15 \times 15 \text{ mm}^2$ (FWHM)


□ Beam Intensity

- p^+ are delivered in “spills” of $\sim 5 \times 10^{11} p$
- Number of spills/frequency depends on CPS
- Typical CPS after LS1: 30s
- Typical figures (High Intensity): 3 spills per CPS
 - $\sim 1 \times 10^{16} p \text{ cm}^{-2} 5 \text{ days}^{-1}$ ($15 \times 15 \text{ mm}^2$ FWHM)
 - $\sim 4x$ more than the old facilities
- Design figures (maximum): 6 spills per CPS
 - $\sim 1 \times 10^{17} p \text{ cm}^{-2} 4 \text{ days}^{-1}$ ($5 \times 5 \text{ mm}^2$ FWHM)




L. Gagnon, preliminary calculations (EDMS 1270807)
Here dimensions are mm (RMS)







IRRAD Shuttle System assembled and READY for installation!




- Irradiation tables and boxes
 - Sheffield, Liverpool, Birmingham, CERN
 - Irradiation tables produced and tested
 - at CERN proton irradiation facility (24 GeV/c protons)
 - at Birmingham Cyclotron 26 MeV p (up to 40 MeV)
 - 3 cold boxes produced, 2 further under assembly
 - Recirculate cold air (forced convection)
 - LN2 cooling under study





Scanning system + Thermal Chamber

- Fully portable plug & play scanning system
- Thermal chamber using similar principle to PS irradiation facility CERN (IRRAD 5)
 - -22°C minimum operating temp
 - ~ 480W heat load removal (@ -20°C).
- Readout and control system using COTS FPGA based technology
- Networked readout allowing remote access for data analysis and real-time sample performance



- Fluence monitoring system using microwave absorption
 - Vilnius University, CERN, Louvain
 - Monitoring based on carrier lifetime measurement in silicon by microwave absorption probed photoconductivity transients



- System designed and produced in Vilnius
 - System tested at CERN in November 2012
- System upgrade and improvements in 2013 (VUTEG-5)
 - temperature stabilization, possibility to scan sample, T & RH measurements
 - System to be transferred to CERN to be tested during facility commissioning



- **Decommissioning of the old facilities in the East Area**

- **Proton Facility Design**

- Finalization and validation of the area/infrastructure layout
- Study and definition of the operational model and related aspects

AIDA D8.4

- **Proton Facility Construction & Infrastructure installation**

- **Shuttle system** (ready to be installed)
- **Remote-controlled Irradiation tables**
 - Design and construction of prototype done and operation tested
 - Production & assembly of 9 tables; production & assembly of front-end control electronics
 - Cold boxes operational
- **Sample management, databases and tracing**
- **Beam Instrumentation & DAQ**
- **Development of a multiple-devices web application for users & CCC**
- **Radiation Monitoring (Vilnius)**
 - Tested at CERN, Under upgrade in Vilnius now, Instrument to be transferred back to CERN

AIDA MS31

AIDA MS35

AIDA MS35

- **Proton Facility commissioning**

- **Commissioning starting in July 2014**
- **First users in end of 2014**

AIDA D8.10


Qualification of components and common database

Task 8.4

- 8.4.1. Review existing data and experience from LHC, define test program
- 8.4.2. Define test procedures and conduct tests on selected components
- 8.4.3. Set-up and publish a WEB database compiling the information above

- Participants: INFN (MI, PG), STFC-RAL, UNIGE, ETHZ
 - Leader: Simon Canfer, STFC
- Sub-task:
 - 1. **Review existing data and experience from LHC, define test programme**
 - **Achieved**; See AIDA-D8.1. document on CDS
 - 2. **Define test procedures and conduct tests on selected materials & components**
 - List of tests to be performed within AIDA WP8.4. given in AIDA-MS30
 - *Material tested: inorganic scintillating crystals, electronics, APS, epoxies.(examples: next slides)*
 - 3. **Set-up and publish a WEB database compiling the information above**
 - Enquired with potential user community asking for input to database structure (done)
 - Data fields for the database have been defined within WP 8.4. participants
 - Database online from this AIDA meeting: <http://tinyurl.com/aidaimhotep>

IMHOTEP




IMHOTEP
Properties of Materials under Irradiation

AIDA HOME **IMHOTEP** FAQ ABOUT US CONTACT


AIDA >> Imhotep

Welcome to Imhotep

This database contains summary data from tests to quantify materials and components for LHC detector upgrades.
If you would like to submit data to IMHOTEP, you can do so [here](#)



- Online (<http://tinyurl.com/aidaimhotep>)
 - Ready to take data
 - To be announced to community
 - Possibility to upload pdf
 - Robust implementation
4 servers (backup, firewalled)
 - STFC will maintain database beyond AIDA
 - Today: 17 entries



IMHOTEP
Properties of Materials under Irradiation

AIDA HOME | **IMHOTEP** | FAQ | ABOUT US | CONTACT

AIDA >> Imhotep

Welcome to Imhotep

This database contains summary data from tests to quantify materials and components for LHC detector upgrades.
If you would like to submit data to IMHOTEP, you can do so [here](#)

Scope of Search

Material or Component

Particle Type

Radiation Parameters
Please choose either
Particle Energy/Fluence
OR
Dose

Particle Energy (MeV)	More than	<input type="text"/>
	Less than	<input type="text"/>
and Fluence (cm²)	More than	<input type="text"/>
	Less than	<input type="text"/>

OR

Dose (MGy)	More than	<input type="text"/>
	Less than	<input type="text"/>

Irradiation Temperature (K)

	More than	<input type="text"/>
	Less than	<input type="text"/>

Related Experiment

Record contains these words:

Published After (inclusive)

SEARCH

IMH000
Build 28/02/14 10:52

IMHOTEP is part of the AIDA project and is provided by STFC.
About IMHOTEP | About AIDA | Disclaimer | © STFC 2013 - 2017
AIDA is co-funded by the European Commission within Framework Programme 7 Capacities, Grant Agreement 262025


Link to data entry page

Search options

- Work on electronic components (Milano, Perugia)
 - Radiation damage test of commercial MAPS sensors (Perugia, M.Menichelli)

MT0V011 CMOS Imager from Aptima Imaging



- very high pixel granularity (> 300000)
- thin epitaxial layer ($\sim 2-5 \mu\text{m}$)
- 130 nm technology, - small pixel size ($< 6 \mu\text{m}$)
- Proton irradiation (24 MeV)
 - imager after $6 \cdot 10^{13} \text{ p/cm}^2$
- Characterization with x-ray source and 500 MeV electron beam
- Detection efficiency in damaged region 0.24% w.r.t. undamaged region



- Next tests after 24 MeV proton irradiation:

Sensori	RAPS03	MT0V011	MT9T012	MT9T013	MT9T031
Pixel size [μm]	10x10	5.6x5.6	2.2x2.2	1.75x1.75	3.2x3.2
substrate	Non-epi	Epi (4 μm)	Epi (2.5 μm)	Epi (2.5 μm)	Epi (4 μm)
Technology	180 nm	130 nm	130 nm	130 nm	130 nm

- Work on radiation damage in epoxy resins (STFC, Steve Robertson)
 - Application example: ATLAS stave for tracker upgrade
 - Data exists on rigid, rad-hard epoxies which tend to be highly crosslinked, high modulus and brittle.
 - Focus on characterizing the rad-hardness of more flexible epoxies and silicones (Two resins tested: 5519, 5555)
 - Irradiation: 26 MeV protons (Birmingham facility)



- Conclusions:
 - FTIR can show some of the damage processes occurring in the resin.
 - DMA (Dynamic Mechanical Analyses) shows increasing Tg with radiation dose.
 - Next step:
 - Irradiated further samples for intermediate data points
 - Develop a flexible resin with lower cure temperature
- Tg – Glass Transition Temperature

General infrastructure for test beam and irradiation lines

Task 8.5



8.5.1. Commission and operate beam tracking telescope

8.5.2. *TASD and MIND*

8.5.3. *GIF++ user infrastructure*




Top-bottom view on the EUDET telescope sensor fixtures with a DUT box mounted in between. (Photo by CLICpix group at DESY testbeam)



- in January 2013 - March 2014
 - 49 Calendar weeks
 - 123 User weeks in total
 - 7100 Testbeam hours
 - 400 Users in total
- DESY-II primary beam at 6.3 GeV
 - high availability time (>99%)
 - secondary e^+/e^- at 1-6 GeV
 - rates 0.1-10 kHz
- beamtests in 1 Tesla magnet
 - new telescope mechanics
 - new DUT cooling system
 - over 20 weeks in B-field

- ✓ D8.5 – [m40] “**Installation of tracking telescope**” is partially delayed: final integration tests have been planned at CERN in **July PS** test beam, and final assembly at **SPS H6B in October**. (see development of telescope in WP9.3)
- ✓ MS36 – [m44] “**Commissioning of tracking telescope**” consequently partially delayed


Totally Active Scintillating Detector (TASD)



- **Stopping properties** of pions and muons up to 200 MeV/c (MICE EMR);
- **Electron and muon charge separation** inside a magnetic field, in particular electron charge ID in electron neutrino interaction for the platinum channel at a neutrino factory: 0.5 to 5 GeV/c.

MS28


Magnetised Iron Neutrino Detector (MIND)






- **Muon charge identification**, for wrong sign muon signature of a neutrino oscillation event: golden channel at a NF: requires correct sign background rejection of 1 in 10⁴: test beam 0.8 to 5 GeV/c;
- **Hadronic shower reconstruction** for identification of charged current neutrino interactions and rejection of neutral current n.i.: test beam protons/pions 0.5 to 9 GeV/c



AIDA TASD integration & delivery



RAL MICE HALL: 27th September 2013





- ▶ Red: e^+ beam;
- ▶ Blue: π^+ beam;
- ▶ Green: e^- beam;
- ▶ Black: π^- beam.




Online operation at RAL: October 2013

Rate_5



Integrated crosstalk rate for a given plane

- crosstalk** is under study, preliminary analysis show
- at **MIP** level crosstalk < **0.5 %**
 - at **high energy** deposition **~ 100%**



- Detector module **designed**
- MIND plastic **scintillator** bars delivered from INR of Russia
- Scintillator bar **connector** designed
- Plastic **scintillators tested** with cosmics
- **Light yield** study (slabs with chemical reflector) done.
- **Timing** characteristics studied
- **Light yield** for the different **WLS** fibers studied
- **Photosensor** chosen and test done
- **Readout/electronics chosen** and Easiroc schematic and planned charge+hit measurements

- ▶ **TASD successfully tested online:**
 - ▶ Assembled at the University of Geneva;
 - ▶ Installed on MICE beamline at RAL September 2013;
 - ▶ Detector performance under evaluation;
 - ▶ Data analysis ongoing.
- ▶ **MIND construction underway:**
 - ▶ Several component choices made (plastic scintillator, WLS fiber, optical glue);
 - ▶ Photosensor characterization ongoing for final choice in May;
 - ▶ Good progress on manufacturing of scintillator bars by INR;
 - ▶ Electronics by UniGe;
 - ▶ Steel and magnetisation in collaboration with CERN.
- ▶ **Outlook for TASD and MIND:**
 - ▶ Several projects plan such detectors;
 - ▶ MIND prototype foreseen for WA105 at CENF.




• Conclusion and actual status


- ✓ Design of MIND and T ASD done
- ✓ T ASD detector is under test @ RAL – MICE test beam line
- ✓ MIND detector is under construction;

• Milestone/deliverable status:


- ✓ MS28 [m20] “T ASD & MIND design” **done**
- ✓ MS33 [m36] “T ASD & MIND installation”
T ASD done;
MIND delayed of 10 months
- ✓ D8.11 [m48] “neutrino telescope test & results”
 on schedule (need for appropriate
 beam line for testing the detectors)




- **GIF++ Facility:** CERN is constructing the facility with strong CERN-EN & PH teams involved!
- **Location:** H4 line in SPS North Area; 100GeV muons, 10x10cm²
- **Size:** 100 m² Irradiation bunker
- **Source:** ¹³⁷Cs, 14 TBq (~260 μGy/s at 1m; 30 times present GIF) 662 KeV, $\tau_{1/2}=30y$
- **Irradiator & Filter :** 2 independent irradiation fields ($\pm 37^\circ$). Attenuators (up to 50.000)
- **Wide range of available gases**



- Irradiator can be moved by 1.5 m





Next : gas pipes, cable trays, cables, false floor, painting....

- **Commissioning: Sept-Oct.2014**



- **Leader:** Davide Boscherini (INFN Bologna)
- **Participants:** *Bulgaria:* INRNE; *Greece:* NTUA, AUTH, Demokritos, NCUA; *Israel:* Weizmann, Technion, Tel-Aviv; *Italy:* INFN-Bari, -Bologna, -LNF, -Rome2
- **Deliverable:** Infrastructure for the GIF++ Facility



- **Beam tracker**

- Detectors (TGCs) ready and tested in beam tests



Status: Chambers ready for installation with temporary electronics


beam-position detectors





• Cosmic tracker (top)


- **Trigger and high time resolution.**
 - 4 independent detectors area 1.0 x 0.5m²
- **Fine tracking.**
 - One or 2 RPC 30x30 cm² with 1 cm strips in both direction ; strips: 64 (128)



View from bottom

• Cosmic tracker (ground)

- **Trigger and high time resolution:**
 - A 1x0.5m² chamber as for the top tracker. Strips: 16 + 32 = 48
- **Fine tracking:** 1 chamber 30x30 cm² as in the previous point (# strips: 64)
- **Underground detector**
 - Double layer chambers: total size 2.8 x 2.4 (=2x1.2) m² (two chambers; bi-dimensional read out with 40 mm strips, # strips: 224)



Status: Chambers expected for mid May (underground) resp. July (top/bottom)


Radiation sensors



RADMON PCB BASED WITH 2 RadFETS DETECTORS
1xLAAS 1600 - till 10 Gy
1xREM 250 - till 2000 Gy




FOUR DETECTORS CAN BE CONNECTED TO ONE SPLITTER BY SHORT CABLES
THE SPLITTER IS CONNECTED TO THE DETECTOR NODE BY A LONG CABLE



MAIN CONTROLLER


Ready for installation

In preparation – Radmons after the calibration test.




PRELIMINARY CABLING PLAN

TEST RESULTS FOR TWO LAAS 1600 RADFETS



TEST RESULTS FOR TWO REM 250 RadFETS



Status: Ready to be installed

Beam tracker:

- chambers ready though with a temporary electronics until 2015

Cosmic tracker:

- chambers under construction
- expected delivery at CERN in May (underground chambers) and July (top/bottom trackers)

DCS:

- test setup in place (at old GIF) with minimal hardware infrastructure
- need detailed specifications from detectors
- plan to provide a basic version of the system by September

DAQ:

- positive results from the test-bench setup at Tel Aviv University
- TGC are already working with the proposed DAQ scheme
- need to integrate RPC
- test with real detectors planned in next June

Radiation sensors:

- dosimeters ready to be installed in the bunker area

Environmental sensors:

- sensor procurement in progress
- mechanical containers are being designed

Final remarks (Plamen Iaydjiev)

Installation of user infrastructure can start in next August

The items covered by the WP-8.5.3 are generally on schedule: the user infrastructure is expected to be **installed until end of September** with basic functionalities

Further commissioning of the infrastructure has to be expected in the weeks following the installation completion

Coordination of combined beam tests and common DAQ

Task 8.6

- 8.6.1. Common test beam experiments at CERN and DESY
- 8.6.2. Common DAQ

- **EDMS (Engineering Data Management System)**
 - Development driven by DESY with aim to provide functionality as:
 - Document and data management with version & access control, life cycle support.
 - Design and viewing features; Collaborative work including collision analyses
 - Documents: Regular, Engineering, Management
 - Two systems available: CERN EDMS and DESY EDMS with different WBS
 - EDMS for the AIDA project combining both is ready (MS34)
 - Access: <http://flc-edms.desy.de/> (see also link on AIDA web site);
 - Regularly maintained by DESY
 - Most of the web pages are created dynamically from the info in the EDMS systems, via web interfaces; Collection of documents is an ongoing process
 - Outlook
 - Support for the EDMS will continue; Consolidation of existing design docs
 - Develop processes: releasing/reviewing, change control, collaborative design
 - Extend to support further PM activities: scheduling; cost estimation; risk analysis,...

- EDMS (Engineering Data Management System)
 - <http://flc-edms.desy.de/>



The screenshot shows the website's navigation bar with links for Home, Facilities, Movable Infrastructure, LC Infrastructure, and Contact. The main header features the AIDA logo and the title "Test Beam Documentation". A featured article titled "FLC EDMS Field Cage" includes a photograph of a large, cylindrical metal component with orange and silver bands. To the right of the image, there is a "Mission" section explaining the website's goal to ensure complete documentation and access to public information. Below that is a "Links" section with hyperlinks to CERN EDMS, DESY EDMS, AIDA at CERN, and DESY. At the bottom right, there is a "Feedback" section.

Home Facilities ▼ Movable Infrastructure ▼ LC Infrastructure ▼ Contact

 **AIDA** Test Beam Documentation

FLC EDMS

Field Cage



Mission

The goal of this website is to ensure a complete documentation of the infrastructures developed within the AIDA project and an up-to-date access to public information stored in the DESY and CERN EDMS.

Links

- [CERN EDMS](#)
- [DESY EDMS](#)
- [AIDA at CERN](#)
- [DESY](#)

Feedback

The development of complex detector systems requires large test experiments, which typically are performed at test beam facilities either at CERN or at DESY. These experiments are intrinsically complex and include participants from several institutes and many pieces of

Task 8.1: Coordination and Communication

- ▶ **WP8.1.** Most of the tasks within WP8 achieved a very good progress within last year.
- ▶ **WP8.2** The tasks related to the test beam infrastructure at Frascati **are well on track and the anticipated milestones and deliverables** are at no risk. The CERN **deliverable D8.2.** on low energy beam line design study has been **achieved** concluding this part of task 8.2.
- ▶ **WP8.3 and 8.5** Excellent **progress was achieved in the construction of the irradiation facilities** at CERN, namely the Proton & Mixed field irradiation facility in the East Area and the **GIF++** facility in the North Area. Both projects are now under construction at CERN!
- ▶ **WP8.4** The irradiation testing plan for materials and components has been established (MS30) and the database on irradiated materials and components is online since this week.
- ▶ **WP8.5** T ASD installed at RAL test beam line and MIND prototype under construction with delay of 10 months with respect to schedule.
- ▶ **WP8.6** AIDA EDMS system at DESY existing. **EDMS milestone MS34 reached.** Test beam support given throughout 2013 at DESY. DAQ is part of WP9

MS27	Specification for beam line fixed	CERN (1)	m12 <u>Jan 2012</u>	Final specification for the design study in task 8.2. (Task 8.2.1)	o.k. [m14]
MS28	Design of T ASD and MIND	STFC (31)	m20 <u>Sept.2012</u>	Design for deliverable D8.11 (Task 8.5.2)	o.k.
MS29	Design of GIF++ infrastructure	INFN (18)	m20 <u>Sept.2012</u>	Detailed design ready for the cosmic ray tracker, the radiation measurement facility and the DCS (Task 8.5.3)	o.k.
MS30	Definition of test procedure and specification	STFC (31)	m20 <u>Sept.2012</u>	Common agreement of how tests for materials will be conducted and which components to test (Task 8.4)	o.k.
MS31	Installation of new equipment	CERN (1)	m26 <u>March 2013</u>	Movable irradiation tables operational (Task 8.3.2) CERN, UK	o.k.
MS32	First test results on selected components	STFC (31)	m26 <u>March 2013</u>	Intermediate result with respect to D8.7 (Task 8.4)	o.k.
MS33	Installation of T ASD and MIND	STFC (31)	m36 <u>Jan.2014</u>	Installation at CERN for deliverable D8.11 completed (Task 8.5.2)	o.k. T ASD: 2/14 MIND:12/14
MS34	Test beam, EDMS and DAQ commissioning	DESY (9)	m36 <u>Jan.2014</u>	Intermediate stage for deliverable D8.8 (Task 8.6. 1&2)	o.k., EDMS delay DAQ
MS35	Installation of infrastructure	(34)	m37 <u>Feb. 2014</u>	Cold boxes and Fluence monitoring system operational (Task 8.3.2) CERN, UK, VU	Need to wait for facility to exist
MS36	Commissioning of tracking telescope	DESY (9)	m44 <u>Sept.2014</u>	Start of operation of telescope delivered in D8.5 (Task 8.5.1)	

D8.1	Experience at LHC and definition of test programme: Based on the experience and expectations for the LHC test programme is defined and described in a document.	[m12] <u>Jan. 2012</u>	Task 8.4	o.k. [m18]
D8.2	Publication of specification documents for the DAQ and for the central documentation facilities: Description of common infrastructures and interfaces for the linear collider test beams.	[m20] <u>Sept. 2012</u>	Task 8.6. 1&2	o.k. [m30]
D8.3	Design study on low energy beamline: Design and implementation study on a low energy beam to the range of 1 (or possibly less) to 10 GeV	[m26] <u>March 2013</u>	Task 8.2.1 CERN	o.k. [m33]
D8.4	Upgrade scenarios for irradiation lines: Design study on new or upgraded irradiation facilities at CERN based on slow extracted proton beams. Containing a proton and – if feasible – a mixed field irradiation facility.	[m 37] <u>Feb. 2014</u>	Task 8.3.1 CERN	...writing <u>report</u>
D8.5	Installation of tracking telescope: The tracking telescope is installed in the beam line and operational.	[month 40] <u>May 2014</u>	Task 8.5.1	
D8.6	Detector and detector control system operational: Cosmic ray tracker including front end electronics, power and gas systems. Detector for radiation measurement. Detector Control System monitoring the tracker working and the environment parameters.	[month 44] <u>Sept. 2014</u>	Task 8.5.3	
D8.7	Populated data base of components qualification: The materials and components database is online and populated with data.	[month 46] <u>Nov. 2014</u>	Task 8.4.1.	
D8.8	DAQ performance and test beam utilization: Report on the performances and use of the integrated DAQ setup, and of the common test beam facilities at DESY and CERN	[month 46] <u>Nov. 2014</u>	Task 8.6 1&2	
D8.9	Performance of beamline and infrastructure: Report on performance of beamline and infrastructure including GEM based beam profile and tracking detector	[month 48] <u>January 2015</u>	Task 8.2.2 Frascati	
D8.10	Commissioning of new facility equipment: Report on commissioning of shuttle systems, movable irradiation tables with cold boxes and a fluence monitoring system based on a microwave absorption technique in silicon.	[month 48] <u>January 2015</u>	Task 8.3.2 CERN, UK, VU	
D8.11	Infrastructure performance and utilization: T ASD and MIND are constructed and tested for their performance.	[month 48] <u>Jan. 2015</u>	Task 8.5.2	