




Design Principles and Operational Results of the Cryogenic System for the ATLAS Liquid Argon Calorimeter

Caroline Fabre
CERN
Accelerator Technology Department
Cryogenics Group

on behalf of the ATLAS Liquid Argon Cryogenics Collaboration




1. The ATLAS liquid argon calorimeters
2. The procedures during cool-down
3. The steady-state operational performance
4. Special feature: uninterrupted functioning over 15 years
5. Safety aspects
6. Conclusion






✓ Barrel Calorimeter:

- D: 4.3 m; L:6.5 m
- Weight: 120 t
- Argon volume: 40 m³





Electromagnetic barrel half-wheel





✓ End-cap Calorimeter:

- D: 4.3 m; L: 3 m
- Weight: 219 t
- Ar volume: 19 m³



➡ Calorimeters are highly complicated composite structures made of copper, lead, stainless-steel and glass-epoxy... placed in aluminium cryostats



The ATLAS liquid argon calorimeters (3)

✓ Project stages:

1997-2004:

Cold performance test and calibration in particle beam of the 128 individual detector modules




2001-2005:

Cryostat and detector integration
Individual cryogenic test, at operating temperature of the 3 calorimeters



Nov. 2004:

Barrel lowering in ATLAS pit



Sept. 2005:

Transport of an end-cap calorimeter towards Point 1



✓ **Cooling criteria:** ΔT must be kept within strict limits to avoid excessive stresses or displacements ($< 6...45$ K)

✓ **Procedures :**


1. Rinsing cycles

2. Gas cooling: forced convection of GN₂ in heat exchangers
inlet T decreased on a ramp

3. Liquid cooling:
circulation of vaporizing LN₂


4. Filling:
Condensing of argon

Cool-down rate limited by an **interlock** triggered by the cooling criteria






The procedures during cool-down (2)





The steady-state operational performance (1)

✓ The argon bath is sub-cooled to about 88.3 K to prevent gas bubble formation



(End-cap A)





✓ Barrel steady-state performance:

- Temperature uniformity over detector volume: < 70 mK rms
- Temperature stability: < 5 mK rms
- LAr bath sub-cooled with 4.2 K to 7.7 K
- Argon purity: between 0.1 and 0.3 ppm of O₂-equivalent


Energy measurement sensitivity: 2 % per K

Statistical occurrence of barrel mean T



Stability measurements in barrel over 24 h

Probe #85 (Barrel)





The steady-state operational performance (3)

✓ Heat load balance:

- Heat load to the cryostats measured at the **test facility**:

barrel	end-cap	
1.8 kW	2 x 2.1 kW	estimated (TDR 1996)
1.9 kW	2 x 2.5 kW	
~ 50 % feedthroughs	~ 25 % cold electronics	

- Heat load to the complete cryogenic system measured at the **final installation**:

11.2 kW estimated (TDR 1996)

9.2 kW

(8 kW [EC cold electronics off] + 2 x 0.6 kW EC cold electronics)

- 2.3 kW resulting heat load to :
 - 2 argon tanks, PSD,
 - 5 valve boxes, LN2 circulator,
 - ~ 700 m transfer-lines



✓ 12 meter translation of the end-cap cryostats :

Cryogenic lines between expansion vessel and cryostat
Transfer-line supplying LN₂ to the heat exchangers
Signal cables and compressed air pipes


designed to follow this displacement

Inner diameter: DN150
Outer diameter: DN300
Length: 35 m
Bending radius: 1.5 m


LAr expansion vessels

LN₂ heat exchangers
regulation valve boxes

End-cap



LAr flexible line between expansion vessel and cryostat and associated displacement system




The 1000 t End-cap A calorimeter displaced to its extreme opening position with all services connected





✓ Redundancies :


- LN₂ pumps (x3)
- LN₂ supply services (x3)
- all essential devices on backed-up electrical power system:
 - EDF/EOS network
 - diesel generators
 - UPS
- compressed air and cooling water backed up





- ✓ Special features related to safe handling of large volume of cryogenic liquids in underground area
 - Argon volume of the three cryostats can be emptied into 2 x 50 m³ argon storage tanks by:
 - gravity
 - cryogenic pump
 - Argon tanks are:
 - equipped with LN₂ condenser and kept cold
 - Items containing large volumes are:
 - equipped with safety valves collected to a dedicated DN 500 pipe going to surface
 - placed above retention pits
 - Gas constantly renewed from the retention pits by surface extraction system
 - Insulation vacuum levels are monitored
 - Oxygen detectors

- ✓ 3 cryostats successfully installed, cooled-down and filled with argon in the underground area
 - ✓ Argon bath regulated to about 88.3 K with argon bath purity, temperature homogeneity and stability fully satisfactory for detector physics operation
 - ✓ Continuous functioning for up to 8 year periods
- ➡ demonstrates reliability of cryogenic system



**This achievement is the result of collaboration between:
BNL, CEA, CERN, LAL, LPSC and NTNU**