



ALICE DAQ


Plans for 2006

Procurement, Installation, Commissioning

P. VANDE VYVRE – CERN/PH for

LHC DAQ Club - CERN - May 2006

DAQ architecture




ALICE online logical model



Trigger level 0,1

Trigger level 2

High-Level Trigger



Detector

Digitizers

Front-end Pipeline/Buffer

Decision

Readout Buffer

Decision

Data transfer

Subevent Buffer

Decision

Event Building

Event Buffer

Storage

ALICE Terminology

Detector Data Link (DDL)
DAQ Read-Out Receiver Card (D-RORC)

Local Data Concentrator (LDC)

Global Data Collector (GDC)

Transient Data Storage (TDS)
Permanent Data Storage (PDS)




DAQ Deployment



- Staged deployment of DAQ:
 - Full detector readout from the start (enough PCI slots for all DDLs)
 - 20/40/100 % of event building and storage bandwidth
- Jan 2006: DAQ Stage 0
 - DAQ for detector test and commissioning at CERN
 - Covers needs till June 06
- Jun 2006: DAQ Stage 1 (20%)
 - Equipment of present generation of hw (Supermicro X6, FC 2G) already qualified after extensive and competitive testing
 - Tender delayed till 20 February to include latest developments from industry
 - LDCs: dual-core Xeon CPUs, FB DIMM memory, I/O acceleration
 - Servers: dual-core AMD CPUs
 - Storage Fibre Channel 4 Gb (FC 4G)

Detector Data Link (DDL)

- Two functions:
 - Detector readout: fast data transfer to PC memory
 - Electronics configuration: pedestals download



- PCI-X adapter for 2 DDL





DDL SIU and D-RORC production

- Jan '06: tender launched for production of
 - 550 DDL SIU cards
 - 460 D-RORC cards
- Mar '06 – Jun '06: delivery of DDL SIUs in batches
 - So far 108 DDL SIUs cards produced, burnt in and tested by manufacturer
 - Used to equip 1 side of TPC
 - Delay of delivery of ACTEL ProASIC 3
- May '06 – July '06: delivery of D-RORCs in batches

PCs



- LDC

- 110 x 4U PCs
- Dual Xeons
- Up to 6 PCI-X slots

- GDC

- 30 x 1U PCs
- Dual Xeons
- 1 PCI-X slot with Q-LOGIC FC-4G adapter


- DS

- 5 x 1U PCs
- Dual AMD Opteron 27x

- IT 3294/PH/ALICE (adjudication on 20 April '06)

- LDC:

- Supermicro X6DHE-XB now (50 ordered)
(CPU Nocona/Irwindale, Chipset Lindenhurst, DDR2 400, 6 PCI-X slots)
- Supermicro X7DBE-XB not yet available
(CPU Dempsey, Chipset Blackford, DDR2 FBD, 6 PCI-X slots)
- Supermicro X7DB8-E under test
(CPU Dempsey, Chipset Blackford, DDR2 FBD, 3 PCI-X slots)





Transient Data Storage

Local disk buffer at P2 (Fibre Channel 4G)

Storage network:

- 3 x QLogic SANbox 5602
16 ports FC4G
4 uplinks ports FC10G




Transient Data Storage

- 18 x Infortrend INF-A16F-G2422
2 ports FC 4G
16 SATA II HD




DO 23295/PH/ALICE (adjudication on 20 April '06)





Event Building Switch

- ALICE baseline:
 - TCP/IP over switched Ethernet
- Event-Building Switch
 - CERN frame contracts
 - Needs of IT and experiments
 - Good prices
 - On site maintenance (company+IT)
- Switch qualification test
 - Special set-up (IT): 60 PCs
 - DATE software used for benchmarking
- Force 10 Model 1200 delivered and installed





DAQ and ECS Software

- DAQ software ready for startup
 - DDL software
 - DAQ framework (Control, configuration, dataflow) (DATE V5)
 - Performance Monitoring (AFFAIR)
 - Data quality monitoring (MOOD)
- Information dissemination
 - Documentation: 4 DAQ sw packages + ECS: fully documented. User's guide released and printed
 - Regular DAQ trainings (70 people in last 3 years)
- Linux
 - Linux SLC3 now.
 - ALICE DAQ contributing to Linux SLC4 certification. Transition to SLC4 scheduled before end '06.
- Process defined to produce, distribute, install new versions
 - Code management system: CVS. Release packaging and distribution: RPM (~20 MB)
 - Automatic installation of Linux and DATE on DAQ nodes

DATE V5

- Control
- Configuration
- Dataflow

- Using
 - DIM, SMI++
 - Tcl/Tk
 - MySQL

ALLALICE
DAQ - Run Control
HI running on pcald21 with PID 24842
RC running on pcald21 with PID 24790

Disconnected Configuration < > Connected Run Parameters < > Ready to start

Start processes Start
Stop
Abort

AFFAIR EDM GDC
HLT mode A: DAQ only
Recording disabled

RUN NUMBER : 11 Run Control Status : RUNNING

Trace	Mon 08 17:10:40 (RC) Starting Data Taking for run 11
Clear	Mon 08 17:10:37 (HI) Current RC options loaded from : JCM_20
Debug	Mon 08 17:10:37 (HI) Start processes time : 7 seconds
Pause	Mon 08 17:10:30 (RC) Starting run 11
Bigger	Mon 08 17:10:30 (RC) Get and update run number from database
Smaller	Mon 08 17:10:30 (RC) New Run options loaded from : Database JCM_20
	Mon 08 17:10:24 (HI) Stop processes time : 6 seconds
	Mon 08 17:10:18 (ldc20) End of run requested from LDC20

DATE database

Roles

Detectors

Memory banks

Event building rules

Quit

Roles

Roles list

aloneldc
thedetector
thetriggermask

Name: aloneldc
Role: LDC
ID: 1
HLT role: Undefined
Hostname: pcald37
Description: Single LDC
Made of: Undefined
Top level:
Active:
Equipment: ->




New
Cancel
Add
Suppression

Commit Rollback Quit



Data quality monitoring: MOOD


- Monitoring Of Online Data
 - Raw data integrity
 - Detector performance
- Using
 - DATE
 - ROOT



DAQ performance monitoring: AFFAIR



- DAQ performance monitoring
- Node view
- System view



- Using
 - Apache
 - DATE, ROOT
 - DIM, SMI++

ECS

• Overall ALICE Control

- TRG
- DAQ
- HLT
- DCS

• Using

- DIM, SMI++
- Tcl/Tk
- MySQL

ITS Individual Detectors operations

SPD	SPD	SPD
INHIBITED	INHIBITED	INHIBITED

ITS DAQ details

ALLITS	SPD	SPD	SPD
RUNNING	DISCONNECTED	DISCONNECTED	DISCONNECTED

ITS TRG details

TPA	LTP-SPD	LTP-SPD	LTP-SPD
RUNNING	MASTER_RUNNING	SLAVE1	SLAVE2

LDC status display

LDC name	ssdic	spdic	ssdic
Number of equipments	1	1	1
Number of triggers	67449	67457	67457
Trigger rate	0	0	0
Number of events	67449	67457	67457
Event rate	0	0	0
Events recorded	67451	67459	67459

GDC status display

GDC name	epshbeam03gdc
Number of events	202389
Event rate	354
Events recorded	67451
Events recorded rate	121
Bytes recorded	2004943168
Bytes recorded rate	3.799 M

ALLITS DAQ - Run Control

HI running on epatbeam04.cern.ch with PID 21171
RC running on epatbeam04.cern.ch


Run NUMBER : 113 Run Control Status : RUNNING

Trace: Tue 09 18:39:43 (HI) Run Options loaded from : /local/ITS_site/DAQ/configurationFiles/ALLITS/0
Clear: Tue 09 18:39:43 (HI) Run parameters loaded from : /local/ITS_site/DAQ/configurationFiles/ALLI
Pause: Tue 09 18:39:43 (HI) Configuration loaded from : /local/ITS_site/DAQ/configurationFiles/ALLITS/0
Bigger: Tue 09 18:39:43 (HI) HI options loaded from : /local/ITS_site/DAQ/configurationFiles/ALLITS/0


DAQ Commissioning



- DAQ commissioning:
 - 1 system DAQ commissioning: “reference system” in DAQ lab
 - Test all functionalities
 - Running last released versions of DDL firmware, DAQ and ECS software
- Detector emulator
 - DDL Data Generator (DDG)
 - DDL data source triggered by TTC
 - Generation of busy
 - Uses the D-RORC as DMA engine to read data from PC memory
 - Send them over DDL



DAQ Reference System: hw data generator





DAQ systems for detector test & commissioning

- Detector tests with DAQ
 - Data transfer: 25 DDLs for tests (1 chain per detector delivered since 2002)
 - DATE sw
- Detector commissioning with DAQ
 - Hardware DAQ dedicated to detector tests:
Distributed in different locations according to needs
 - Data transfer
 - CERN: 20 DDL SIUs, 16 D-RORCs, 8 DIUs
 - DAQ fabric
 - 12 LDCs (6 PCI slots)
 - 4 GDCs, 3 servers
 - 2 storage units 2 TB



DAQ systems for detector test & commissioning

- SPD First sector with DAQ, TRG, ECS in DSF (CERN Bld 186)
- SSD DAQ system (Utrecht)
- SDD DAQ system (Torino)
- TPC Electronics setup (Bergen, CERN Bld 13). Detector (SXL2 CERN)
- TRD DAQ ready for super-module being assembled (Heidelberg)
- TOF DAQ ready for module being assembled (Bologna, CERN Bld 156)
- Muon TRK DAQ system (Orsay). Feb '06: test SXL2
- Muon TRG DAQ system (Nantes)
- HMPID DAQ system (CERN Bld 581)
- PHOS DAQ for electronics test, then module assembly (Bergen, CERN Bld 167)
- FMD DAQ installed for test in March (NBI, CERN Bld 1)
- T0 DAQ in TOF labs (Bologna and CERN)
- V0 Test of CCIU (Lyon)
- ACORDE DAQ system for detector (SXL2 CERN)
- EMCAL DAQ system used during TB (Fermilab)



Detector/DAQ integration (Mar 06)

	S P D	S S D	S D D	T P C	T R D	T O F	M U O N T R K	M U O N T R G	H M P I D	P H O S	F M D	T O	V O	Z D C	P M D	A C O R D E	E M C A L
DATE system	Green	Green	Green	Green	Green	Green	Green	Green	Green	Green	Green	Green	Green	Green	Green	Red	Green
DDL with data gen.	Green	Green	Green	Green	Green	Green	Green	Green	Green	Green	Green	Green	Green	Red	Red	Red	Green
Detector readout with DDL & DATE	Green	Green	Green	Green	Green	Green	Green	Green	Green	Green	Red	Red	Green	Red	Red	Red	Green
Data quality monitor. (MOOD)	Green	Green	Green	Orange	Green	Orange	Green	Green	Green	Red	Red	Red	Red	Red	Red	Red	Red



Must be done in the lab before starting commissioning at Point 2



Services

- Ready
 - 35 racks 56 U
 - Normal Power
 - Air conditioning
 - Cooling doors for 35 racks
 - Connections to chilled water
 - Chilled water circuits
 - Network
 - Access control
 - Optical fibres SXL-CR1
- In progress
 - Optical fibres between CR1 and other CRs and UX
- Quality and schedule critical





Some of the next steps

- Apr '06 DAQ standalone commissioned in lab
- May '06 ECS + DAQ + HLT at Point 2
- Jun '06 ECS + TRG + DAQ test and commissioning in lab
Installation DAQ Stage 1
- Jun'06 – Sep'06
Data Challenge from Point 2 to IT

- May '06 TPC commissioning on surface with cosmics
- Jul '06 PHOS, TOF, TRD, HMPID, ACORDE
- Sep '06 TPC
- Jan '07 ITS
- Feb '07 TOF, TRD
- Apr '07 FMD, V0, T0, PMD



Conclusion

- Production of DDL and D-RORC in progress
 - Mar-Jul '06. Enough DDL SIUs to equip 1 side of TPC
- DAQ fabric hardware
 - All hw elements qualified. Tenders include most recent equipment.
 - Procurement and delivery in progress.
- DAQ software ready
 - Software (DDL sw, DATE, AFFAIR, MOOD) released and documented.
 - Linux SLC3 now. Transition to SLC4 scheduled before end '06.
- DAQ system deployment
 - Stage 0: small DAQ system for detector test and commissioning
 - Stage 1: deployed in June (full readout, 20% performance)
- Installation
 - Services for DAQ finished. Optical fibres progressing with detector installation.
- Commissioning of detectors in parallel