


CMS

May 3 2006, S. Cittolin

DAQ status and plans



DAQ baseline structure




Collision rate 40 MHz
Level-1 Maximum trigger rate 100 kHz
Average event size ≈ 1 Mbyte
 Event Flow Control $\approx 10^6$ Mssg/s

No. of In-Out units **512**
Readout network bandwidth ≈ 1 Terabit/s
Event filter computing power $\approx 10^6$ SI95
 Data production \approx Tbyte/day
 No. of PC motherboards \approx Thousands




DAQ structure & layout



12.5 kHz

+12.5 kHz



Readout

Data to Surface (D2S)

Readout Builders (RB)

Filter Farms



DAQ 2005-07 activities

1. Production

Readout systems: Slink (720), FRL(560), FMM(50) modules, cables (800) and crates(60)

2. Procurement & Installation

Pre-series scale 1:10 DAQ system for development and integration

USC DAQ control PCs(80): FRL, FMM, FED, FEC, DCS, VME-PCs (180),

D2S Data to Surface Myrinet links(1024), FED Builder switches(12), Fibers(2048)

SCX Readout Builders: Racks(120), DAQ PCs (600 RU-BU), EVB (2000 ports), HTL (800 PCs)

3. Commissioning

USC DAQ racks, FRL/FMM crates, PCs

D2S Data to Surface Myrinet links, FED Builder switches, Fibers

SCX Readout Builders: Racks, DAQ farms (RU-BU), EVB switch, Filter Farm

4. MTCC integration

Pre-series DAQ for final detector readout : Slink, FRL, FMM modules, cables and crates

5. TriDAS integration

Detector readout systems: Slink, FRL, FMM modules, cables and crates

6. Development&Consolidation


Frameworks: XDAQ, RCMS, FF-HTL. Interfaces: XDAQ-DB, PVSS

Applications: RB(EVM/RU/BU), FMs, Configurator, DAQ Monitor, Flow controllers, DQM, DBs

Online software releases: MTCC May 2006, First Run Jan 2007



Integration: Pre-series



Green Barrack

Current activities

- DAQ integration and MTCC
- Online services pre-series
- Detector readout integration
- First Run EVB technologies
 - GbE with a FORCE10 E1200 switch

Readout Builder PCs

- 64 dual Xeon 2.6 GHz RU-BU PCs
- Myrinet +GbE interfaces
- 16 dual Xeon 2.6 GHz Filter nodes
- OS Linux 2.4




Scale:

Structure	1:8
Functionality	1:1
Performances	1:4




Pre-series: Hw&Sw integration

32 GIII FED emulators



64 FRLs



4 FRL crates




200m fibers
Data links



8 8x8 FED builders



64x64 RU builders
16 FUs Filter SF



Up to 32 detector FED





Pre-series system integrations

- **MTCC DAQ system:**
 - 6 TTC partitions, single DAQ partition
 - Single RU Builder and FED builder (as in final CMS)
 - 7x8 RU Builders and 7 times FB N x1
 - Filter Farm 16 FUs available
 - 10 Central/Local DCS servers
- **MTCC Data bases**
 - Data base server (oracle 10G)
- **MTCC Event data storage**
 - Server 900 Gbyte (to be doubled) (network write around 50 MB/s)
- **First run EVB and PC technologies evaluation (Jul 2006)**
 - Force 10 GBE switch (RU to multiple BU EVB etc..)
 - Multi Core 64 bit next generation PCs, Multi-GBE network interfaces
- **Service Network**
 - Same structure as for CMS (final specification ready for installation):
 - CERN GPN and private network for all DAQ
 - Head nodes (aka application servers, aka proxy nodes) in between
 - Connection Cessy - CERN backbone is 1 Gbps
- **System admin**
 - Linux SLC3
 - Few windows-XP nodes (for DCS)
 - Services: NFS server, DHCP, LDAP, ..
 - Nodes on private network must be centrally administered



SCX surface computing room



Apr 2006 110 racks installed
Jul 2006 technical network infrastructure
Aug 2007 Ready for PC installation



DAQ configuration for first run

Subsystem

2005 Pre-series

Development and Magnet Test

Nominal Ready

100%

32x32x2 EVB, 16FU FF

2006 D2S

Procurement and production

100%

FRL/FMM, PC control, FED Builders, Fibers

Readout Builders

2006-07

Infrastructure

>50 %

Racks, Control, Networks, Remote

2007 Readout

4x (64x64) EVB full installation

50% (50 kHz)

500 Gb/s switch, Local Storage

June 2006 600 DAQ-PCs and EVB switch

2008-9 Filter Farm incremental




10-30% (*)

Dec 2007 800 FU-PCs and Filter farm Switch

*) The 4 RBs readout network (GBE or Myrinet) allows the global DAQ system be reconfigured with part of BUs becoming FUs so LV1 maximum rate can be adjusted to fit the available Filter Farm selection power

20.. DAQ completion (not funded, 8 slices, 100 kHz...) 100%

Infrastructures, xy1800 FU-PCs, EVB and FF Switches





DAQ PC/GBE material profile

	Dec. 05	Dec 06	Dec 07	Jun 08	Dec 08	Jun 09
D2S	Completed 100 kHz readout					
DAQ RU-BU		600 PCs Market Mar 06 Tender Jul 06			600 PCs	
Networks EVB		2000 GBE 50 kHz EVB			2000 GBE 100 kHz EVB	
Filter Farm				0-900 PCs 50 kHz HLT		0-900 PCs 100 kHz HLT

First run (technical)
 - Up to 50 kHz readout
 - HLT power limited
 DAQ-FF PCs can be reconfigured to fit optimum HLT rate

Second run (physics)
 - Up to 50 kHz HLT

High-Lum runs
 Up to 100 kHz HLT




DAQ 05-07: plans & milestones

- ✓ **Apr 05** **DAQ Pre-series DAQ completed. Integration started**
- ✓ **Aug 05** **D2S Myrinet links and switches procured**
- ✓ **Jan 05** **D2S FRL/FMM systems produced and tested**
- **May 06-Jun 06** **USC FRL/FMM crates, Cables, Fibers and PCs installed**
- **Jul 06-Dec 06** **USC FED/FRL/FMM readout commissioning**
 - FED-FRL cables and interfaces auto-test, USC FED Builder Myrinet test
 - USC-miniDAQ (8x8) sub-detector global DAQ commissioning
- **May 06-Aug 06** **Preseries integration: MTCC multi-detector full chain DAQ**
- **Aug 06-Feb 06** **SCX DAQ GBE&PCs procurement and installation**
 - DAQ PCs (600) and 2000 port GBE switch procurement
 - USC-SCX links: Test SCX FED builders and run SCX-miniDAQ (8x8)
 - Install 4 Readout Builders (512 PCs) with GBE-EVB (2000 ports)
- **Oct 06-May 07** **USC-SCX Central DAQ commissioning**
 - GTPe, FRL-eFED central DAQ auto test mode.
 - Full DAQ integration (EVB,FF, DQM,Local storage)
 - Central RCMS/DCS, DBs and Connection with remote data storage
 - Multiple Readout Builders and multiple TTC/DAQ Partitions
- **Feb 06-Aug 07** **TriDAS system commissioning**
 - SCX miniDAQ Trigger and DAQ integration (TTC/TTS)
 - Multiple Readout Builders and Trigger Partitions
 - Regular dry runs and training sessions
- **Aug 07** **Ready for first collision data taking**
 - Variable configuration from 50 kHz (10% Filter Farm), 15 kHz (100% Filter Farm)
- **Jan 08-.....** **First phase DAQ completed (3 slices) for physics runs**





DAQ hardware & infrastructure



• Front-end readout

- FED SLINK64-LVDS interface (CMC)
- Front-end Readout Link (FRL)
- Fast Monitor Module (FMM)
- FRL and FMM crates
- FRL and FMM control PCs
- Myrinet LANai 2XP data link



• FED Builders and optical links


- Myricom 256 port switches
- Myricom LANai 2XP (FRL-RUI)

• Surface SCX Readout Builders

- DAQ RU/BU PC farms
- Event Builder switches
- Filter Farms
- Local/Remote data storage

• USC/SCX DAQ Infrastructure

- Counting rooms networks
- D2S Optical cables
- Water cooled PC racks





DAQ software



- **Core framework and components**

- System and communication services
- Hardware access facilities and device drivers
- Interface to external systems (e.g. DCS, computing services)
- Basic configuration and control facilities (GUI, script)
- Benchmarking and testing software
- Re-usable DAQ modules (e.g. event builders, FED readout)
- DAQ monitoring



- **Run Control and Monitor System**

- Configuration, control and monitoring
- Interface to operators (GUI, script)
- Interface to DCS



- **Databases**

- Persistency technology
- Data categories
- Data access tools
- Administration



- **Detector Controls**

- Detector DCS coordination. Common tools development&support
- Framework and central DCS system
- DAQ infrastructure controls

