

Managed by Fermi Research Alliance, LLC for the U.S. Department of Energy Office of Science

Neutrino Beam Plans in the U.S.

Jim Strait, LBNE Project Director International Meeting for Large Neutrino Infrastructures 22 June 2014

Outline


- Survey of existing Fermilab neutrino program
 - Neutrino Beams
 - Running and planned experiments
- Increasing proton beam intensities
 - PIP and PIP-II
- New beam for the new long-baseline neutrino facility

Accelerator-Based Neutrino Program in the U.S.


Fermilab hosts an active and diverse accelerator-based neutrino program.

- Two neutrino beams in operation and a third under design
- Four experiments currently taking data
- Three completed experiments analyzing data
- One experiment under construction
- One experiment under design
- Two proposals reviewed by the PAC and under consideration by Fermilab management
- Several experimental proposals submitted or in development.
- Supporting test beam program for detector development and calibration.





NuMI and Booster Beams




5

Experiments in the NuMI Beam

The MINOS+ Concept Long-baseline neutrino oscillation experiment Measure NuMI Neutrino beam energy and flavor composition

- Near Detector at Fermilab
- Far Detector at Soudan Underground Lab, MN
- Compare Near and Far measurements to study neutrino mixing

MINOS/MINOS+, Neutrino 2014



V

neutrino beam.

First LArTPC in a low (1-10 GeV) energy

ArgoNeuT in the NuMI beam line

Experiments in the Booster Neutrino Beam

Ten Years of Successful MiniBooNE **Running and Results!**



MicroBooNE

Ì,


TPC push-in: Fri, 20th Dec, 2013






J.Strait | Neutrino Beam Plans in the U.S.; 7

Proposed Short-Baseline Neutrino Program




8


Additional Possible Experiments



Measure ν -induced backgrounds relevant for large water detectors using an Optical Time Projection Chamber in BNB



Short-baseline ν_{μ} -disappearance measurement in BNB (NESSiE)



9

Neutrino beam delivery over the last 15 years:

	protons on target (x10 ²⁰)	
K2K	0.92	
T2K	6.70	
OPERA/ICARUS	1.81	
	9.43 = total Asia + Euro	ope
NuMI	18.00	
BNB	17.50	
	35.50 = total Fermilab	


• Delivering protons to neutrino experiments is a top priority for the Fermilab accelerator complex.

Increasing beam intensity

- Upgrades to the Main Injector and Recycler done as part of the NOvA construction will enable doubling the NuMI beam power to 700 kW
 - Convert Recycler to proton-stacking ring
 - Increase Main Injector ramp rate
 - ~10% increase in intensity per pulse
- Proton Improvement Plan (PIP) to increase proton flux from Booster to the Main Injector
 - Refurbish Booster RF system: $7.5 \rightarrow 15$ Hz beam operation
 - Upgrades to Linac and Booster for higher reliability
- Combined upgrades will deliver 700 kW to NOvA and increase the intensity of the Booster Neutrino Beam.




Proton delivery scenario (approximate)



22 June 2014

Proton Improvement Plan II (PIP-II)


- Goal is to increase Main Injector beam power to 1.2 MW.
 - Replace the existing 400 MeV linac with a new 800 MeV superconducting linac => 50% increase in Booster intensity.
 - − Shorten Main Injector cycle time $1.33 \rightarrow 1.2$ sec.
- Build this concurrently with new long-baseline facility
 => deliver 1.2 MW to
 LBNE from t = 0.
- This plan is based on welldeveloped SRF technology.
- Developing an international partnership for its construction
- Strong support from DOE and P5



22 June 2014

Flexible Platform for the Future


- PIP-II Inherent Capability
 ~200 kW @ 800 MeV
 x10 Mu2e sensitivity
- Future upgrade would provide > 2 MW to LBNE
- Flexibility for future
 experiments
 - Muons, Kaons at 100's kW



Beamline for a new Long-Baseline Neutrino Facility


LBNE is developing a design for a new neutrino beam at Fermilab, to support a new long-baseline neutrino facility.

- Directed towards the Sanford Underground Research Facility (SURF) in Lead, South Dakota, 1300 km from Fermilab.
- Beam spectrum to cover 1st (2.4 GeV) and 2nd (0.8 GeV) oscillation maxima => Cover 0.5 ~ 5 GeV ^{2nd}
 ^{1st Osc Max}
- All systems designed for 1.2 MW initial proton beam power.
- Facility is upgradeable to ≥2.3 MW proton beam power.




22 June 2014


Fermilab Accelerator Complex



Beamline for a new Long-Baseline Neutrino Facility



Target Hall and Decay Pipe Layout



18 J.Strait | Neutrino Beam Plans in the U.S.;

22 June 2014

Improved Focusing for Second Oscillation Maximum

1st Horn: NuMI Design (current LBNE baseline)

1st Horn: Improved Design Concept

Energy hpx pos **Beam to Homestake** Entries 143470 3.048 Mean 2.742 RMS Horn separation 6.6m 35 LBNE horn design 30 flux (m⁻² pot⁻¹ GeV⁻¹ NuMI horn design 25 + 30<mark>%</mark> at 2nd osc. Max 20 ... not fully optimized yet. 15E 10 12 10 GeV Energy

This is one example of significant improvements that are possible and needed, which new collaborators could bring into the design of the long-baseline neutrino facility beam design.




Summary

- Fermilab hosts an active and diverse accelerator-based neutrino program.
- Fermilab has a record of delivering high-intensity proton beams with high reliability and long running time for neutrino physics.
- On-going upgrades will increase the Main Injector beam power to 700 kW over the next ~2 years.
- PIP-II will further increase the beam power to 1.2 MW and provide a platform for future beam power >2 MW.
- A neutrino beam design is being developed to support a new long-baseline neutrino facility directed from Fermilab to SURF. There is substantial room for new collaborators to bring new ideas to improve the design and performance.

Fermilab

320 kW on target


- Previous operation:
 - H- linac at ~35 mA
 - Charge exchange injection into Booster 10-11 turns: 4.3e12
 - 9 pulses (at 15 Hz) into Main Injector with RF slip stacking
 - Ramp to 120 GeV at 204 GeV/s and extract to NuMI target
 - 3.7e13 / 2.2 sec cycle 323 kW



S. Nagaitsev | Fermilab Accelerator

Increasing Beam Power to 700 kW

- Move slip-stacking to recycler
- 11 batch -> 12 batch
- Increase Main Injector ramp rate (204 GeV/s -> 240 GeV/s)
- 330 (380) -> 700kW with only ~10% increase in perpulse intensity
- Peak intensity 10% just more frequent
- Achieving 700 kW will require the 15-Hz Booster operations



Fermilab Accelerator

Conselar

The Status and the Plan

- Booster at 4.3e12 ppp, 7.5 Hz ✓
- Started NuMI operation with MI only
 - 2.5e13 0.6 Hz (1.67 s cycle)
 - ~290 kW peak
- We can currently run the Recycler with~2.2E13 p every 1.33 sec

 (300KW or 270KW with one slow-spill event).
 - 6 Booster batches (no slip-stacking)
 - We run in this mode a few hours every day. Need to finish damper commissioning and reduce the losses before we can run 100% like this (expected before the end of June)
- Increase the Recycler beam intensity to 2.5E13 p delivering 345 kW (beginning of July).
- Plan to reach 450 kW by the end of the summer by using 8 Booster batches (4 slip stacked plus 4 single).



PIP-II Performance Goals

Performance Parameter	PIP	PIP-II	
Linac Beam Energy	400	800	MeV
Linac Beam Current	25	2 mA	
Linac Beam Pulse Length	0.03	0.5 msec	
Linac Pulse Repetition Rate	15	15	Hz
Linac Beam Power to Booster	4	13	kW
Linac Beam Power Capability (@>10% Duty Factor)	4	~200	kW
Mu2e Upgrade Potential (800 MeV)	NA	>100	kW
Booster Protons per Pulse	4.2×10 ¹²	6.4×10 ¹²	
Booster Pulse Repetition Rate	15	15	Hz
Booster Beam Power @ 8 GeV	80	120	kW
Beam Power to 8 GeV Program (max)	32	40	kW
Main Injector Protons per Pulse	4.9×10 ¹³	7.5×10 ¹³	
Main Injector Cycle Time @ 120 GeV	1.33	1.2	sec
LBNF Beam Power @ 120 GeV*	0.7	1.2	MW
LBNF Upgrade Potential @ 60-120 GeV	NA	>2	MW

*LBNF beam power can be maintained to ~80 GeV, then scales with energy



PIP-II Status and Strategy

- PIP-II is currently pre-CD-0
 - Complete concept exists
 - Documented in whitepaper; technical backup in PX RDR
 - R&D program underway
 - Front end (PXIE) and superconducting rf development
- Strong endorsement from P5
 - Recommendation 14: Upgrade the Fermilab proton accelerator complex to produce higher intensity beams. R&D for the Proton Improvement Plan II (PIP-II) should proceed immediately, followed by construction, to provide proton beams of >1 MW by the time of first operation of the new long-baseline neutrino facility.

Fermilab

6/11/2014

- Applies in all budget scenarios considered.
- Discussions with P5, Fermilab, and DOE/OHEP management have been in context of FY19 construction start
 - Consistent R&D deliverables list established
 - Preliminary discussions on potential international in-kind contributions
 - Aligned with LCLS-II and LBNF activities
- Goals for the next year
 - Release PIP-II specific RDR
 - Maintain PXIE and SRF development on established schedules
 - Support DOE in the development of Mission Need Statement
 - Establish PIP-II Office, within Accelerator Division

Beam Improvements Under Consideration

Changes	0.5-2 GeV	2-5 GeV	Extra Cost
Horn current 200 kA \rightarrow 230 kA	1.00	1.12	\$0
Proton beam 120 \rightarrow 80 GeV,700 kW	1.14	1.05	\$0
Target graphite \rightarrow Be	1.10	4% <u>1.00</u> 🕻	31‰ 1 M\$
$DP Air \rightarrow He$	1.07	1.11	\sim 8 M\$
DP diameter $4 \text{ m} \rightarrow 6 \text{ m}$	1.06	1.02	\sim 17 M\$
DP length 200 m \rightarrow 250 m	1.04	1.12	\sim 30 M\$
Total	1.48	1.50	

- Target/horn system can be replaced with more advanced designs as they become available.
- Decay pipe design must be fixed at the beginning.
- First four improvements appear technically and financially feasible.
- The last two proposals regarding the decay pipe diameter and length are still under study.

5 Fermilab