Experience of Commissioning the CMS Silicon Strip Tracker

Joanne Cole
University of Kansas
On behalf of the CMS Collaboration


28th July 2008

- Introduction to the CMS Silicon Strip Tracker (SST)
- Integration to commissioning: The story so far ...
- **** The commissioning procedures**
 - **Preliminary results from the first round of commissioning**
- **** Outlook**



The CMS tracking system






5.4m x 2.4m 210m² of active silicon 15148 modules 75000 APV FE chips 9.6M readout channels

Only Strip Tracker considered here See talk from Anders about Pixels



Modules







Each module includes analogue readout chips (APV25)

27 different types of modules


TOB stereo module (100 mrad stereo angle)



TIB module




TID/TEC modules





Readout and DAQ Architecture





- ****** FE does analogue pulse shaping & optical transmission
- **FEDs** → Process data & send to central DAQ
 - **** Pedestal & noise suppression**
 - **** Cluster finding**

Use copy of CMS DAQ for "local" runs:

- **→** Reconstruct full events (readout units)
- → Process the events as they are taken (Builder/Filter units)
- → Raw data as well as specialised tracker root files written out to disk (Storage Manager)




The SST in pictures





SST integration at CERN main site

The SST ready for transport to CMS (20km journey)





From Integration to Commissioning




- **Summer 06 MTCC first experience of running CMS**
- November 06 July 07
 - Integration & operation at "Tracker Integration Facility"
 - **** 15% of tracker operated warm and then cold (down to -15°C coolant temperature)**
 - **** Huge amount of experience gained**
- # July November 07: Cabling of central CMS section ("YB0")
 - A mammoth task!
- December 07: SST installed in CMS
- **# January March 08: Connection & checking of tracker services**
- March April 08: First test of commissioning procedures with temporary cooling
- **# June 08 Present**
 - **First round of checkout & commissioning with final cooling plant**
 - ** Preparation for inclusion of SST in Global Run (7th July)
 - **Cover only the results from this period here**



Installing the SST underground









Connecting up the SST



- *** A major achievement!**
- **** 980 pipes**
- **%1080km fibres**
- **** 80km power cables**





Cabling of +Z end - March 2008


Power cabling layout for SST



How to commission the SST (I)



Step 1: Provide tracker with cooling, power & safety interlocks:



- → Power on/off tracker
- → Monitor environmental conditions; attempt to shutdown SST nicely (ie. BEFORE hardware) in case of problems
- 72 TIB/TID cooling loops
- 44 TOB cooling loops
- 16 TEC sectors



How to Commission the SST (II)



- ****** Control PSU map
 - **# Identify connections between control and power supply systems**
- Control Readout map
 - **# Identify connections between control and readout systems**
- # Internal timing
 - **Synchronization of all channels**
- Optical Gain Scan
 - **** Optimal bias & gain settings for FE laser devices**
- ****** Analogue baseline tuning
- ****** Tuning APV pulse shape
- Pedestal and noise (needed for physics)
- ** APV latency scan
 - **Synchronize tracker with LHC clock**
- ****** Fine tuning of pulse shape sampling
 - **Tune to 1ns (account for time-of-flight etc.)**

Checkout procedures



Checkout results





- * These results are Preliminary first round of commissioning
 - ** Aim was to validate commissioning procedures and to include SST in Global Run in early July
 - Excluded anything that was not completely understood
 - Deliberately conservative approach
- Second round of commissioning now underway
 - Systematic investigation of all channels not previously included
 - ** Large scale testing of all commissioning procedures not yet performed



Synchronization (I)








- **** APV** synchronization pulses:"tick marks"
- **** Use tick marks to synchronize the SST internally**
- ** Account for different cable lengths etc.
- ** Adjust programmable "Phase Lock Loop" chip on each module



Synchronization (II)






BEFORE: Cabling structure clearly visible AFTER: All channels aligned




Opto-Gain Scan



- **Solution** **Optimize use of available dynamic range of analog opto-hybrid (AOH)
 - Laser bias
 - input scale factor (gain)





- ** Laser diode output scales linearly with input current above threshold
 - **** Monitor slope, threshold**
 - Monitor output tickmark seen at FED
 - **** Monitor estimated input tickmark to LLD**
- Note: Temperature dependence!



Pedestals & Noise



**** Quality of the SST is excellent**


**** Example: TEC+**

** Preliminary results from first round of checkout:

Number of dead strips << 1 %

Number of noisy strips < 1 %

Mean noise < 2000 e-/strip





Latency scan




- Synchronization of tracker with external trigger
 - **** APV latency set in steps of 25ns**
 - **Determine optimal latency by reconstructing pulse shape**

**** Choose working point closest to maximum**

First large scale test of procedure
Very limited statistics

Based on these results, TIB/TID, TOB (and later TEC+) entered Global Run in early July! ©




28th July 2008

CMS Tracker



First tracks in CMS!







First round of commissioning



- # First round of commissioning all subdetectors checked out!
- **Quality of connections is excellent:**

 - **81% of TEC- channels** ✓ (one sector excluded)
- ** TIB-TID-TOB participated in full global run
 - **** TEC+ joined later**

A GREAT SUCCESS!!



Summary & Outlook



- First round of SST commissioning complete
 - **Most commissioning procedures validated**
 - **** TIB,TID, TOB and TEC+ participated in CMS global run in early July**
- Quality of the SST is impressive
 - **** Vast majority of channels passed checkout first time**
 - First look at performance looks good!
- Second round of commissioning underway
 - Large scale testing of remaining commissioning procedures
 - Systematic investigation and repair of channels excluded during the first round

Thanks to Phil Harris & Christophe Delaere for the plots!






Extras


28th July 2008




The subdetectors in pictures












APV25






- **** Two readout modes:**

 - - **** Necessary for high luminosity running**



YB0 cabling







Tracker Cooling


Chilled water

USC55 - CV zone



Failure of heat exchanger in one of two tracker cooling stations (late November 2007)

Brine leaked in C₆F₁₄ and contaminated the system



Chiller group

(R507 A)

- # Full cleaning procedure rapidly developed and carried out
- **** Tracker to be operated at room temperature this year**
 - **# Use C₆F₁₄ instead of brine**
- **** Longer term: Replacement of all heat exchangers**


Top



Control - Readout Map



- **** Connects APVs to FED channels**
- # ID information from hybrid sent as bit pattern to FEDs



- ****** Identify any missing connections
- ** Also spot any "grey" connections

