


Status of CTF3

G.Geschonke
CERN


CLIC Test Facility CTF3



Provide answers for CLIC specific issues

→ Write CDR in 2010

Two main missions:



Prove CLIC RF power source scheme:

- bunch manipulations, beam stability,
- Drive Beam generation
- 12 GHz extraction

Demonstration of “relevant” linac sub-unit:

- acceleration of test beam

Provide RF power for validation of CLIC components:

accelerating structures,
RF distribution,


PETS (Power extraction and Transfer
Structure)

Drive Beam generation in CTF3





*Principle: A long high intensity bunch train (1.4 μ s) is accelerated with 3 GHz
Bunch manipulations increase bunch repetition frequency
and increase peak current*


“Phase-coding” of bunches





bunch interleaving with Delay Loop




Drive Beam generation



successive injection of 4 bunch trains into **Combiner Ring**



CTF3 - CLIC




CTF3 is scaled down from CLIC:

	CLIC	CTF3
Drive Beam energy	2.4 GeV	150 MeV
compression / frequency multiplication	24 (Delay Loop + 2 Combiner Rings)	8 (Delay Loop + 1 Combiner Ring)
Drive Beam current	4.2 A*24 → 101 A	3.5 A*8 → 28 A
RF Frequency	1 GHz	3 GHz
train length in linac	139 μs	1.5 μs
energy extraction	90 %	~ 50 %

CTF3 uses existing infrastructure from LEP injector:


Building, infrastructure,
3 GHz RF power plant,

CTF3 building blocks






Infrastructure from LEP



PULSE COMPRESSION
FREQUENCY MULTIPLICATION




Present CTF3 status




CTF3 Installation



Thermionic gun



Injector solenoid





Thermionic gun
10 A max,
after bunching
3.5 A nominal, max. 7 A
one sw and one tw buncher
three 1.5 GHz bunchers





Magnetic chicane

Injector and Linac



RF power plant




**11 s-band klystrons 3 GHz
35 – 45 MW, 5.5 μ s**

**9 with pulse compressors:
factor 1.9 – 2 (1.6 μ s)**


**3 L-band travelling wave
tubes
40 kW, 3 μ s
1.5 GHz BW >200 MHz**

**1 L-band klystron
22 MW, 5.5 μ s**

RF Pulse compression →






CLIC Workshop 2006 CTF3 G. Gessner




**phase error: 6 deg
amplitude: $\pm 1\%$**

Sub-harmonic bunching / phase coding




1.5 GHz




Switching transient about 7 bunches

Full Beam loading






Proof of one of the major CLIC features:
Full Beam Loading



RF to beam transfer:
95.3 % measured

Drive Beam accelerating structure.




RF power at output of accelerating structure

Linac routinely operated with full beam loading




$\pm 0.5 \text{ m}$




The image displays a 3D perspective view of a linear accelerator (LINAC) structure, showing a series of accelerating cells (red and blue blocks) mounted on yellow supports, connected by a central beam pipe. The structure is shown on a white base. Surrounding the main diagram are several inset photographs showing various components and sections of the LINAC, including a large blue cryogenic chamber, a red accelerating cell, a blue accelerating cell, a section with blue flexible ducting, and a close-up of a nozzle or gun assembly.

Delay Loop

Designed and built by INFN Frascati




circumference 42 m (140 ns)
isochronous optics
wiggler to tune path length
(9 mm range)






1.5 GHz RF deflector



Bunch interleaving in Delay Loop







Beam current measured:



Successful demonstration of Delay Loop operation !

Combiner Ring




Combiner Ring commissioning






Achieved recombination:


- Linac current lower than nominal
- DL bypassed (no holes, missing factor 2)
- Losses during recombination (**instability**...)




Instability in CR




New Installation: Strip-line kicker






Strip-line kicker from CIEMAT installed in the Combiner Ring and tested:
works according to specifications




Transfer line TL2




large part been done by RRCAT:
Optics design
Aluminium vacuum chambers
Bending magnets



Accelerating structure testing



Tests at 30 GHz still continuing




100 MW produced at 30 GHz,
Transmission via circular
 TE_{01} line (17 m) with 65 % efficiency

operation for 30 GHz now routine,
largely automatic.
24 hour operation

12 GHz work:



Collaboration with SLAC and KEK,
presently no test facility at CERN

Stand-alone power source in preparation



Klystron with
pulse compressor


CLEX (CLIC Experimental Area)



**All Beam lines installed, except TBL !
(ITB is not part of the base-line programme)**

Probe Beam

Responsibility of IRFU (DAPNIA), CEA, Saclay




200 MeV
bunch charge 0.5 nC
number of bunches 1 - 64

Status:

Installed, RF conditioning in June


Laser under development



CALIFES

A. Mosnier, CEA Dapnia

Califes



Klystron and BOC



waveguide RF distribution






Photo Injector



Accelerating sections



RF deflector for diagnostics

Klystron and modulator installed
Waveguides installed, Phase shifter is late
RF conditioning starts now




UPPSALA
UNIVERSITET

TBTS



- intro
 - design
 - status
- Summary

Roger Ruber
CTF3 Meeting


TBTS Design



From Dream to reality!




Two Beam test Stand




All hardware installed !
(Uppsala University)
Commissioning with beam starting

PETS (CERN) will be installed in October,
first accelerating structure in 2009




Phase #1

PE






Uranus





Neptune

Test Beam Line TBL



- High energy-spread beam transport decelerate to 50 % beam energy
- Drive Beam stability
- Stability of RF power extraction total power in 16 PETS: 2.5 GW
- Alignment procedures



PETS design



5 MV/m deceleration (35 A)


165 MV output Power

2 standard cells, 16 total



PETS development: CIEMAT
BPM: IFIC Valencia
and UPC Barcelona

TBL



- Prototype PETS + vacuum tank being built by CIEMAT
- Precision quadrupole movers are being built by CIEMAT, prototype has been successfully tested
- All quadrupole magnets are being built by BINP, delivery end 2008
- Beam Position monitor prototype was built by IFIC Valencia, front-end analogue electronics is being developed by UPC Barcelona
- Vacuum components built by CERN
- Beam line will be installed with all quadrupoles and PETS replacement chambers during winter shut-down.





BPS for TBL (IFIC Valencia and UPC Barcelona)



BPS Status Report

Designed and Const
2 BPS prototypes [IFIC]
(with PCB electronics containing sensing transformers)




2nd CTF3 Committee


2

Series of 15 start in October!

CTF3 Collaboration




CTF3 – Collaborations



R.Corsini

CLIC / CTF3 collaboration




27 collaborating institutes

Ankara University (Turkey)
Berlin Tech. Univ. (Germany)
BINP (Russia)
CERN
CIEMAT (Spain)
Finnish Industry (Finland)
Gazi Universities (Turkey)

IRFU/Saclay (France)
Helsinki Institute of Physics (Finland)
IAP (Russia)
IAP NASU (Ukraine)
Instituto de Fisica Corpuscular (Spain)
INFN / LNF (Italy)
J.Adams Institute, (UK)

JASRI (Japan)
JINR (Russia)
JLAB (USA)
KEK (Japan)
LAL/Orsay (France)
LAPP/ESIA (France)
LLNL/LBL (USA)
NCP (Pakistan)
North-West. Univ. Illinois (USA)


PSI (Switzerland),
Polytech. University of Catalonia (Spain)
RAL (England)
RRCAT-Indore (India)
Royal Holloway, Univ. London, (UK)
SLAC (USA)
Svedberg Laboratory (Sweden)
University of Oslo
Uppsala University (Sweden)



Goals & milestones 2008 run

- 1st run (April - June)
 - Injector & Linac: establish stable & documented working point, automatic beam steering & steering algorithm studies, diagnostics consolidation, stability studies, EUROTev BPMs
 - Delay Loop: complete beam optics measurements (dispersion, orbit, kick measurements, matching), re-establish combination
 - TL1 & combiner ring: complete optics studies (dispersion, closed orbit correction, matching, tunes, kick measurements, quad displacement evaluation), tune and β function dependence of vertical instability, factor four combination with DL bypass (≥ 10 A)
 - DL, TL1 & CR: factor 8 combination (≥ 15 A)
- 2nd run (July - September)
 - Complete DL + CR, new RF deflectors (20 A ?)
 - TL2 commissioning
 - First CALIFES commissioning
 - TBTS commissioning (no PETS)
- 3rd run (September - December)
 - Complete above program
 - Coherent Diffraction Radiation tests
 - TBTS, PETS running in

CDR Experiment



Coherent Diffraction Radiation experiment

Maximilian Micheler, Grahame Blair, Stewart Boogert, Pavel Karataev
John Adams Institute at Royal Holloway


David Howell
John Adams Institute at Oxford University

Nicolas Chritin, Roberto Corsini, Thibaut Lefevre, Patrick Lelong
CERN

We also would like to acknowledge help of Dr. V. Antonov for target manufacturing and J. Taylor for the workshop efforts


June 19, 2008

CDR Experiment



Basic Principle:

- Diffraction radiation (DR) appears when a charged particle moves in the vicinity of a medium
- Impact parameter, h , is the shortest distance between the target and the particle trajectory








Photo Injector



smaller emittance, faster phase coding, no “satellite bunches”




CERN

Cs₂Te photo cathode
3% QE
40 hours life time
pulse train: 1.5 μ s,
charge per bunch: 2.33 nC
bunch spacing 0.67 ns
number of bunches: 2332

RAL




diode pumped
Nd:YLF laser
10 μ J IR / bunch
0.37 μ J UV on
cathode /bunch



RF gun installed.

**Laser: needs to be finished , new diagnostics available,
➔ much more optimistic now**

Status of the PHIN photoinjector




PHIN-2 gun brazed at LAL – tested o.k. -
delivery of PHIN-2 gun from LAL to CERN: 20 May
preparation for bake-out, installation + assembly
(with help from LAL – MERCI!), waveguides, etc.

? ready in September ? – **yes !**

RF conditioning:
start in October shutdown


(klystron shared with
Combiner Ring deflectors)




PHIN photo injector prototype



Within the framework of second Joint Research Activity PHIN of the European CARE program a new photo injector for CTF3 drive beam has been designed and being constructed.



RF frequency (GHz)	2.99855
RF Power (MW)	30
Beam Energy (MeV)	5-6
Beam Current (A)	3.51
Charge/bunch(nC)	2.33
Bunch lenght (ps)	10
Energy Spread (%)	$<2 \times 10^{-6}$
Normalized emittance ()	<25
Pulse train duration (μs)	1.518



2-1/2 rf gun

References:




- 1) Steffen Doeber, Integrati of the PHIN rf gun into the CLIC Test Facility, proceedings of EPAC 2006, Edinburgh, Scotland
- 2) R. Roux, et al, Design of a RF gun, CARE Note-2004-034-PHIN
- 3) J. N. Ross, Feasibility study for the PHIN photo injector, CARE Note-2004-034-PHIN

Next steps: Tail clipper



change length of bunch train going into CLEX
with fast transverse kickers – collimator/dump

Strip-line kickers from CIEMAT,

Collimator / dump (CERN):
serves also as safety element to inhibit beam into CLEX



CTF3 KICKER STATUS (CIEMAT)




- Design is already finished.
- Practically all the materials & components have been acquired.
- Electrodes have been manufactured
- Test devices have been received or will be soon at CIEMAT (Including the pulsed power supply).
- Still waiting for the reception of some more CERAMASEAL feedthroughs.
- Delivery will depend on the reception of the feedthroughs and the ability to achieve 10^{-8} mbar




Tentative long-term CLIC scenario

Shortest, Success Oriented, Technically Limited Schedule

Technology evaluation and Physics assessment based on LHC results
for a possible decision on Linear Collider funding with staged
construction starting with the lowest energy required by Physics



Conclusion II



Well advanced programme
Consistent parameter set

Technical programme is on track

- **CTF3 on schedule**

full beam loading

bunch phase coding and Delay Loop operation

First results on recombination on Combiner Ring

**Progress is only possible because we have a very prosperous
collaboration between 27 international institutes**